

• PARK ROADS  
 \*\* OAK RIDGE CEMETERY INTERNAL ROADS  
 CONTRACT NO. 72774

BITUMINOUS RESURFACING SCHEDULE				
LOCATION	BIT. MATERIALS ( P.C. ) ( TON )	AGG ( P.C. ) ( TON )	LEVELING BINDER ( TON )	BIT. CONC. SURF. CSE ( TON )
<u>HONOR ROAD</u> STA 60+15.99 TO 64+24.29	1.0	3.0	65.0	110.0
TOTAL =	1.0	3.0	65.0	110.0

P. C. C. SIDEWALK 4"		
LOCATION		QUANTITY ( SQ FT )
<u>VIETNAM VETERANS MEMORIAL PARKING LOT</u> STA 10+45.13 TO STA 11+11.34	LT	381.2
STA 16+23.49 TO STA 16+90.27	LT	383.0
TOTAL =		764

INLET ADJUSTMENTS	
LOCATION	QUANTITY ( EACH )
<u>LINCOLN MEMORIAL DRIVE</u> STA 10+66.48 - 24.78' RT	1
STA 10+75.24 - 45.11' LT	1
STA 10+95.71 - 26.46' LT	1
STA 10+96.10 - 24.12' RT	1
STA 14+28.29 - 24.44' RT	1
STA 14+28.81 - 24.12' LT	1
STA 15+14.63 - 41.24' LT	1
STA 15+34.53 - 40.33' LT	1
<u>HONOR ROAD</u> STA 62+84.36 - 9.62' LT	1
STA 62+85.87 - 10.37' RT	1
TOTAL =	10

BOLLARDS	
LOCATION	QUANTITY ( EACH )
<u>VIETNAM VETERANS MEMORIAL</u> STA 10+27.51 - 36.50' LT	1
STA 10+27.51 - 52.54' LT	1
STA 10+33.08 - 28.99' LT	1
STA 10+33.08 - 60.06' LT	1
STA 10+41.38 - 24.67' LT	1
STA 10+41.38 - 64.37' LT	1
TOTAL =	6

ESTIMATED QUANTITIES		
PAY ITEMS	UNIT	TOTAL QUANTITY
CLASS C PATCHES, TYPE I, 8"	SQ YD	130
CLASS C PATCHES, TYPE II, 8"	SQ YD	85
CLASS C PATCHES, TYPE III, 8"	SQ YD	52
CLASS C PATCHES, TYPE IV, 8"	SQ YD	215

FURNISH AND INSTALL TRAFFIC COUNTER	
LOCATION	QUANTITY ( EACH )
<u>VIETNAM VETERANS MEMORIAL PARKING LOT</u> STA 10+62.19	1
STA 16+74.01	1
TOTAL =	2

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
**SCHEDULE OF QUANTITIES**  
 SCALE: VERT. \_\_\_\_\_  
 HORIZ. \_\_\_\_\_  
 DATE \_\_\_\_\_  
 DRAWN BY \_\_\_\_\_  
 CHECKED BY \_\_\_\_\_

PLOT DATE = 11/4/2004  
 FILE NAME = S04011  
 SCALE = 1/8" = 1'-0"  
 REFERENCE = 09REF