

SEEDING SCHEDULE						
LOCATION:	SEEDING CLASS 2 (ACRE)	AGRICUL. LIME (TON)	NITROGEN FERT. (LBS)	PHOS. FERT. (LBS)	POT. FERT. (LBS)	MULCH METHOD 2 (ACRE)
<u>LINCOLN MEMORIAL DRIVE</u>						
LT STA 10+40.60 TO STA 15+77.10	0.03	0.06	3	3	3	0.03
RT STA 10+40.60 TO STA 15+77.10	0.02	0.04	2	2	2	0.02
<u>HONOR ROAD</u>						
LT STA 60+15.99 TO STA 64+24.29	0.02	0.04	2	2	2	0.02
RT STA 60+15.99 TO STA 64+24.29	0.02	0.04	2	2	2	0.02
<u>VIETNAM VETERANS MEMORIAL PARKING LOT</u>						
LT STA 10+60.13 TO STA 16+73.60	0.02	0.04	2	2	2	0.02
RT STA 10+23.00 TO STA 17+11.32	0.04	0.08	4	4	4	0.04
<u>LOW AREA OFF OF V.V.M.</u>						
STA 21+77.85	0.10	0.20	9	9	9	0.10
TOTAL =	0.3	0.5	23	23	23	0.3

EARTHWORK SCHEDULE					
LOCATION (STATION TO STATION)	EARTH EXCAV. (CU YD)	EMBANK. (CU YD)	EMBANK. X 1.25 (CU YD)	WASTE (BOR.) (CU YD)	ACC. W / (B) (CU YD)
<u>LINCOLN MEMORIAL DRIVE</u>					
STA 10+40.60 TO STA 15+77.11	361	0	0	361	361
<u>VIETNAM VETERANS MEM. PARKING</u>					
STA 10+23.00 TO STA 17+11.32	383	0	0	383	383
<u>LOW SPOT</u>					
STA 21+60.00 TO STA 22+00.00	0	9	11	(11)	-11
TOTAL =	744	9	11	733	733
NOTES: THE ABOVE SCHEDULE CONSIDERS A SHRINKAGE OF 20% TO DETERMINE FACTOR = 1 / (1.0 - 0.2) = 1.25.					

REVISIONS	
NAME	DATE