

PAVEMENT MARKING SCHEDULE									
STATION	TYPE	PAINT PVT MK LINE 5"		THERM PVT MK LINE 5"		THERM PVT MK LINE 12"	PREF PVT MK LINE 6"	PREF PVT MK LTRS & SYMB	PREF PVT MK LINE 24"
		WHITE	YELLOW	WHITE	YELLOW	YELLOW	YELLOW	YELLOW	WHITE
LT & RT 464+40 TO 478+82	EDGE LINE	2,884 FT							
LT & RT 464+40 TO 467+88	NO PASS		696 FT						
RT 467+88 TO 470+32	NO PASS		244 FT						
LT 467+88 TO 470+32	SKIP DASH		61 FT						
470+32 TO 478+82	SKIP DASH		213 FT						
478+78 TO 489+57	SKIP DASH		270 FT						
LT & RT 478+78 TO 498+80	EDGE LINE	4,004 FT							
LT 489+57 TO 498+52	SKIP DASH		224 FT						
RT 489+57 TO 498+52	NO PASS		895 FT						
LT & RT 498+52 TO 498+80	NO PASS		56 FT						
LT & RT 1098+25 TO 1097+08	EDGE LINE	234 FT							
LT & RT 1098+25 TO 1097+08	NO PASS		234 FT						
LT & RT 1097+08 TO 1084+79	EDGE LINE			2,458 FT					
1097+08 TO 1084+79	MEDIAN LINE				3,800 FT				
1097+08 TO 1084+79	DIAGONAL					143 FT			
1097+08 TO 1084+79	LANE LINE						109 FT		
1097+08 TO 1084+79	ARROW							33 SQ FT	
1097+08 TO 1084+79	STOP BAR								11 FT
LT & RT 1084+79 TO 1029+69	EDGE LINE	11,020 FT							
LT & RT 1084+79 TO 1083+27	NO PASS		304 FT						
LT 1083+27 TO 1077+20	NO PASS		607 FT						
RT 1083+27 TO 1077+20	SKIP DASH		152 FT						
1077+20 TO 1046+14	SKIP DASH		776 FT						
LT 1046+14 TO 1035+53	SKIP DASH		264 FT						
RT 1046+14 TO 1035+53	NO PASS		1,061 FT						
LT & RT 1035+53 TO 1029+69	NO PASS		1,168 FT						
DEDUCT FOR SIDEROADS		(80 FT)		(240 FT)					
TOTALS		17,828 FT	7,225 FT	2,218 FT	3,800 FT	143 FT	109 FT	33 SQ FT	11 FT

NOTES:

STATIONS ARE APPROXIMATE.

SEE SHEET 9-11 FOR MARKING DETAILS FOR STA. 1097+08 TO 1084+79.

SCHEDULES
 FAP 757 (OLD US 36)
 SECTION (21X, 22)RS-7
 SCOTT COUNTY