steffenmk
10/26/2004
c:\projects\74048d\d02904pa.dgn
SOQ

FAP RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
821	*	JEFFERSON	11	3
FED. ROAD DIST. NO. 7	ILLINOIS	FED. AID PROJECT NO.		

CONTRACT NO. 74048
* (13-2)RS-2,13ZRS-3

SUMMARY OF QUANTITIES

	CODE NO	ITEM	UNIT	TOTAL QUANTITIES (URBAN 80% FED. 20% STATE)	CONSTRUCTION TYPE CODE I000-2A		
	40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	4865	4865		
	40600895	CONSTRUCTING TEST STRIP	EACH	1	1		
	44000030	BITUMINOUS SURFACE REMOVAL (VARIABLE DEPTH)	SQ YD	48652	48652		
	44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	10	10		
	60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	10	10		
	66700205	PERMANENT SURVEY MARKERS, TYPE I	EACH	9	9		
	67000500	ENGINEER'S FIELD OFFICE, TYPE B	CAL MO	3	3		
	67100100	MOBILIZATION	L SUM	1	1		
	70102632	TRAFFIC CONTROL AND PROTECTION, STANDARD 701602	L SUM	1	1		
	70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1		
	70300100	SHORT-TERM PAVEMENT MARKING	FOOT	5185	5185		
	70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1730	1730		
*	78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	982.8	982.8		
*	78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	18650	18650		
*	78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	3250	3250		
*	78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	620	620		
*	78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	490	490		
	78003130	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 6"	FOOT	3260	3260		
*	78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	530	530		
	78300400	THERMOPLASTIC PAVEMENT MARKING REMOVAL	SQ FT	170	170		
*	88600100	DETECTOR LOOP, TYPE I	FOOT	1960	1960		
	X4066538	POLYMERIZED BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "E", N90	TON	4768	4768		

*SPECIALTY ITEMS

REVISIONS NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: VERT. HORIZ.
DATE
DRAWN BY
CHECKED BY