

ILLINOIS DEPARTMENT OF TRANSPORTATION			URBAN TOTAL QUANTITIES	1000-2A	1000-2A	Y031-1F		X020-2A	Y030-1E		
CODE NO	ITEM	UNIT		4 LANE 100% STATE	2 LANE 100% STATE	TRAFFIC SIGNALS IL 162	PARKING LANES 50% STATE	BOX CULVERT SN 060-0403	HIGHWAY LIGHTING		
40600990	TEMPORARY RAMP	SQ YD	550	418					132		
40800020	BITUMINOUS MATERIALS (PRIME COAT)	TON	6.2	1.5					4.7		
40800030	AGGREGATE (PRIME COAT)	TON	13.2	3.8					9.4		
40800040	INCIDENTAL BITUMINOUS SURFACING	TON	1036	269					767		
42000300	PORTLAND CEMENT CONCRETE PAVEMENT 8"	SQ YD	1156	1156							
42001300	PROTECTIVE COAT	SQ YD	6905	4948					1957		
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SQ YD	188	50					138		
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	3603	2791					812		
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SQ FT	3952	2377					1575		
44000004	BITUMINOUS SURFACE REMOVAL 1"	SQ YD	1877						1877		
44000006	BITUMINOUS SURFACE REMOVAL 1 1/2"	SQ YD	3975						3975		
44000007	BITUMINOUS SURFACE REMOVAL 2"	SQ YD	1075						1075		
44000030	BITUMINOUS SURFACE REMOVAL (VARIABLE DEPTH)	SQ YD	16,082	9676					6406		
44000100	PAVEMENT REMOVAL	SQ YD	1075	1075							
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	9954	6240					3714		
44000400	GUTTER REMOVAL	FOOT	3985						3985		
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	45						45		
44000600	SIDEWALK REMOVAL	SQ FT	2453	895					1558		
44003100	MEDIAN REMOVAL	SQ FT	72						72		
44004250	PAVED SHOULDER REMOVAL	SQ YD	3083	2826					257		
44200144	PAVEMENT PATCHING, TYPE II, 12 INCH	SQ YD	676	322					354		
44200148	PAVEMENT PATCHING, TYPE III, 12 INCH	SQ YD	143	62					81		
44200150	PAVEMENT PATCHING, TYPE IV, 12 INCH	SQ YD	175						175		
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	24408	22248					2160		
48100500	AGGREGATE SHOULDERS, TYPE A 6"	SQ YD	7687						7687		
48202600	BITUMINOUS SHOULDERS SUPERPAVE 8"	SQ YD	10014						10014		
50100400	REMOVAL OF EXISTING STRUCTURES NO. 2	EACH	1						1		
50100600	REMOVAL OF EXISTING STRUCTURES NO. 4	EACH	1						1		
50100700	REMOVAL OF EXISTING STRUCTURES NO. 5	EACH	1						1		
50100800	REMOVAL OF EXISTING STRUCTURES NO. 6	EACH	1						1		
50104400	CONCRETE HEADWALL REMOVAL	EACH	5						5		