

ILLINOIS DEPARTMENT OF TRANSPORTATION			URBAN TOTAL QUANTITIES	I000-2A	I000-2A	Y031-1F		X020-2A	Y030-1E	
SUMMARY OF QUANTITIES				4 LANE	2 LANE	TRAFFIC SIGNALS	PARKING LANES	BOX CULVERT	HIGHWAY	
CODE NO	ITEM	UNIT				IL 162 @	50% STATE	SN 060-0403	LIGHTING	
						100% STATE	100% STATE	RIGGIN RD. 50% CITY	100% STATE	100% STATE
						90% STATE / 10% CITY	Y025			
81013000	CONDUIT IN TRENCH, 4" DIA., PVC	FOOT	10			10				
81018500	CONDUIT PUSHED, 2" DIA., GALVANIZED STEEL	FOOT	201			111			90	
81018800	CONDUIT PUSHED, 3 1/2" DIA., GALVANIZED STEEL	FOOT	214			214				
81019000	CONDUIT PUSHED, 5" DIA., GALVANIZED STEEL	FOOT	122			122				
81400400	CONCRETE HANDHOLE	EACH	4			4				
81400600	CONCRETE DOUBLE HANDHOLE	EACH	2			2				
81500200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	2977			812			2165	
81600315	UNIT DUCT, 2*6XLP, 1*6 XLP GROUND 1" POLYETHYLENE	FOOT	2205						2205	
83600200	LIGHT POLE FOUNDATION, 24" DIAMETER	FOOT	25						25	
85700200	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET	EACH	1			1				
87301215	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C	FOOT	1364			1364				
87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	1422			1422				
87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	1900			1900				
87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	1004			1004				
87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	4110			4110				
87301805	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 2 C	FOOT	31			31				
<del>87502690</del>	<del>TRAFFIC SIGNAL POST, ALUMINUM 15 FT.</del>	<del>EACH</del>	<del>4</del>			<del>4</del>				
87502690	TRAFFIC SIGNAL POST, ALUMINUM 15 FT.	EACH	4			4				
87700210	STEEL MAST ARM ASSEMBLY AND POLE, 34 FT.	EACH	2			2				
87700230	STEEL MAST ARM ASSEMBLY AND POLE, 38 FT.	EACH	2			2				
87800100	CONCRETE FOUNDATION, TYPE A	FOOT	12			12				
87800200	CONCRETE FOUNDATION, TYPE D	FOOT	3.5			3.5				
87800400	CONCRETE FOUNDATION, TYPE E 30-INCH DIAMETER	FOOT	44			44				
88200100	TRAFFIC SIGNAL BACKPLATE	EACH	10			10				
88500100	INDUCTIVE LOOP DETECTOR	EACH	15			15				
88600100	DETECTOR LOOP, TYPE I	FOOT	2066			2066				
88800100	PEDESTRIAN PUSH-BUTTON	EACH	8			8				
89000100	TEMPORARY TRAFFIC SIGNAL INSTALLATION	EACH	1			1				
89502300	REMOVE ELECTRIC CABLE FROM CONDUIT	FOOT	115						115	

\* SPECIALTY ITEMS

Rev.