FAP ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO
586	60R-2,37R-1	MADISON	502	31
STA.		TO STA.		
CONTRACT NO: 76301				

STORM SEWER AND PIPE CULVERT SCHEDULE

POINT	SLOPE	STORM SEWER CLASS A (FOOT)														PIPE CULVERTS CLASS A (FOOT)		PIPE CULVERTS, CLASS A, (FOOT)					PIPE CULVERTS, CLASS D, (FOOT)							TRENCH BACKFILL (CU YD)	STORM SEWERS WATER MAIN QUALITY PIPE (FOOT)					STORM SEWER (WATER MAIN REQUIREMENTS) (FOOT)			
		12"		15"		18"	24"	30"	36"	42"		48"	60"		66"	15"	18"	12"	15"	18"	15"	60"	12"	15"	18"	21"	24"	30"	60"		12"		15"	24"	66"	18"	21"	36"	42"
		TY 1	TY 2	TY 1	TY 2	TY 2	TY 2	TY 2	TY 2	TY 2	TY 3	TY 3	TY 2	TY 3	TY 2			TYPE 1			TYPE 2		TYPE 1								TY 1	TY2	TY 1	TY2	TY2				
19L - 10L	0.80%																													2.3	54								
19L - 29R	1.00%	66																												17.3									
29R - 31R	-0.87%																													240.0								216	
31R - 32R	-0.41%																													189.4									146
31R - 62R	9.97%																													3.0	18								
32R - 33R	-0.45%									106																				119.4									
33R - 34R	-0.50%									187																				197.3									
20L - 31R	1.00%	68																												42.9									
21L - 22L	-0.50%	79																												7.5									
22L - 23L	-0.50%	140																												15.8									
23L - 24L	-0.50%			85																										12.1									
24L - 25L	-0.50%			8																										1.5									
25L - 35R	1.00%				81																									69.9									
34R - 35R	0.50%									5																				15.2									
35R - 61R	-1.04%										243																			542.6									
61R - 36R	1.04%										147																			445.4									
36R - 38R	-0.55%											134																		439.9									
26L - 27L	5.00%																													3.1	29								
26L - 36R	1.00%				67																									84.2									
36R - 37R	1.00%	10																												3.6									
38R - 39R	-0.60%											116																		371.1									
39R - 40R	5.40%	16																												3.1									
39R - 41R	-0.69%											136																		444.1									
41R - 42R	-1.88%													100																380.5									
42R - 43R	-0.26%													164																511.3									
28L - 29L	1.00%						25																							0.0									
43R - 44R	-0.53%													152																347.3									
44R - 45R	-1.37%												68																	145.7									
EOP - 44R	0.50%																													55.8				95					
31L - 32L	2.90%																													0.0	12								
32L - 48R	2.90%	46																												31.0									
45R - 47R	-0.29%														260															500.8									
47R - 48R	-0.44%														123															185.3									
48R - 49R	-0.24%														109															179.9									
49R - 50R	-0.25%														101															174.2									
50R - 52R	-0.26%														128															193.0									
52R - 53R	-0.30%														81															109.7									
53R - 54R	-0.30%														5															12.4									
54R - 55R	-0.30%														77															110.4									
55R - 56R	-0.28%																													88.0					61				
56R - 58R	1.00%																													25.4	35								
55R - 59R	10.00%	17																												1.1									

STORM SEWER AND PIPE CULVERT SCHEDULE CONTINUED ON NEXT SHEET

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

STORM SEWER & PIPE CULVERT SCHEDULE

FAP ROUTE 586 (IL 162)
SECTION 60R-2,37R-1
MADISON COUNTY

DRAWN BY:

PLOT DATE: Wednesday December 01, 2004 @ 1:56:10 PM

PLAN
NOTE BOOK NO. ____
SURVEYED
PLOTTED
ALIGNMENT CHECKED
R/L OF WAY CHECKED
CADD FILE NAME
BY
DATE

12/1/2004
Wednesday December 01, 2004 @ 1:56:10 PM
cr:\pw-gates\ved80799\plan\ved80799sch08.dgn LV=1:63