

SUMMARY OF QUANTITIES

FILE NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
255	60-6-ITS	MADISON	11	2
STA.		TO STA.		
CONTRACT NO.: 76799				

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE YO31-1F			
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	FED-90% STATE-10%		
67100100	MOBILIZATION	L SUM	1	1		
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1		
70103800	TRAFFIC CONTROL (SPECIAL)	L SUM	1	1		
* 72000100	SIGN PANEL - TYPE 1	SQ FT	13	13		
* 72400100	REMOVE SIGN PANEL ASSEMBLY - TYPE A	EACH	1	1		
* 72400310	REMOVE SIGN PANEL - TYPE 1	SQ FT	13.5	13.5		
* 72400710	RELOCATE SIGN PANEL - TYPE 1	SQ FT	3	3		
* 73000100	WOOD SIGN SUPPORT	FOOT	13	13		
* 78008270	POLYUREA PAVEMENT MARKING TYPE I - LINE 24"	FOOT	100	100		
78300100	PAVEMENT MARKING REMOVAL	SQ FT	72	72		
80300100	LOCATING UNDERGROUND CABLE	FOOT	660	660		
80500100	SERVICE INSTALLATION, TYPE A	EACH	1	1		
81012300	CONDUIT IN TRENCH, 1" DIA., PVC	FOOT	779	779		
81012500	CONDUIT IN TRENCH, 1 1/2" DIA., PVC	FOOT	952	952		
81012600	CONDUIT IN TRENCH, 2" DIA., PVC	FOOT	153	153		
81012700	CONDUIT IN TRENCH, 2 1/2" DIA., PVC	FOOT	170	170		
81012800	CONDUIT IN TRENCH, 3" DIA., PVC	FOOT	15	15		
81013000	CONDUIT IN TRENCH, 4" DIA., PVC	FOOT	7	7		
81018200	CONDUIT PUSHED, 1" DIA., GALVANIZED STEEL	FOOT	70	70		
81018600	CONDUIT PUSHED, 2 1/2" DIA., GALVANIZED STEEL	FOOT	120	120		
81018700	CONDUIT PUSHED, 3" DIA., GALVANIZED STEEL	FOOT	85	85		
81400400	CONCRETE HANDHOLE	EACH	8	8		
81400600	CONCRETE DOUBLE HANDHOLE	EACH	1	1		
81500200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	1951	1951		
81500205	TRENCH AND BACKFILL FOR ELECTRICAL WORK (SPECIAL)	FOOT	49	49		
85700200	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET	EACH	1	1		
86000100	MASTER CONTROLLER	EACH	1	1		
86400100	TRANSCEIVER - FIBER OPTIC	EACH	2	2		
87100105	FIBER OPTIC CABLE IN CONDUIT, NO. 62.5/125, 4F	FOOT	1970	1970		
87301215	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C	FOOT	215	215		
87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	2040	2040		
87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	265	265		

*SPECIALTY ITEMS

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE YO31-1F			
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	FED-90% STATE-10%		
87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	2417	2417		
87301805	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 2 C	FOOT	35	35		
87502680	TRAFFIC SIGNAL POST, ALUMINUM 14 FT.	EACH	1	1		
87700230	STEEL MAST ARM ASSEMBLY AND POLE, 38 FT.	EACH	1	1		
87700240	STEEL MAST ARM ASSEMBLY AND POLE, 40 FT.	EACH	1	1		
87700260	STEEL MAST ARM ASSEMBLY AND POLE, 44 FT.	EACH	1	1		
87800100	CONCRETE FOUNDATION, TYPE A	FOOT	3	3		
87800200	CONCRETE FOUNDATION, TYPE D	FOOT	3.5	3.5		
87800415	CONCRETE FOUNDATION, TYPE E 36-INCH DIAMETER	FOOT	37	37		
87900200	DRILL EXISTING HANDHOLE	EACH	1	1		
88200300	TRAFFIC SIGNAL BACKPLATE, PLASTIC	EACH	6	6		
88500100	INDUCTIVE LOOP DETECTOR	EACH	10	10		
88600100	DETECTOR LOOP, TYPE I	FOOT	1266	1266		
89502200	MODIFY EXISTING CONTROLLER	EACH	1	1		
89502350	REMOVE AND REINSTALL ELECTRIC CABLE FROM CONDUIT	FOOT	2047	2047		
X0322925	ELECTRIC CABLE IN CONDUIT, TRACER, NO. 14 1C	FOOT	1970	1970		
X7015000	CHANGEABLE MESSAGE SIGN	CAL MO	1	1		
X8801300	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 3-SECTION, BRACKET MOUNTED	EACH	4	4		
X8801310	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 3-SECTION, MAST ARM MOUNTED	EACH	5	5		
X8801395	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 5-SECTION, BRACKET MOUNTED	EACH	1	1		
X8801400	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 5-SECTION, MAST ARM MOUNTED	EACH	1	1		