

SCHEDULE OF QUANTITIES

FAS ROUTE NO	SEC	COUNTY	TOTAL SHEETS	SHEET NO
-	*	LEE	23	4

ILLINOIS PROJECT TE-D2(115)

* 01-P4000-00-BT

20100110 TREE REMOVAL (6 TO 15 UNITS DIAMETER)		
LOCATION	UNITS	
LT. STA. 109+34	14	
RT. STA. 119+75	12	
TOTAL	26	
20100210 TREE REMOVAL (OVER 15 UNITS DIAMETER)		
LOCATION	UNITS	
RT. STA. 109+71	30	
RT. STA. 110+04	16	
RT. STA. 110+04	16	
RT. STA. 110+04	16	
RT. STA. 120+87	26	
TOTAL	120	
25000900 SEEDING, CLASS 1, SPECIAL		
LOCATION	ACRES	
LT. STA. 100+00 - LT. STA. 107+15.1	0.0375	
RT. STA. 100+00 - RT. STA. 107+15.1	0.0349	
LT. STA. 108+62.5 - LT. STA. 111+60.7	0.0455	
RT. STA. 108+62.5 - RT. STA. 111+60.7	0.0582	
RT. STA. 119+30 - RT. STA. 121+30	0.0571	
LT. STA. 119+95 - LT. STA. 121+31	0.0242	
TOTAL	0.2574	
28000400 PERIMETER EROSION BARRIER		
LOCATION	FOOT	
RT. STA. 105+00 - RT. STA. 106+00	99	
LT. STA. 105+49 - LT. STA. 107+15	168	
RT. STA. 109+22 - RT. STA. 110+67	150	
LT. STA. 108+31 - LT. STA. 109+80	150	
LT. & RT. STA. 119+50	75	
TOTAL	642	
28100109 STONE RIPRAP, CLASS A5		
LOCATION	SQ. YD.	
RT. STA. 106+00 - RT. STA. 106+98	99	
RT. STA. 108+35 - RT. STA. 108+78	24	
TOTAL	123	
28200100 FILTER FABRIC FOR USE WITH RIPRAP		
LOCATION	SQ. YD.	
RT. STA. 106+00 - RT. STA. 106+98	99	
RT. STA. 108+35 - RT. STA. 108+78	24	
TOTAL	123	

35101400 AGGREGATE BASE COURSE, TYPE B		
LOCATION	TON	
STA. 100+00 - STA. 106+88.81	459	
LT. STA. 103+38	22	
STA. 109+16.5 - STA. 111+60.74	163	
STA. 119+64.5 - STA. 121+31	397	
TOTAL	1041	
40200800 AGGREGATE SURFACE COURSE, TYPE B		
LOCATION	TON	
UNDER PEORIA AVE. BRIDGE	225	
TOTAL	225	
40500100 BITUMINOUS MATERIALS (PRIME COAT)		
LOCATION	GALLON	
STA. 100+00 - STA. 106+88.81	322	
LT. STA. 103+38	16	
STA. 109+16.5 - STA. 111+60.74	114	
STA. 119+98 - STA. 121+31	329	
TOTAL	781	
40500300 BITUMINOUS MIXTURE COMPLETE		
LOCATION	TON	
STA. 100+00 - STA. 106+88.81	106	
LT. STA. 103+38	1	
STA. 119+65 - RT. STA. 121+32	93	
TOTAL	200	
40800040 INCIDENTAL BITUMINOUS SURFACING		
LOCATION	TON	
LT. STA. 119+52 - LT. STA. 119+65	1	
TOTAL	1	
42400200 PORTLAND CEMENT CONCRETE SIDEWALK, 5 INCH		
LOCATION	SQ. FT.	
LT. STA. 121+23	87	
RT. STA. 121+23	92	
TOTAL	179	
44000500 COMBINATION CURB & GUTTER REMOVAL		
LOCATION	FOOT	
LT. STA. 121+20	30	
RT. STA. 121+20	30	
TOTAL	60	

44000600 SIDEWALK REMOVAL		
LOCATION	SQ. FT.	
LT. STA. 120+32 TO LT. STA. 121+30	473	
RT. STA. 121+21 TO RT. STA. 121+30	118	
TOTAL	591	
51204900 STEEL SHEET PILING		
LOCATION	SQ. FT.	
RT. STA. 106+91 - RT. STA. 107+15	220	
TOTAL	220	
550A0050 STORM SEWERS, CLASS A, TYPE 1 12"		
LOCATION	FOOT	
RT. STA. 119+46 - RT. STA. 119+57.5	18	
TOTAL	18	
60242700 INLETS, SPECIAL, NO. 3		
LOCATION	EACH	
RT. STA. 119+57.5	1	
TOTAL	1	
60255500 MANHOLES TO BE ADJUSTED		
LOCATION	EACH	
RT. STA. 121+05	1	
TOTAL	1	
60400105 FRAMES, TYPE 1		
LOCATION	EACH	
RT. STA. 119+46	1	
TOTAL	1	
60603800 COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12		
LOCATION	FOOT	
LT. STA. 119+46.5 - RT. STA. 121+30.64	264	
LT. STA. 119+95 - LT. STA. 121+30.64	161	
TOTAL	425	
63200310 GUARDRAIL REMOVAL		
LOCATION	FOOT	
RT. STA. 119+58	38	
TOTAL	38	
78001100 PAINT PAVEMENT MARKING - LETTERS AND SYMBOLS		
LOCATION	SQ. FT.	
RT. STA. 120+12	2.9	
TOTAL	2.9	

78001110 PAINT PAVEMENT MARKING - LINE 4"		
LOCATION	FOOT	
RT. STA. 119+72 - RT. STA. 120+88	221	
TOTAL	221	
78001140 PAINT PAVEMENT MARKING - LINE 8"		
LOCATION	FOOT	
RT. STA. 119+82 - RT. STA. 120+08	117	
TOTAL	117	
81012600 CONDUIT IN TRENCH, 2" DIA. PVC		
LOCATION	FOOT	
LT. STA. 109+10 - LT. STA. 109+25	14	
LT. STA. 109+25 - LT. STA. 110+00	76	
LT. STA. 110+00 - LT. STA. 110+80	78	
TOTAL	168	
81400100 HANDHOLE		
LOCATION	EACH	
LT. STA. 109+10	1	
TOTAL	1	
LIGHT POLE FOUNDATION, 20" DIAMETER		
LOCATION	EACH	
LT. STA. 109+25	1	
LT. STA. 110+00	1	
LT. STA. 110+80	1	
TOTAL	3	
A2001714 TREE ACER SACCHARUM (SUGAR MAPLE), 1 3/4" CALIPER, BALLED & BURLAPPED		
LOCATION	EACH	
JOBSITE	8	
TOTAL	8	
A2007114 TREE QUERCUS RUBRA, (RED OAK) 1 3/4" CALLIPER, BALLED & BURLAPPED		
LOCATION	EACH	
JOBSITE	8	
TOTAL	8	
B2005064 TREE MALUS SNOWDRIFT (SNOWDRIFT CRAB APPLE) 5' HEIGHT, CLUMB FORM, BALLED & BURLAPPED		
LOCATION	EACH	
JOBSITE	8	
TOTAL	8	
BRICK SURFACE COURSE		
LOCATION	S.Y.	
STA. 109+16.5 - STA. 111+60.74	272	
STA. 119+64.5 - STA. 121+05.6	157	
TOTAL	429	
X0322973 REMOVE EXISTING SEA WALL		
LOCATION	FOOT	
RT. STA. 108+35 TO RT. STA. 109+16	81	
TOTAL	81	
63400305 GUARD POST, SPECIAL		
LOCATION	EACH	
STA. 100+05	2	
TOTAL	2	

EARTH WORK SCHEDULE

LOCATION	EARTH	
	EXCAVATION	EMBANKMENT
	CU. YD.	CU. YD.
STA. 100+00 - STA. 106+88	376	44
STA. 108+62 - STA. 111+51	506	17
STA. 119+65 - STA. 121+05	178	8
TOTAL	1060	69

SIGN SCHEDULE

LOCATION	M.U.T.C.D. CODE								DISMOUNT YOUR BIKE
	METAL POST TYPE A	R7-8	R7-101	R1-1	D11-1	M7-1	M4-12	CUSTOM	
FOOT	1.5 SQ FT	0.50 SQ FT	1.13 SQ FT	3.0 SQ FT	0.75 SQ FT	0.33 SQ FT	1.5 SQ FT		
STA. 100+00	2@ 10 1@ 12			1	2	1			
STA. 110+00	2@ 10				1				
STA. 119+50	1@ 12				1	1			
STA. 121+00	1@ 12			1		1			
RT. STA. 120+12	1@ 12	1	1						
RT. STA. 114+20	1@ 12			1					
TOTAL	100 FEET	1.5 SQ FT	0.50 SQ FT	3.39 SQ FT	15.0 SQ FT	1.5 SQ FT	0.33 SQ FT	1.5 SQ FT	23.72 SQ FT

WENDLER ENGINEERING SERVICES, INC.

Structural & Civil Engineers—Land Surveying—Environmental Services
Illinois Professional Design Firm No. 184-000848



698 TIMBER CREEK ROAD - P.O. BOX 486 - DIXON, IL 61021 - 815-288-2261
28 E. MARION - SUITE 3 - PRINCETON, IL 61356 - 815-879-4731
1770 WEST STATE ST. - SYCAMORE, IL 60178 - 815-895-5008
804 FREEPORT RD. - STERLING, IL 61081 - (815) 626-4428
E-MAIL: info@wendler.nu

REVISION	DATE	SURVEYED BY	JOB NO.	DRAWN BY	DESIGNED BY
			99022	BDS	
		BOOK NO.	DRAWING NAME	DRAWING DATE	
			SCHD	2/3/2004	
TITLE SCHEDULE OF QUANTITIES					
CLIENT DIXON PARK DISTRICT					

SCALE: 1"=NTS