

FAS ROUTE NO	SEC	COUNTY	TOTAL SHEETS	SHEET NO
	*	DEKALB	26	3

ILLINOIS PROJECT BHOS-037(39)

* 99-00103-01-BR

SCHEDULE OF QUANTITIES

07N - DESIGNATES COUNTY FUNDING

20100110 TREE REMOVAL (6 TO 15 UNITS DIAMETER)

LOCATION	UNIT
LT. STA. 18+09	806
LT. STA. 18+40	6
LT. STA. 17+48	4@12
TOTAL	102 UNIT

20100120 TREE REMOVAL (OVER 15 UNITS DIAMETER)

LOCATION	UNIT
07N LT. STA. 6+82	36
LT. STA. 17+31	4@16
TOTAL	100 UNIT

21101815 TOPSOIL FURNISH AND PLACE 4"

LOCATION	SQ. YD.
07N RT. STA. 4+00 - RT. STA. 5+25	163
07N LT. STA. 4+00 - RT. STA. 5+18	168
07N LT. STA. 5+48 - LT. STA. 8+20	369
07N RT. STA. 5+55 - RT. STA. 8+16	323
07N RT. STA. 8+50 - RT. STA. 11+43	485
TOTAL	1508 SQ. YD.

28000400 PERIMETER EROSION BARRIER

LOCATION	FOOT
07N LT.&RT. STA. 8+75 - LT.&RT. STA. 13+00	850
LT.&RT. STA. 13+00 - LT.&RT. STA. 24+00	1700
TOTAL	2550 FOOT

35101400 AGGREGATE BASE COURSE TYPE B

LOCATION	TON
STA. 13+00 - STA. 15+53	683
STA. 17+97 - STA. 22+50	1110
07N P.E.R. STA. 10+07	28
07N P.E.R. STA. 11+50	28
TOTAL	1849 TON

40500200 BITUMINOUS MATERIALS (PRIME COAT)

LOCATION	TON
(0.3 GAL/SQ.YD. AGGREGATES)	
(0.15 GAL/SQ.YD. PAVEMENTS)	
07N STA. 3+80 - STA. 13+00	2.07
STA. 13+00 - STA. 15+53	0.84
STA. 17+97 - STA. 24+00	1.75
TOTAL	4.66 TON

40600980 BITUMINOUS SURFACE REMOVAL - BUTT JOINT

LOCATION	SQ. YD.
07N STA. 3+80 - STA. 4+25	153
07N BYERS ST. WEST	80
07N BYERS ST. EAST	78
07N NORTH ST. WEST	95
07N NORTH ST. EAST	95
STA. 23+50 - STA. 24+00	122
TOTAL	623 SQ. YD.

42300300 PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 7 INCH

LOCATION	SQ. YD.
07N P.E.L. STA. 6+90	29
07N P.E.R. STA. 7+25	29
TOTAL	58 SQ. YD.

42400200 PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH

LOCATION	SQ. FT.
07N RT. STA. 3+97 - RT. STA. 5+27	520
07N RT. STA. 5+55 - RT. STA. 6+00	231
07N LT. STA. 5+47 - LT. STA. 8+21	1200
07N RT. STA. 7+60 - RT. STA. 8+18	279
07N RT. STA. 8+51 - RT. STA. 10+00	663
TOTAL	2893 SQ. FT.

44000600 SIDEWALK REMOVAL

LOCATION	SQ. FT.
07N RT. STA. 3+97 - RT. STA. 5+27	520
07N RT. STA. 5+51 - RT. STA. 6+00	196
07N LT. STA. 5+47 - LT. STA. 8+24	1112
07N RT. STA. 7+60 - RT. STA. 8+20	240
07N RT. STA. 8+36 - RT. STA. 10+00	638
07N RT. STA. 10+15 - RT. STA. 11+24	444
TOTAL	3150 SQ. FT.

44004500 PAVEMENT REMOVAL (SURFACE COURSE)

LOCATION	SQ. YD.
STA. 13+00 - STA. 15+53	613
STA. 17+97 - STA. 22+50	1097
TOTAL	1710 SQ. YD.

44300200 STRIP REFLECTIVE CRACK CONTROL TREATMENT

LOCATION	FOOT
07N LT. & RT. STA. 4+00 TO LT. & RT. STA. 13+00	1878
TOTAL	1878 FOOT

48101200 AGGREGATE SHOULDERS TYPE B

LOCATION	TON
07N BYERS STREET EAST	4
07N BYERS STREET WEST	4
07N NORTH STREET EAST	1
07N NORTH STREET WEST	1
07N LT. STA. 8+49 - LT. STA. 13+00	68
07N RT. STA. 8+49 - RT. STA. 13+00	57
LT. STA. 13+00 - LT. STA. 15+43	41
RT. STA. 13+00 - RT. STA. 15+70	44
LT. STA. 17+80 - LT. STA. 24+00	90
RT. STA. 18+06 - RT. STA. 24+00	92
TOTAL	402 TON

55000050 STORM SEWERS CLASS A TYPE 1, 12"

LOCATION	FOOT
07N LT. STA. 4+98 - LT. STA. 5+10	10
07N LT. STA. 5+61 - LT. STA. 5+81	20
07N LT. STA. 5+81 - LT. STA. 5+89	45
07N LT. STA. 7+85 - LT. STA. 8+10	42
07N RT. STA. 5+89 - RT. STA. 7+81	190
TOTAL	307 FOOT

55000070 STORM SEWER CLASS A TYPE 1, 18"

LOCATION	FOOT
07N RT. STA. 7+81 - RT. STA. 8+10	24
TOTAL	24 FOOT

54200217 PIPE CULVERTS CLASS D TYPE 1, 12"

LOCATION	FOOT
07N P.E.R. STA. 11+50	30
TOTAL	30 FOOT

54213447 END SECTIONS 12"

LOCATION	EACH
07N LT. STA. 4+98	1
07N RT. STA. 8+56	1
07N P.E.R. STA. 11+50	2
TOTAL	4 EACH

60242600 INLETS SPECIAL NO. 2

LOCATION	EACH
07N LT. STA. 7+85	1
07N RT. STA. 8+10	1
TOTAL	2 EACH

60236700 INLETS TYPE A TYPE 10 FRAME & GRATE

LOCATION	EACH
07N LT. STA. 5+12	1
TOTAL	1 EACH

60236700 INLETS TYPE A TYPE 8 GRATE

LOCATION	EACH
07N LT. STA. 5+81	1
07N RT. STA. 5+89	1
07N RT. STA. 7+81	1
TOTAL	3 EACH

60255500 MANHOLES TO BE ADJUSTED

LOCATION	EACH
07N 9' LT. STA. 5+22	1
07N 16' RT. STA. 5+46	1
07N 17' RT. STA. 8+24	1
07N 24' RT. STA. 8+32	1
07N 18' RT. STA. 10+82	1
TOTAL	5 EACH

60805000 COMBINATION CONCRETE CURB & GUTTER TYPE B-6.24

LOCATION	FOOT
07N RT. STA. 4+03 - RT. STA. 5+30	144
07N LT. STA. 4+03 - LT. STA. 5+20	141
07N RT. STA. 5+54 - RT. STA. 8+25	308
07N LT. STA. 5+44 - LT. STA. 8+27	313
TOTAL	906 FOOT

63000000 STEEL PLATE BEAM GUARDRAIL TYPE A

LOCATION	FOOT
LT. STA. 14+73.7 - LT. STA. 15+23.7	50
RT. STA. 14+30.7 - RT. STA. 15+55.7	125
LT. STA. 17+94.2 - LT. STA. 20+69.2	275
RT. STA. 18+26.2 - RT. STA. 21+01.2	275
TOTAL	725 FOOT

63100075 TRAFFIC BARRIER TERMINAL TYPE 5A

LOCATION	EACH
LT. STA. 15+23.7 - LT. STA. 15+36.9	1
RT. STA. 15+55.7 - RT. STA. 15+68.9	1
LT. STA. 17+80.9 - LT. STA. 17+94.2	1
RT. STA. 18+12.9 - RT. STA. 18+26.2	1
TOTAL	4 EACH

63100167 TRAFFIC BARRIER TERMINAL TYPE 1 SPECIAL (TANGENT)

LOCATION	EACH
LT. STA. 14+23.7 - LT. STA. 14+73.7	1
RT. STA. 13+80.7 - RT. STA. 14+30.7	1
LT. STA. 20+69.2 - LT. STA. 21+19.2	1
RT. STA. 21+01.2 - RT. STA. 21+51.2	1
TOTAL	4 EACH

63200305 STEEL PLATE BEAM GUARDRAIL REMOVAL

LOCATION	FOOT
LT. STA. 15+00 - LT. STA. 15+40	40
RT. STA. 15+28 - RT. STA. 15+68	40
LT. STA. 17+82 - LT. STA. 18+22	40
RT. STA. 18+10 - RT. STA. 18+50	40
TOTAL	160 FOOT

70300100 SHORT-TERM PAVEMENT MARKING

LOCATION	FOOT
07N STA. 3+80 - STA. 13+00 (DASHED CENTER-YELLOW 4")	230
STA. 13+00 - STA. 24+00 (DASHED CENTER-YELLOW 4")	275
07N LT. & RT. STA. 8+90 - LT. & RT. STA. 13+00 (EDGE-WHITE 4")	820
LT. & RT. STA. 13+00 - LT. & RT. STA. 24+00	2200
TOTAL	3525 FOOT

X4066490 BITUMINOUS CONCRETE SURFACE COURSE SUPERPAVE II-9.5I (LOW ESAL)

LOCATION	TON
07N STA. 3+80 - STA. 13+00	358
STA. 13+00 - STA. 15+53	58
STA. 17+97 - STA. 24+00	139
07N P.E.R. 4+74	8
07N P.E.R. 10+10	6
07N P.E.L. 11+50	6
P.E.L. 23+12	9
TOTAL	584 TON

X4066630 BITUMINOUS CONCRETE BINDER COURSE SUPERPAVE II-19.0I (LOW ESAL)

LOCATION	TON
07N STA. 4+25 - STA. 13+00	598
STA. 13+00 - STA. 15+53	116
STA. 17+97 - STA. 23+50	253
07N P.E.R. STA. 10+10	6
07N P.E.R. STA. 11+50	6
TOTAL	979 TON

Z0013825 CONTROLLED LOW STRENGTH MATERIAL

LOCATION	CU YD
07N LT. STA. 5+82 TO RT. STA. 5+88	20
07N LT. STA. 7+85 TO RT. STA. 8+08	21
BACKFILL BEHIND BRIDGE ABUTMENTS	44
TOTAL	85 CU. YD.

SCHEDULE OF QUANTITIES
TYPICAL SECTIONS
SECTION 99-00103-01-BR
KIRKLAND RD. (CO. HIGHWAY 29)
DEKALB COUNTY