

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO
80	*	LASALLE	460	7
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

\* (50-2)HBR, (71X)N&TS-1

← ACF →

SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE							
CODE NO.	ITEM	UNIT	URBAN TOTAL QTY	80% FED 20% STATE		CONSTRUCTION TYPE CODE			ACFM 90% FED 10% STATE		
				I 000-2A ROADWAY IL 351	J000-2A ROADWAY IL 351	Y 031-1F TRAFFIC SIGNALS 80% FED 10% STATE 10% CITY IL 351	I000-2A STATE ENTRANCE 80% FED 20% STATE IL 351	Y030-1E LIGHTING 100% CITY IL 351	I 000-2A ROADWAY I-80	J000-2A I-80	X771-2A EXIST S.N. 050-0026 PROP. SN 050-0230 I-80
550A2580	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 2 30"	FOOT	39	39							
6010060	CONCRETE HEADWALL FOR PIPE DRAINS	EACH	30							30	
60100915	PIPE DRAINS 6"	FOOT	50							50	
60100925	PIPE DRAINS 8"	FOOT	50							50	
60100945	PIPE DRAINS 12"	FOOT	187							187	
60108100	PIPE UNDERDRAINS 4" (SPECIAL)	FOOT	450							450	
60218300	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, OPEN LID	EACH	1							1	
60219000	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 8 GRATE	EACH	12	12							
60221100	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1	1							
60221700	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 8 GRATE	EACH	5	5							
60223700	MANHOLES, TYPE A, 6'-DIAMETER, TYPE 1 FRAME, OPEN LID	EACH	1							1	
60224005	MANHOLES, TYPE A, 6'-DIAMETER, TYPE 8 GRATE	EACH	1	1							
60234200	INLETS, TYPE A, TYPE 1 FRAME, OPEN LID	EACH	1							1	
60235110	INLETS, TYPE A, TYPE 1 FRAME, OPEN LID (48" DEPTH)	EACH	1							1	
60235700	INLETS, TYPE A, TYPE 3 FRAME AND GRATE	EACH	20	20							
60240220	INLETS, TYPE B, TYPE 3 FRAME AND GRATE	EACH	13	13							
60240301	INLETS, TYPE B, TYPE 8 GRATE	EACH	2	2							
60255500	MANHOLES TO BE ADJUSTED	EACH	2	2							
60260300	INLETS TO BE ADJUSTED WITH NEW TYPE 1 FRAME, OPEN LID	EACH	2							2	
60260400	INLETS TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	1	1							
60263000	INLETS TO BE RECONSTRUCTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	1	1							
60500040	REMOVING MANHOLES	EACH	2	2							
60500050	REMOVING CATCH BASINS	EACH	3							3	
60500060	REMOVING INLETS	EACH	6							6	
60500005	MANHOLES TO BE FILLED TO MAINTAIN FLOW	EACH	1							1	
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	2996	2996							
60620400	CONCRETE MEDIAN, TYPE SB-9.06	SQ FT	2220							2220	
60620600	CONCRETE MEDIAN, TYPE SB-9.06 (MODIFIED)	SQ FT	3450							3450	
60620700	CONCRETE MEDIAN, TYPE SB-9.06 (SPECIAL)	SQ FT	1974							1974	
60900315	TYPE D INLET BOX, STANDARD 609006	EACH	2							2	
60900515	CONCRETE THRUST BLOCKS	EACH	6							6	
61100500	EXPLORATION TRENCH 52" DEPTH	FOOT	200							200	
61100605	MISCELLANEOUS CONCRETE	CU YD	10							10	

\* INDICATES SPECIALTY ITEM

11/1/2004 c:\projects\ec02994\cvsrnt.dgn