

SCHEDULE OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL	CONSTRUCTION TYPE CODE		
				I000-2A	J000-2A	X271-2A
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	30250		30250	
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	2160		2160	
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	5900		5900	
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	800		800	
70300520	PAVEMENT MARKING TAPE, TYPE III 4"	FOOT	52000		52000	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	34565		34565	
70400100	TEMPORARY CONCRETE BARRIER	FOOT	6740		6740	
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	4830		4830	
* 72000100	SIGN PANEL - TYPE 1	SQ FT	99		99	
* 72000200	SIGN PANEL - TYPE 2	SQ FT	193		193	
* 72000300	SIGN PANEL - TYPE 3	SQ FT	2060		2060	
72000100	REMOVE SIGN PANEL ASSEMBLY - TYPE A	EACH	8		8	
72000200	REMOVE SIGN PANEL ASSEMBLY - TYPE B	EACH	17		17	
* 72400030	REMOVE SIGN PANEL - TYPE 3	SQ FT	2116		2116	
* 72700000	STRUCTURAL STEEL SIGN SUPPORT - BREAKAWAY	POUND	7500		7500	
72900000	METAL POST - TYPE A	FOOT	165		165	
72900000	METAL POST - TYPE B	FOOT	340		340	
73000000	WOOD SIGN SUPPORT	FOOT	115		115	
* 73300000	OVERHEAD SIGN STRUCTURE - SPAN TYPE 1-A (MAX. SPAN 4'-6")	FOOT	76		76	
* 73300000	OVERHEAD SIGN STRUCTURE WALKWAY	FOOT	88		88	
* 73400000	CONCRETE FOUNDATIONS	CU YD	16.4		16.4	
* 73400200	DRILLED SHAFT CONCRETE FOUNDATIONS	CU YD	33.6		33.6	
* 73600100	REMOVE OVERHEAD SIGN STRUCTURE - SPAN	EACH	2		2	
73700100	REMOVE GROUND-MOUNTED SIGN SUPPORT	EACH	16		16	
73700200	REMOVE CONCRETE FOUNDATION - GROUND MOUNT	EACH	16		16	
73700300	REMOVE CONCRETE FOUNDATION - OVERHEAD	EACH	4		4	
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	15747		15747	
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	1908		1908	
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	3724		3724	
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	492		492	
* 8005110	EPOXY PAVEMENT MARKING - LINE 4"	FOOT	14501		14501	
* 8005130	EPOXY PAVEMENT MARKING - LINE 6"	FOOT	250		250	
* 8005140	EPOXY PAVEMENT MARKING - LINE 8"	FOOT	2175		2175	
* 8005150	EPOXY PAVEMENT MARKING - LINE 12"	FOOT	303		303	
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	96		96	
* 78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	25		25	

* INDICATES SPECIALTY ITEM

SCHEDULE OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL	CONSTRUCTION TYPE CODE		
				I000-2A	J000-2A	X271-2A
* 78200300	PRISMATIC CURB REFLECTOR	EACH	116		116	
* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	50		50	
* 78200520	BARRIER WALL MARKERS, TYPE B	EACH	16		16	
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	6		6	
83001000	PAVEMENT MARKING REMOVAL	SQ FT	7500		7500	
83002000	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	50		50	
* 80300100	LOCATING UNDERGROUND CABLE	FOOT	500		500	
* 80400100	ELECTRIC SERVICE INSTALLATION	EACH	1		1	
* 80600200	GROUNDING ELECTRODE BELOW GRADE	EACH	25		25	
* 80800500	TEMPORARY WOOD POLE, 60 FT., CLASS 4	EACH	13		13	
* 81001000	CONDUIT IN TRENCH, 4" DIA., GALVANIZED STEEL	FOOT	20		20	
* 81008500	CONDUIT PUSHED, 2" DIA., GALVANIZED STEEL	FOOT	325		325	
* 81008700	CONDUIT PUSHED, 3" DIA., GALVANIZED STEEL	FOOT	190		190	
* 81100400	CONDUIT ATTACHED TO STRUCTURE, 2" DIA., GALVANIZED STEEL	FOOT	910		910	
* 81300510	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 12" X 8" X 4"	EACH	2		2	
* 81500200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	6755		6755	
* 81600320	UNIT DUCT, WITH 2-1/C NO. 6 AND 1/C NO. 8 GROUND, 600V (XLP-TYPE USE), 1" DIA., POLYETHYLENE	FOOT	12160		12160	
* 81700410	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 3-1/C NO. 4	FOOT	30		30	
* 82100300	LUMINAIRE, SODIUM VAPOR, 150 WATT, HIGH PRESSURE SODIUM	EACH	29		29	
* 82100400	SIGN LIGHTING LUMINAIRE, 150 WATT, HIGH PRESSURE SODIUM	EACH	5		5	
* 82500520	LIGHTING CONTROLLER TYPE CB-RCS 60AMP - 480VOLT	EACH	1		1	
* 83034000	LIGHT POLE, STEEL, 45 FT. M.H., TENON MOUNT	EACH	29		29	
* 83500385	LIGHT POLE FOUNDATION METAL, 15" BOLT CIRCLE, 8" X 6"	EACH	25		25	
* 83800600	BREAKAWAY DEVICE, COUPLING, WITH STAINLESS STEEL SCREEN	EACH	72		72	
84100110	REMOVAL OF TEMPORARY LIGHTING UNITS	EACH	13		13	
* 84200500	REMOVAL OF EXISTING LIGHTING UNIT, SALVAGE	EACH	13		13	
84200700	LIGHTING FOUNDATION REMOVAL	EACH	13		13	
* 84400105	RELOCATE EXISTING LIGHTING UNIT	EACH	13		13	
84500110	REMOVAL OF LIGHTING CONTROLLER	EACH	1		1	
84500120	REMOVAL OF ELECTRIC SERVICE INSTALLATION	EACH	1		1	
84500130	REMOVAL OF LIGHTING CONTROLLER FOUNDATION	EACH	1		1	
89502300	REMOVE ELECTRIC CABLE FROM CONDUIT	FOOT	10000		10000	

* INDICATES SPECIALTY ITEM

REVISIONS	NAME

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

F.A.I. 80 AT ILLINOIS ROUTE 351

SCALE: NONE
DATE: 09/04

DRAWN BY: JJK
CHECKED BY: MTD