F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
6108	(70X)N & TS-1	LASALLE	460	215
STA. ———		TO STA. ———		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

CONTRACT NO. 86603

DESIGN		
INT.	DATE	REASON

PLOTS & CHECKS			
INT.	DATE	NO.	REASON

CHECKS		
INT.	DATE	REASON

FILE NAME = $FILE$
PROJECT SCALE = $PROJSCALE$ DRV = $PLOTTER$
PLOT DATE = $DATE$
PLOT TIME = $TIME$
OPERATOR = $USER$

PROFILE	BY	DATE
SURVEYED		
PLOTTED		
ALIGNMENT		
REF. NOTED		
STRUCTURE		

NOTE BOOK NO. ____ STRUCTURE BOOK

SCHEDULE OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL QTY.	CONSTRUCTION CODE: I 000-1A ROADWAY	Y 031-1F TRAFFIC SIGNALS 80% FED 10% STATE 10% CITY	MAIN 2A STATE ENTRANCE 100% STATE	Y030-1E LIGHTING 100% CITY	I000 BITUMINOUS	J000 CONCRETE
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	895	895					
40600300	AGGREGATE (PRIME COAT)	TON	13	13					
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	20					20	
60098	BITUMINOUS SURFACE REMOVAL - BUTT JOINT	SQ YD	181.0	181.0					
60099	TEMPORARY RAMP	SQ YD	136.0	136.0					
80000	INCIDENTAL BITUMINOUS SURFACING	TON	133	133					
00001	PORTLAND CEMENT CONCRETE PAVEMENT 10" (JOINTED)	SQ YD	7,118.0						7,118.0
00000	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SQ YD	325.0	325.0					
00400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	487.0	397.0		90.0			
0030	BITUMINOUS SURFACE REMOVAL (VARIABLE DEPTH)	SQ YD	3,839.0	3,839.0					
0100	PAVEMENT REMOVAL	SQ YD	5,148.0	5,148.0					
0200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	1,749.0	1,749.0					
0500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	1,086	1,086					
0010	BITUMINOUS BASE COURSE REMOVAL	SQ YD	2,938.0	2,938.0					
0020	BITUMINOUS CONCRETE SHOULDER REMOVAL	SQ YD	1,346.0	1,346.0					
0020	CONCRETE MEDIAN SURFACE REMOVAL	SQ FT	4,793	4,793					
42017	CLASS D PATCHES, TYPE II, 8 INCH	SQ YD	196.9	196.9					
42017	CLASS D PATCHES, TYPE III, 8 INCH	SQ YD	17.6	17.6					
44300900	STRIP REFLECTIVE CRACK CONTROL TREATMENT SYSTEM A	FOOT	3,297	3,297					
48101200	AGGREGATE SHOULDERS, TYPE B	TON	146	146					
48202600	BITUMINOUS SHOULDERS SUPERPAVE 8"	SQ YD	230.0					230.0	
48300500	PORTLAND CEMENT CONCRETE SHOULDERS 10"	SQ YD	1,199.0						1,199.0

REVISIONS	
NAME	DATE

SCHEDULE

ILLINOIS DEPARTMENT OF TRANSPORTATION

~~SUMMARY~~ OF QUANTITIES

FAU 6108 (IL. RTE. 351)
SECTION (70X)N & TS-1
LASALLE COUNTY

SCALE: VERT. HORIZ.
DATE: 01/03/03

DRAWN BY: JETT
DESIGNED BY: KUNTZMAN
CHECKED BY: COLBROOK

GREENE & BRADFORD, INC. OF SPRINGFIELD
CONSULTING ENGINEERS
INDUSTRIAL DISTRICT
SPRINGFIELD, ILLINOIS
PROFESSIONAL DESIGN FIRM 184-001005
PROFESSIONAL & STRUCTURAL ENGINEERING CORPORATION
(217) 753-3894, (217) 753-5227 FILE MAIL - info@greenebradford.com

COMPUTER FILE NO. SUMMARY 02
PROJECT 01194.B.N
10/30/03-JLJ