F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
6108	(70X)N & TS-1	LASALLE	460	217
STA. ———		TO STA. ———		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

CONTRACT NO. 86603

DESIGN		
INT.	DATE	REASON

PLOTS & CHECKS			
INT.	DATE	NO.	REASON

CHECKS		
INT.	DATE	REASON

FILE NAME = $FILE$
PLOT SCALE = $PLOTSCALE$ DRV = $PLOTTER$
PLOT DATE = $DATE$
PLOT TIME = $TIME$
OPERATOR = $USER$

PROFILE: SURVEYED / PLOTTED / ALIGNMENT CHKD / DATA NOTED / STRUCTURE NOTATNS CHKD — BY / DATE

NOTE BOOK NO. ____

SCHEDULE OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL QTY.	CONSTRUCTION CODE: I 000-1A, ROADWAY	Y 031-1F TRAFFIC SIGNALS 80% FED 10% STATE 10% CITY	MAIN 2A STATE ENTRANCE 100% STATE	Y030-1E LIGHTING 100% CITY
550A2320	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 1 12"	FOOT	414	414			
550A2330	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 1 15"	FOOT	125	125			
550A2350	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 1 21"	FOOT	134	134			
550A2520	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 2 12"	FOOT	21	21			
550A2580	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 2 30"	FOOT	39	39			
40070	STORM SEWER REMOVAL 15"	FOOT	363	363			
602219000	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 8 GRATE	EACH	12	12			
602210 0	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1	1			
602210 00	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 8 GRATE	EACH	5	5			
602 05	MANHOLES, TYPE A, 6'-DIAMETER, TYPE 8 GRATE	EACH	1	1			
602 700	INLETS, TYPE A, TYPE 3 FRAME AND GRATE	EACH	20	20			
602 220	INLETS, TYPE B, TYPE 3 FRAME AND GRATE	EACH	13	13			
602 601	INLETS, TYPE B, TYPE 8 GRATE	EACH	2	2			
60 00	MANHOLES TO BE ADJUSTED	EACH	2	2			
60 0	INLETS TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	1	1			
6 630 0	INLETS TO BE RECONSTRUCTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	1	1			
6 5000	REMOVING MANHOLES	EACH	2	2			
60500	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	2,996	2,996			
1101001	STORM SEWERS, PROTECTED, CLASS A, 6"	FOOT	50	50			
61101009	STORM SEWERS, PROTECTED, CLASS A, 8"	FOOT	50	50			
61101011	STORM SEWERS, PROTECTED, CLASS A, 10"	FOOT	50	50			
61133100	FIELD TILE JUNCTION VAULTS, 2' DIA.	EACH	2	2			
61139900	STORM SEWERS, SPECIAL 6"	FOOT	50	50			

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE ~~SUMMARY~~ OF QUANTITIES

FAU 6108 (IL. RTE. 351)
SECTION (70X)N & TS-1
LASALLE COUNTY

SCALE: VERT.
HORIZ.
DATE: 01/03/03

DRAWN BY: JETT
DESIGNED BY: KUNTZMAN
CHECKED BY: COLBROOK

GREENE & BRADFORD, INC. OF SPRINGFIELD
CONSULTING ENGINEERS, SOIL/CONSTRUCTION TESTING, MATERIALS TESTING & TEST PROCEDURES, DESIGN FIRM NO. 184-001079
PROFESSIONAL DESIGN FIRM NO. 184-001079
PROFESSIONAL & STRUCTURAL ENGINEERING CORPORATION
1210 7th AVENUE, SPRINGFIELD, ILLINOIS 62703 (217) 789-8606, (217) 75-5277 FAX, E-MAIL - GSBSPRINGFIELD@COMCAST.NET

COMPUTER FILE NO. SUMMARY 04
PROJECT 01194.B.N
08/29/04-GSJ