F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
6108	(70X)N & TS-1	LASALLE	460	234
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

CONTRACT NO. 86603

STORM SEWER REMOVAL SCHEDULE

LOCATION	STORM SEWER REMOVAL 15"
	FOOT
MAINLINE	
STA. 255+56.90, 29.85' LT TO STA. 256+55.37, 30.13' LT	99
STA. 258+05, 30' LT TO STA. 256+55.37, 30.13' LT	151
STA. 258+05, 30' LT. TO STA. 258+05, 45' LT.	15
STA. 258+05, 30' LT TO STA. 258+53, 30' LT	45
STA. 259+06, 30' LT TO STA. 258+53, 30' LT	53
	363

STRUCTURE REMOVAL SCHEDULE

LOCATION	MANHOLES
	EACH
STATION 258+05, 30' LT	1
STATION 258+53, 30' LT	1
TOTALS	2

STRUCTURES TO BE ADJUSTED SCHEDULE

LOCATION	MANHOLES	SANITARY MANHOLES	INLETS TO BE RECONSTRUCTED WITH NEW TYPE 1 FRAME, CLOSED LID	INLETS TO BE ADJUSTED W/ NEW TYPE 1 FRAME CLOSED LID
	EACH	EACH	EACH	EACH
STATION 254+51.04, 40.60' LT	1			
STATION 255+56.90, 29.85' LT				1
STATION 256+55.37, 30.13' LT			1	
STATION 256+56.26, 17.65' LT	1			
STATION 258+52.91, 45' LT		1		
STATION 261+28.23, 45' LT		1		
TOTALS	2	2	1	1

PAVEMENT MARKING SCHEDULE

LOCATION	THERMOPLASTIC PAVEMENT MARKING-LINE 4"	THERMOPLASTIC PAVEMENT MARKING-LINE 6"	THERMOPLASTIC PAVEMENT MARKING-LINE 8"	THERMOPLASTIC PAVEMENT MARKING-LINE 12"	THERMOPLASTIC PAVEMENT MARKING-LINE 24"	THERMOPLASTIC PAVEMENT LETTERS AND SYMBOLS	EPOXY PAVEMENT MARKING-LINE 4"	EPOXY PAVEMENT MARKING-LINE 6"	EPOXY PAVEMENT MARKING-LINE 8"	EPOXY PAVEMENT MARKING-LINE 12"	EPOXY PAVEMENT MARKING-LINE 24"	EPOXY PAVEMENT LETTERS AND SYMBOLS	TEMPORARY PAVEMENT MARKING-LINE 4"	TEMPORARY PAVEMENT MARKING-LINE 6"	TEMPORARY PAVEMENT MARKING-LINE 8"	TEMPORARY PAVEMENT MARKING-LINE 12"	TEMPORARY PAVEMENT MARKING-LINE 24"	TEMPORARY PAVEMENT LETTERS AND SYMBOLS	SIGN PANEL TYPE 1	TELESCOPING STEEL SIGN SUPPORT
	FOOT	FOOT	FOOT	FOOT	FOOT	SQ. FT.	FOOT	FOOT	FOOT	FOOT	FOOT	SQ. FT.	FOOT	FOOT	FOOT	FOOT	FOOT	SQ. FT.	SQ. FT.	FOOT
MAINLINE																				
STA. 247+00 TO STA. 252+00	550	150			22								550	150			22			
STA. 252+00 TO STA. 257+00	604	120		202									604	120		202			16	18
STA. 257+00 TO STA. 261+00	1,281	80	40	953			160	20	80			15.6	1,441	100	120	953		15.6	16	18
STA. 261+00 TO STA. 266+00							2,026	100	404	864	84	67.6	2,026	100	404	864	84	67.6	27	
STA. 266+00 TO STA. 269+38							2,046	160	69	668		52.0	2,046	160	69	668		52.0	31	33
CIVIC ROAD / N. 30TH ROAD																				
STA. 43+84 TO STA. 47+00							1,897		28	713			1,897		28	713				
STA. 47+00 TO STA. 53+00	942		42	380		15.6	1,113		353		84	46.8	2,055		395	380	84	62.4		
STA. 53+00 TO STA. 54+75	1,025			342									1,025			342				
	4,402	350	82	1,877	22	15.6	7,242	280	934	2,245	168	182	11,644	630	1,016	4,122	190	197.6	90	69

DESIGN

INT.	DATE	REASON

PLOTS & CHECKS

INT.	DATE	NO.	REASON

FILE NAME = $FILE$
PLOT SCALE = $PLTSCALE$ DPV = $PLOTTER$
PLOT DATE = $DATE$
PLOT TIME = $TIME$
OPERATOR = $USER$

PROFILE — SURVEYED / PLOTTED / GRADES CHECKED / B.M. NOTED / SIGNATURE NOTATIONS OMITTED — BY — DATE

NOTE BOOK NO.

CHECKS

INT.	DATE	REASON

REVISIONS

NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

FAU 6108 (IL. RTE. 351)
SECTION (70X)N & TS-1
LASALLE COUNTY

SCALE: VERT.
HORIZ.
DATE: 08/13/04

DRAWN BY: BISHOP
DESIGNED BY: KUNTZMAN
CHECKED BY: COLBROOK

GREENE & BRADFORD, INC.
OF SPRINGFIELD
CONSULTING ENGINEERS
1011 SOUTH GRAND AVENUE EAST
SPRINGFIELD, ILLINOIS 62704
PROFESSIONAL DESIGN FIRM NO. 184-001072
PROFESSIONAL DESIGN FIRM NO. 184-000709 CORPORATION
(217) 753-8870 (FAX) 753-8871 E-MAIL: TRUSSING@GRADFORDSPRINGFIELD.COM

COMPUTER FILE NO. SCHEDULE_B-07
PROJECT 01194_B_N
08/13/04-RPB