

RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
C.H. 11	*	MENARD	44	5

PROJECT SR-565(110)  
\* 98-00047-00-RS

Location	Length (Ft.)	Temp. Pmnt. Mk. Line - 4"			Short Term Pmnt. Marking		Work Zone Pmnt. Marking		Paint Pmnt. Mk. Line - 4"		
		White (Ft.)	Yellow 30' Spc. (Ft.)	No Yellow Passing (Ft.)	White (Ft.)	Yellow (Ft.)	White (Sq. Ft.)	Yellow (Sq. Ft.)	White (Ft.)	Yellow 30' Spc. (Ft.)	No Yellow Passing (Ft.)
Sta. 5+36 to Sta. 29+10	2374										
Sta. 29+10 to Sta. 134+00	10490										
Sta. 5+36 to Sta. 134+00	12864										
Sta. 5+36 to Sta. 16+00	1064	2128	270 Rt.	1064 Lt.					2128	270 Rt.	1064 Lt.
Sta. 16+00 to Sta. 28+00	1200	2400	300						2400	300	
Sta. 28+00 to Sta. 38+00	1000	2000		2000					2000		2000
Sta. 38+00 to Sta. 56+50(Sta. 197+18)	1850	3700	460 Lt.	1850 Rt.					3700	460 Lt.	1850 Rt.
Sta. 197+18 to Sta. 210+70(Sta. 68+35)	1352	2704		2704					2704		2704
Sta. 68+35 to Sta. 76+00	765	1530	190 Lt.	765 Rt.					1530	190 Lt.	765 Rt.
Sta. 76+00 to Sta. 86+00	1000	2000		2000					2000		2000
Sta. 86+00 to Sta. 107+00	2100	4200		4200					4200		4200
Sta. 107+00 to Sta. 117+00	1000	3000	250						3000	250	
Sta. 117+00 to Sta. 134+00	1700	3400	430 Lt.	1700 Rt.					3400	430 Lt.	1700 Rt.
Sub-Total	12864	25948	2260	16391		4444	8563	6580	25948	2260	16391
Total	12864	44245			4444		15143		44245		

Note: Temporary Pavement Marking quantities are for one full application.  
Short-Term Pavement Marking quantities are for one centerline application for P.C.C. portion of the project and centerline applications for the remaining portion of the project.  
Work Zone Pavement Marking Removal is based on removal of last full application only.

**SCHEDULE PAVEMENT REMOVAL**

Location	Quantity (Sq. Yd.)
Sta. 5+35.60 to Sta. 8+15	728
Sta. 20+50 to Sta. 28+48	2039
Sta. 28+80 to Sta. 32+80.45	1024
Sta. 196+00 to Sta. 199+00	767
Sta. 208+39 (C.H. 11) to Sta. 209+80 (Ev. Moss Rd.)	360
Sta. 209+40 to Sta. 210+20	406
24" Cross Road Culverts	192
All Remaining Box Culverts	267
Total	5783

**SCHEDULE BITUMINOUS BASE COURSE SUPERPAVE 7"**

Location	Quantity (Sq. Yd.)
Sta. 29+10 to Sta. 32+80.45	929
Sta. 40+13 Lt. (Commercial Entrance)	113
Sta. 196+00 to Sta. 202+28.5	1577
Sta. 208+39 (C.H. 11) to Sta. 209+80 (Ev. Moss Rd.)	354
Sta. 209+40 to Sta. 210+20	397
24" Cross Road Culverts	192
All Remaining Box Culverts	267
Total	3829

**SCHEDULE BITUMINOUS CONCRETE BASE COURSE WIDENING 10"**

Location	Quantity (Sq. Yd.)
Sta. 96+00 to Sta. 99+00 Rt.	68
Sta. 99+75 to Sta. 103+00 Rt.	72
Total	140

**SCHEDULE BITUMINOUS MATERIALS (PRIME COAT)**

Location	Quantity (Ton)
Sta. 29+10 to Sta. 134+00 & Sideroads	4
Total	4

**SCHEDULE BITUMINOUS SHOULDERS, SUPERPAVE 10"**

Location	Quantity (Sq. Yd.)
Sta. 5+35.60 to Sta. 7+00	182
Total	182

**SCHEDULE TRAFFIC BARRIER TERMINAL, TYPE 5A**

Location	Quantity (Each)
Sta. 28+24.10 to Sta. 28+36.60 Lt.	1
Sta. 28+31.70 to Sta. 28+44.20 Rt.	1
Sta. 28+76.20 to Sta. 28+88.70 Rt.	1
Sta. 28+83.80 to Sta. 28+96.30 Lt.	1
Total	4

**SCHEDULE TRAFFIC BARRIER TERMINAL, TYPE 1 SPECIAL(TANGENT)**

Location	Quantity (Each)
Sta. 208+10 to Sta. 208+60 Rt.	1
Sta. 209+10 to Sta. 209+60 Rt.	1
Total	2

**SCHEDULE TRAFFIC BARRIER TERMINAL, TYPE 1 SPECIAL(FLARED)**

Location	Quantity (Each)
Sta. 28+06.7 to Sta. 28+44.2 Rt.	1
Sta. 28+83.8 to Sta. 29+21.3 Lt.	1
Total	2

**SCHEDULE TRAFFIC BARRIER TERMINAL, TYPE 1**

Location	Quantity (Each)
Sta. 28+15.9 to Sta. 28+51.8 Lt.	1
Sta. 28+76.2 to Sta. 29+08.3 Lt.	1
Total	2

**SCHEDULE STEEL PLATE BEAM GUARDRAIL, TYPE A**

Location	Quantity (Foot)
Sta. 208+60 to Sta. 209+10	50
Total	50

**SCHEDULE AGGREGATE SHOULDERS, TYPE A**

Location	Quantity (Ton)
Sta. 5+35.60 to Sta. 28+18 Lt. & Rt.	625
Sta. 29+10 to Sta. 58+55.93 Lt. & Rt.	885
Sta. 58+55.93 (199+24) to Sta. 68+35.25 (200+76) & Kincaid Rd.	92
Sta. 200+76 to Sta. 208+53.52 Lt. & Rt.	236
Sta. 208+53.52 to Sta. 210+05.52 (67+70.85) & Everett Moss Rd.	66
Sta. 67+70.85 to Sta. 132+29.6	1982
Sta. 132+29.6 to Sta. 134+00 & T.R. 164	56
Entrance Totals	260
Total	4182

**SCHEDULE HEAVY DUTY EXCELSIOR BLANKET**

Location	Quantity (Sq. Yd.)
Sta. 28+84 to Sta. 29+80 Lt.	112
Sta. 208+30 to Sta. 209+60 Lt.	188
Total	300

**SCHEDULE SUMMARY EROSION CONTROL ITEMS**

Location	Perimeter Erosion Barrier (Ft.)	Temp. Ditch Check (Each)	Seeding Class 2 & 7 (Acre)
Sta. 5+35.60 to Sta. 18+00	1700	9	0.9
Sta. 18+00 to Sta. 33+00	1450	3	0.9
Sta. 33+00 to Sta. 47+00	1080	4	0.7
Sta. 47+00 to Sta. 56+50 (197+18.07)	-	2	0.3
Sta. 56+50 (197+18.07) to Sta. 69+00	1985	11	0.9
Sta. 69+00 to Sta. 83+00	2800	8	1.0
Sta. 83+00 to Sta. 97+00	2780	11	1.0
Sta. 97+00 to Sta. 111+00	1610	6	0.8
Sta. 111+00 to Sta. 125+00	2780	14	0.8
Sta. 125+00 to Sta. 134+00	1460	4	0.5
Total	17645	72	7.8

**SCHEDULE FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS**

Location	Quantity (Each)
Kincaid Road	
Sta. 198+00 30' Rt.	1
Sta. 198+00 40' Rt.	1
Quarry Road - (C.H. 11)	
Sta. 7+96.44 35' Lt.	1
Sta. 7+96.44 45' Lt.	1
Sta. 8+00 25.02' Rt.	1
Sta. 8+00 40' Rt.	1
Sta. 9+10 40' Rt.	1
Sta. 9+10 45' Lt.	1
Sta. 11+48.53 45' Lt.	1
Sta. 11+48.53 40' Rt.	1
Sta. 13+89.10 45' Lt.	1
Sta. 13+89.44 35' Lt.	1
Sta. 16+84.21 40' Rt.	1
Sta. 16+83.97 26.37' Rt.	1
Sta. 202+00 30' Lt.	1
Sta. 202+00 40' Lt.	1
Sta. 208+50 40' Rt.	1
Sta. 209+84.28 50' Lt.	1
Sta. 210+00 35' Lt.	1
Sta. 210+00 35' Rt.	1
Sta. 98+84.75 35' Lt.	1
Sta. 99+74.80 30' Rt.	1
Sta. 99+85.58 30' Lt.	1
Sta. 104+45 25' Rt.	1
Sta. 104+45 30' Rt.	1
Sta. 106+71.03 25' Rt.	1
Sta. 106+71.07 30' Rt.	1
Sta. 132+00 30' Lt.	1
Sta. 132+00 30' Rt.	1
Sta. 132+77.06 99.89' Rt.	1
Everett Moss Road - (T.R. 158)	
Sta. 210+20 30' Lt.	1
Sta. 210+20 40' Lt.	1
Sta. 210+20 30' Rt.	1
Sta. 210+20 35' Rt.	1
Tilson - Sweetwater Elevator Road	
Sta. 132+81.08 99.84' Lt.	1
Total	35

**SCHEDULE CONCRETE GUTTER TYPE B**

Location	Quantity (Foot)
Sta. 104+45 to Sta. 106+72	227
Total	227

**SCHEDULE PIPE CULVERTS, CLASS D, TYPE 1, 15"**

Location	Quantity (Foot)
C.E. Sta. 22+63 Lt.	70
C.E. Sta. 27+88.5 Lt.	68
F.E. Sta. 40+13 Rt.	32
C.E. Sta. 40+13 Lt.	56
P.E. Sta. 201+12 Lt.	24
F.E. Sta. 83+60 Lt.	30
F.E. Sta. 98+10 Lt.	30
C.E. Sta. 103+22 Lt.	168
F.E. Sta. 108+39 Lt.	30
F.E. Sta. 110+35 Rt.	30
F.E. Sta. 131+00 Rt.	30
F.E. Sta. 133+65 Lt. T.R. 164	40
Total	608

**SCHEDULE STONE RIPRAP DITCH**

Location	Quantity (Ton)
Sta. 104+00 to Sta. 104+17 Rt.	9
Sta. 107+00 to Sta. 107+17 Rt.	9
Sta. 198+50 to Sta. 199+85 Lt. & Rt.	113
Sta. 199+70 (Ev. Moss Rd.) to Sta. 202+00 Rt.	81
Sta. 200+15 to Sta. 202+00 Lt.	80
Crossroad Culverts	43
Total	335

**SCHEDULE MAILBOX RELOCATION**

Location	Quantity (Each)
Sta. 8+00 Lt.	1
Sta. 8+03 Lt.	1
Sta. 29+65 Rt.	1
Sta. 98+01 Rt.	1
Sta. 98+04 Rt.	1
Sta. 105+92 Rt. (Bit. Shldr.)	1
Total	6

Each turnout per Standard BLR 24.  
The cost of mailbox relocation if necessary will not be paid for separately but will be considered incidental to the contract unit price per ton for Aggregate Shoulders, Type A.

**SCHEDULE ROCK FILL**

Location	Quantity (Ton)
Cross Road Culvert @ Sta. 9+86	122
Cross Road Culvert @ Sta. 37+22	62
Cross Road Culvert @ Sta. 202+13	106
Cross Road Culvert @ Sta. 85+65	186
Total	476

**SCHEDULE POROUS GRANULAR BACKFILL**

Location	Quantity (Cu. Yd.)
Cross Road Culvert @ Sta. 9+86	213
Cross Road Culvert @ Sta. 37+22	63
Cross Road Culvert @ Sta. 202+13	185
Cross Road Culvert @ Sta. 85+65	172
All Remaining Cross Road Culverts	240
Total	873

**SCHEDULE BARBED WIRE FENCE TO BE REMOVED AND RE-ERECTED**

Location	Quantity (Foot)
Sta. 34+03 to Sta. 34+98 Lt.	95
Total	95

**SCHEDULE CLASS SI CONCRETE (OUTLET)**

Location	Quantity (Cu. Yd.)
Sta. 104+17 to Sta. 104+45 Rt.	1.9
Sta. 106+72 to Sta. 107+00 Rt.	1.9
Entrance - Sta. 105+29 Rt.	1.9
Total	5.7

**SCHEDULE BITUMINOUS SHOULDERS SUPERPAVE 6"**

Location	Quantity (Sq. Yd.)
Sta. 104+17 to Sta. 107+00 Rt.	126
Total	126

**SCHEDULES**  
F.A.S. 565 - QUARRY ROAD (C.H. 11)  
SECTION 98-00047-00-RS  
MENARD COUNTY