

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
774	*	EFFINGHAM	344	5
FED. ROAD DIST. NO. 7		ILLINOIS	FED. AID PROJECT	
*107WRS-1, 107BY, 107BY-1 & 107B-2		CONTRACT NO. 94827		

SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE									
PAY CODE NUMBER	ITEM	UNIT	TOTAL QUANTITY	1000-2A		X071-2A		X080-2A	Y030-IE		Y031-IF	Y007	
				RURAL	URBAN	RURAL	URBAN	RURAL	URBAN	URBAN	RURAL	URBAN	
44000200	DRIVEWAY PAVEMENT REMOVAL	SO YD	2,184	1,360	824								
44000400	GUTTER REMOVAL	FOOT	1,860	200	1,660								
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	664	151	513								
44001430	BITUMINOUS SHOULDER REMOVAL	SO YD	6,082	4,622	1,460								
44002500	GUTTER OUTLET REMOVAL	EACH	3		3								
44002805	ISLAND REMOVAL	SO FT	303	303									
44003510	MEDIAN REMOVAL PARTIAL DEPTH	SO FT	1,618		1,618								
44004000	PAVED DITCH REMOVAL	FOOT	365		365								
44004510	PORTLAND CEMENT CONCRETE SHOULDER REMOVAL	SO YD	1,748	1,443	305								
48101500	AGGREGATE SHOULDERS, TYPE B 6"	SO YD	7,219	6,779	440								
48101600	AGGREGATE SHOULDERS, TYPE B 8"	SO YD	665	508	157								
48202600	BITUMINOUS SHOULDERS SUPERPAVE 8"	SO YD	27,720	24,314	3,406								
48300100	PORTLAND CEMENT CONCRETE SHOULDER, 6"	SO YD	173		173								
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1					1					
50102400	CONCRETE REMOVAL	CU YD	135.9		77.0	58.9							
50104650	SLOPE WALL REMOVAL	SO YD	1,502		642	860							
50105200	REMOVE EXISTING CULVERTS	EACH	44	38	6								
50200100	STRUCTURE EXCAVATION	CU YD	747		366	310	71						
50300100	FLOOR DRAINS	EACH	24		12	12							
50300225	CONCRETE STRUCTURES	CU YD	449.4	54.6	236.3	121.1	37.4						
50300255	CONCRETE SUPERSTRUCTURE	CU YD	1,249.8		676.2	573.6							
50300260	BRIDGE DECK GROOVING	SO YD	4,105		2,213	1,892							
50300300	PROTECTIVE COAT	SO YD	4,620		2,491	2,129							
50300310	ELASTOMERIC BEARING ASSEMBLY, TYPE I	EACH	40		20	20							
50300320	ELASTOMERIC BEARING ASSEMBLY, TYPE II	EACH	10		10								
50400405	PRECAST PRESTRESSED CONCRETE DECK BEAMS (2" DEPTH)	SO FT	3,101				3,101						
50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1		.48	.52							
50500505	STUD SHEAR CONNECTORS	EACH	4,260		2,460	1,800							
50800105	REINFORCEMENT BARS	POUND	19,760	9,030	130	7,160	3,440						
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	370,596		200,620	165,430	4,546						
50900205	STEEL RAILING, TYPE SI	FOOT	222				222						
51201400	FURNISHING STEEL PILES HP 10x42	FOOT	448		448								
51201500	FURNISHING STEEL PILES HP 10x57	FOOT	294			294							
51201600	FURNISHING STEEL PILES HP 12x53	FOOT	680				680						
51202700	DRIVING STEEL PILES	FOOT	1,422		448	294	680						
51203400	TEST PILE STEEL HP 10x42	EACH	2		2								
51203500	TEST PILE STEEL HP 10x57	EACH	2			2							
51203600	TEST PILE STEEL HP 12x53	EACH	2				2						
51204315	CONCRETE ENCASEMENT	CU YD	31.4				31.4						
51205200	TEMPORARY SHEET PILING	SO FT	1,240		900	340							
51500100	NAME PLATES	EACH	3		1	1	1						
54001001	BOX CULVERT END SECTION, CULVERT NO. 1	EACH	2	2									
54001002	BOX CULVERT END SECTION, CULVERT NO. 2	EACH	2	2									
54001003	BOX CULVERT END SECTION, CULVERT NO. 3	EACH	1		1								
54001004	BOX CULVERT END SECTION, CULVERT NO. 4	EACH	1		1								
54002020	EXPANSION BOLTS 3/4 INCH	EACH	102	72	30								

0 SN 025-0078
00 SN 025-0077
000 SN 025-3309

NOTE:
RURAL STA. 541+93.85 TO STA. 1016+00.00
URBAN STA. 1016+00.00 TO STA. 46+80.05
*DENOTES SPECIALTY ITEM

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		SUMMARY OF QUANTITIES SHEET 2 OF 8
		DRAWN BY ASB CHECKED BY SJK
		DATE 8/02