

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
774	*	EFFINGHAM	344	6
FED. ROAD DIST. NO. 7		ILLINOIS	FED. AID PROJECT	
*107WRS-1, 107BY, 107BY-1 & 107B-2		CONTRACT NO. 94827		

SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE											
PAY CODE NUMBER	ITEM	UNIT	TOTAL QUANTITY	1000-2A		X071-2A		X080-2A		Y030-IE		Y031-IF		Y007	
				RURAL	URBAN	RURAL	URBAN	RURAL	URBAN	RURAL	URBAN	URBAN	RURAL	URBAN	
540I0202	PRECAST CONCRETE BOX CULVERT 2' X 2'	FOOT	45		45										
540I0302	PRECAST CONCRETE BOX CULVERT 3' X 2'	FOOT	52	52											
540I0303	PRECAST CONCRETE BOX CULVERT 3' X 3'	FOOT	30		30										
540I0403	PRECAST CONCRETE BOX CULVERT 4' X 3'	FOOT	133	48	85										
542A0223	PIPE CULVERTS, CLASS A, TYPE I 18"	FOOT	236	200	36										
542A0229	PIPE CULVERTS, CLASS A, TYPE I 24"	FOOT	183	183											
542A0241	PIPE CULVERTS, CLASS A, TYPE I 36"	FOOT	140	128	12										
542D0220	PIPE CULVERTS, CLASS D, TYPE I 15"	FOOT	579	498	81										
542D0223	PIPE CULVERTS, CLASS D, TYPE I 18"	FOOT	449	405	44										
542D0226	PIPE CULVERTS, CLASS D, TYPE I 21"	FOOT	135	135											
542D0229	PIPE CULVERTS, CLASS D, TYPE I 24"	FOOT	232	194	38										
542D0235	PIPE CULVERTS, CLASS D, TYPE I 30"	FOOT	102	102											
542D1066	PIPE CULVERTS, CLASS D, TYPE 2 21"	FOOT	80	80											
542D1075	PIPE CULVERTS, CLASS D, TYPE 2 30"	FOOT	166	166											
542D5470	PIPE CULVERTS, CLASS D, TYPE I, EQUIVALENT ROUND-SIZE 15"	FOOT	225	225											
542D5473	PIPE CULVERTS, CLASS D, TYPE I, EQUIVALENT ROUND-SIZE 18"	FOOT	30	30											
542JA024	PIPE CULVERTS, CLASS A 24" (JACKED)	FOOT	154	154											
542JA030	PIPE CULVERTS, CLASS A 30" (JACKED)	FOOT	182	182											
54207162	PIPE CULVERTS, TYPE I, REINFORCED CONCRETE-ELLIPTICAL EQUIVALENT ROUND-SIZE 27"	FOOT	105	105											
542I3447	END SECTIONS 12"	EACH	4	2	2										
542I3450	END SECTIONS 15"	EACH	28	24	4										
542I3453	END SECTIONS 18"	EACH	18	16	2										
542I3456	END SECTIONS 21"	EACH	8	8											
542I3459	END SECTIONS 24"	EACH	10	8	2										
542I3465	END SECTIONS 30"	EACH	8	8											
542I3663	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 18"	EACH	3	3											
542I3669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	10	7	3										
542I3675	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 30"	EACH	4	4											
542I3681	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 36"	EACH	4	2	2										
542I4290	END SECTIONS, EQUIVALENT ROUND-SIZE 15"	EACH	10	10											
542I4293	END SECTIONS, EQUIVALENT ROUND-SIZE 18"	EACH	2	2											
542I4722	PRECAST REINFORCED CONCRETE FLARED END SECTIONS, ELLIPTICAL EQUIVALENT ROUND-SIZE 27"	EACH	2	2											
542I6930	REINFORCED CONCRETE PIPE TEE, 18" PIPE WITH 18" RISER	EACH	1	1											
542I7680	REINFORCED CONCRETE PIPE TEE, 24" PIPE WITH 24" RISER	EACH	1		1										
550A0070	STORM SEWERS, CLASS A, TYPE I 15"	FOOT	15		15										
550A0120	STORM SEWERS, CLASS A, TYPE I 24"	FOOT	685		685										
550A0160	STORM SEWERS, CLASS A, TYPE I 36"	FOOT	276		276										
*550A2320	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE I, 12"	FOOT	51		51										
*550A2340	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE I 18"	FOOT	21		21										
*550A2360	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE I 24"	FOOT	342		342										
55100500	STORM SEWER REMOVAL 12"	FOOT	8		8										
55100700	STORM SEWER REMOVAL 15"	FOOT	52	43	9										
55100900	STORM SEWER REMOVAL 18"	FOOT	126	126											
55101100	STORM SEWER REMOVAL 21"	FOOT	331	331											
55101200	STORM SEWER REMOVAL 24"	FOOT	754	127	627										
55101600	STORM SEWER REMOVAL 36"	FOOT	195	195											
55101900	STORM SEWER REMOVAL 48"	FOOT	359	359											
59100100	GEOCOMPOSITE WALL DRAIN	SO YD	490												
60100060	CONCRETE HEADWALL FOR PIPE DRAINS	EACH	15	7	8										490

0 SN 025-0078  
00 SN 025-0077  
000 SN 025-3309

NOTE:  
RURAL STA. 541+93.85 TO STA. 1016+00.00  
URBAN STA. 1016+00.00 TO STA. 46+80.05  
\*DENOTES SPECIALTY ITEM

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES  
SHEET 3 OF 8

DATE 8/02

DRAWN BY ASB  
CHECKED BY SJK