

SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE											
PAY CODE NUMBER	ITEM	UNIT	TOTAL QUANTITY	1000-2A		X071-2A		X080-2A	Y030-IE		Y031-IF		Y007		Y031-3D
				RURAL	URBAN	RURAL	URBAN	RURAL	RURAL	100% CITY	URBAN	RURAL	URBAN	URBAN	
* 87502310	TRAFFIC SIGNAL POST, PAINTED STEEL 16 FT.	EACH	1									1			
* 87502330	TRAFFIC SIGNAL POST, PAINTED STEEL 18 FT.	EACH	2									2			
* 87702910	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 36 FT.	EACH	1									1			
* 87702940	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 42 FT.	EACH	1									1			
* 87702970	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 48 FT.	EACH	1									1			
* 87702985	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 52 FT.	EACH	1									1			
* 87800100	CONCRETE FOUNDATION, TYPE A	FOOT	18									18			
* 87800210	CONCRETE FOUNDATION, TYPE D (SPECIAL)	FOOT	6									6			
* 87800415	CONCRETE FOUNDATION, TYPE E 36-INCH DIAMETER	FOOT	52									52			
* 87900100	DRILL EXISTING FOUNDATION	EACH	1									1			
* 88200400	TRAFFIC SIGNAL BACKPLATE, FORMED PLASTIC	EACH	18									18			
* 88700200	LIGHT DETECTOR	EACH	2											2	
* 88700300	LIGHT DETECTOR AMPLIFIER	EACH	1											1	
Z0002600	BAR SPLICERS	EACH	2,903			1,643	1,260								
* Z0007601	BUILDING REMOVAL NO. 1	L SUM	1		1										
* Z0007602	BUILDING REMOVAL NO. 2	L SUM	1		1										
* Z0008236	DRILLED SHAFT IN SOIL 36'	FOOT	169			119	50								
* Z0008330	DRILLED SHAFT IN ROCK 30'	FOOT	128			81	47								
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	.83	.17										
Z0023500	FILLING EXISTING CULVERTS	CU YD	12.2	12.2											
* Z0025100	FURNISHING AND INSTALLING CABLE SPLICES	EACH	1						1						
Z0025500	FURNISHING AND INSTALLING PROPERTY MARKERS	EACH	31	28	3										
Z0028700	GRANULAR SUBGRADE REPLACEMENT	CU YD	1,387	1,387											
Δ Z0030455	IMPACT ATTENUATORS, TEMPORARY (FULLY-REDIRECTIVE, NARROW), TEST LEVEL 2	EACH	4	3	1										
Δ Z0030320	IMPACT ATTENUATORS, RELOCATE (FULLY-REDIRECTIVE), TEST LEVEL 2	EACH	4	3	1										
Z0031301	JACKING AND CRIBBING, LOCATION NO. 1	L SUM	1				1								
Z0031302	JACKING AND CRIBBING, LOCATION NO. 2	L SUM	1				1								
Z0040530	PIPE UNDERDRAIN REMOVAL	FOOT	3,568	1,614	1,954										
Z0043900	PREFORMED JOINT FILLER	FOOT	780		780										
* Z0049901	REMOVAL AND DISPOSAL OF NON-FRIABLE ASBESTOS, BUILDING NO. 1	L SUM	1		1										
Z0075300	TIE BARS	EACH	391		391										
□ Z0076600	TRAINEES	HOUR	1,000	500	500										
A2000274	TREE, ACER X FREEMANII MARMO (MARMO FREEMAN MAPLE), 10' HEIGHT, CLUMP FORM, BALLED AND BURLAPPED	EACH	17	17											
A2000716	TREE, ACER PLATANOIDES COLUMARE (COLUMNAR NORWAY MAPLE), 2" CALIPER, BALLED AND BURLAPPED	EACH	22	22											
A2001216	TREE, ACER RUBRUM RED SUNSET (RED SUNSET RED MAPLE), 2" CALIPER, BALLED AND BURLAPPED	EACH	18	16	2										
A2001016	TREE, ACER RUBRUM (RED MAPLE), 2" CALIPER, BALLED AND BURLAPPED	EACH	14		14										
A2001716	TREE, ACER SACCHARUM (SUGAR MAPLE), 2" CALIPER, BALLED AND BURLAPPED	EACH	21	19	2										
* A2002320	TREE, BETULA NIGRA (RIVER BIRCH), 2-1/2" CALIPER, BALLED AND BURLAPPED	EACH	30	30											
A2002816	TREE, CATALPA SPECIOSA (NORTHERN CATALPA), 2" CALIPER, BALLED AND BURLAPPED	EACH	28	28											
A2002916	TREE, CELTIS OCCIDENTALIS (COMMON HACKBERRY), 2" CALIPER, BALLED AND BURLAPPED	EACH	13		13										
A2007616	TREE, TAXODIUM DISTICHUM (COMMON BALD CYPRESS), 2" CALIPER, BALLED AND BURLAPPED	EACH	26	24	2										
B2000366	TREE, ACER GINNALA FLAME (FLAME AMUR MAPLE) 6' HEIGHT, SHRUB FORM, BALLED AND BURLAPPED	EACH	40		40										
B2000964	TREE, AMELANCHIER LAEVIS (ALLEGHENY SERVICE BERRY), 5' HEIGHT, CLUMP FORM, BALLED AND BURLAPPED	EACH	73	73											
B2001116	TREE, CERCIS CANADENSIS (EASTERN REDBUD), 2" CALIPER, TREE FORM, BALLED AND BURLAPPED	EACH	70	63	7										

○ SN 025-0078
 ○○ SN 025-0077
 ○○○ SN 025-3309
 □ Y080
 Δ SFTY-3N

NOTE:
 RURAL STA. 541+93.85 TO STA. 1016+00.00
 URBAN STA. 1016+00.00 TO STA. 46+80.05
 * DENOTES SPECIALTY ITEM

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		SUMMARY OF QUANTITIES SHEET 6 OF 8 DRAWN BY ASB CHECKED BY SJK DATE 8/02