

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
774	*	EFFINGHAM	344	118
FED. ROAD DIST. NO. 7 ILLINOIS FED. AID PROJECT				
*107WRS-1, 107BY, 107BY-1 & 107B-2				
<b>CONTRACT NO. 94827</b>				

## SCHEDULE OF QUANTITIES

**ELECTRIC SERVICE INSTALLATION (80400100)**

STATION	EACH
56' LT STA. 955+53.55	1

**LIGHT POLE, ALUMINUM, 45 FT. M.H., TENON MOUNT (83012400)**

STATION	EACH
45' LT STA. 955+25.08	1

**CONDUIT IN TRENCH, 2" DIA., PVC (81012600)**

STATION	STATION	FEET
45' LT STA. 955+25.08	51' LT STA. 955+60.40	33
56' LT STA. 955+53.55	51' LT STA. 955+60.40	$\frac{4}{37}$

**LIGHT POLE FOUNDATION, 24" DIAMETER (83600200)**

STATION	FEET
45' LT STA. 955+25.08	8

**TRENCH AND BACKFILL FOR ELECTRICAL WORK (81500200)**

STATION	STATION	FEET
45' LT STA. 955+25.08	51' LT STA. 955+60.40	33
56' LT STA. 955+53.55	51' LT STA. 955+60.40	$\frac{4}{37}$

**BREAKAWAY DEVICE, COUPLING, WITH ALUMINUM SKIRT (83800505)**

STATION	EACH
45' LT STA. 955+25.08	4

**ELECTRICAL CABLE IN CONDUIT, 600V (XLP - TYPE USE) 1/C #10 (81702110)**

STATION	STATION	FEET	SLACK	NO.	FEET
45' LT STA. 955+25.08	51' LT STA. 955+60.40	33	5	3	114

**ELECTRICAL CABLE IN CONDUIT, 600V (XLP - TYPE USE) 1/C #6 (81702130)**

STATION	STATION	FEET	SLACK	NO.	FEET
56' LT STA. 955+53.55	51' LT STA. 955+60.40	29	6	3	105

**LUMINAIRE, SODIUM VAPOR, MULTI MOUNT, 250 WATT (82103900)**

STATION	EACH
45' LT STA. 955+25.08	1

**LIGHTING CONTROLLER TYPE CB-RCS 60 AMP - 240 VOLT (82500510)**

STATION	EACH
51' LT STA. 955+60.40	1

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		NAZARENE ROAD LIGHTING PLANS SHEET 6 OF 8
DATE 8/02		DRAWN BY ASB CHECKED BY BWD