



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

January 3, 2011

SUBJECT: Various Routes
Project HSIP-000S (830)
Section 2010-004-GRR
McHenry County
Contract No. 60K22
Item No. 5, January 21, 2011 Letting
Addendum A

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Replace the Schedule of Prices.
2. Revised page 6 of the Special Provisions.
3. Revised sheets 2 & 3 of the Plans.

Prime contractors must utilize the enclosed material when preparing their bid and must include any Schedule of Prices changes in their bidding proposal.

Bidders using computer-generated bids are cautioned to reflect any and all Schedule of Prices changes, if involved, into their computer programs.

Very truly yours,

Scott E. Stitt, P.E.
Acting Engineer of Design and Environment

A handwritten signature in black ink, appearing to read 'Ted B. Walschleger P.E.'.

By: Ted B. Walschleger, P. E.
Engineer of Project Management

cc: Diane O'Keefe, Region 1, District 1; Mike Renner; Estimates

TBW:MS:jc

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER -

60K22

State Job # - C-91-449-10
 PPS NBR - 1-78559-0000
 County Name - MCHENRY--
 Code - 111 - -
 District - 1 - -
 Section Number - 2010-004-GRR

Project Number
 HSIP-000S/830/

Route
 VARIOUS

* REVISED : January 3, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
X0322194	POLY MOD P C MORTAR	SQ FT	9.000				
X2503100	MOWING	UNIT	138.000				
Z0030030	IMP ATTEN FRD NAR TL3	EACH	3.000				
Z0030850	TEMP INFO SIGNING	SQ FT	154.000				
20200600	EXC & GR EX SHOULDER	UNIT	35.000				
21101615	TOPSOIL F & P 4	SQ YD	1,536.000				
25000210	SEEDING CL 2A	ACRE	0.320				
25000400	NITROGEN FERT NUTR	POUND	29.000				
25000500	PHOSPHORUS FERT NUTR	POUND	29.000				
25000600	POTASSIUM FERT NUTR	POUND	29.000				
25100630	EROSION CONTR BLANKET	SQ YD	1,536.000				
48101620	AGGREGATE SHLDS B 10	SQ YD	2,734.000				
50102400	CONC REM	CU YD	4.000				
50104000	BRIDGE RAIL REMOVAL	FOOT	56.000				
50300255	CONC SUP-STR	CU YD	10.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 60K22

State Job # - C-91-449-10
 PPS NBR - 1-78559-0000
 County Name - MCHENRY--
 Code - 111 - -
 District - 1 - -
 Section Number - 2010-004-GRR

Project Number
 HSIP-000S/830/

Route
 VARIOUS

* REVISED : January 3, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
50800205	REINF BARS, EPOXY CTD	POUND	5,950.000				
63000001	SPBGR TY A 6FT POSTS	FOOT	288.000				
63000025	SPBGR ATTACH TO STR	FOOT	163.000				
63100085	TRAF BAR TERM T6	EACH	8.000				
63100167	TR BAR TRM T1 SPL TAN	EACH	48.000				
63200310	GUARDRAIL REMOV	FOOT	2,941.000				
63301000	REM & REERECT SPBGR	FOOT	88.000				
63301990	REM RE-E T B TERM T1	EACH	3.000				
67000400	ENGR FIELD OFFICE A	CAL MO	6.000				
67100100	MOBILIZATION	L SUM	1.000				
* 70100450	TRAF CONT-PROT 701201	L SUM	1.000				
70100500	TRAF CONT-PROT 701326	L SUM	1.000				
* 70102620	TR CONT & PROT 701501	L SUM	1.000				
78200420	GUARDRAIL MKR TYPE B	EACH	123.000				
78201000	TERMINAL MARKER - DA	EACH	48.000				

Special attention is called to Article 107.09 of the Standard Specifications and the following Highway Standards, Details, Quality Standard for Work Zone Traffic Control Devices, Recurring Special Provisions and Special Provisions contained herein, relating to traffic control.

The Contractor shall contact the District One Bureau of Traffic at least 72 hours in advance of beginning work.

STANDARDS: 701006, **701101**, **701201**, 701326, **701422**, **701501** and 701901

DETAILS:

Arterial Road Information Sign (TC22)

SPECIAL PROVISIONS:

Maintenance of Roadways
Temporary Information Signing
Truck Mounted/Trailer Mounted Attenuators (BDE)
Post Mounting of Signs (BDE)

TEMPORARY INFORMATION SIGNING

Effective: November 13, 1996

Revised: January 2, 2007

Description. This work shall consist of furnishing, installing, maintaining, relocating for various states of construction and eventually removing temporary informational signs. Included in this item may be ground mount signs, skid mount signs, truss mount signs, bridge mount signs, and overlay sign panels which cover portions of existing signs.

Materials. Materials shall be according to the following Articles of Section 1000 - Materials:

	<u>Item</u>	<u>Article/Section</u>
a.)	Sign Base (Notes 1 & 2)	1090
b.)	Sign Face (Note 3)	1091
c.)	Sign Legends	1092
d.)	Sign Supports	1093
e.)	Overlay Panels (Note 4)	1090.02
Note 1.	The Contractor may use 5/8 inch (16 mm) instead of 3/4 inch (19 mm) thick plywood.	
Note 2.	Type A sheeting can be used on the plywood base.	
Note 3.	All sign faces shall be Type A except all orange signs shall meet the requirements of Article 1106.01.	
Note 4.	The overlay panels shall be 0.08 inch (2 mm) thick.	

GENERAL CONSTRUCTION REQUIREMENTS

Installation.

The sign sizes and legend sizes shall be verified by the Contractor prior to fabrication.

Signs which are placed along the roadway and/or within the construction zone shall be installed according to the requirements of Article 701.14 and Article 720.04.

Revised 01/03/2011