90% FED.
10% STATE

CODE NO.	ITEM	UNIT	URBAN TOTAL	ROADWAY 0003	STRUCTURAL 0013	LANDSCAPING 0031
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	215			215
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	173			173
20101300	TREE PRUNING (1 TO 10 INCH DIAMETER)	EACH	46			46
20101350	TREE PRUNING (OVER 10 INCH DIAMETER)	EACH	23			23
20200100	EARTH EXCAVATION	CU YD	18,059	18,059		
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	13,034	13,034		
20800150	TRENCH BACKFILL	CU YD	11,907	11,907		
21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	3,960	3,960		
21101605	TOPSOIL FURNISH AND PLACE, 2"	SQ YD	110,900			110,900
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	19,360			19,360
25000210	SEEDING, CLASS 2A	ACRE	1			1
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	90			90
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	90			90
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	90			90
Δ 25000750	MOWING	ACRE	40			40

* DENOTES SPECIALTY ITEM
Δ NON-PARTICIPATING

90% FED.
10% STATE

CODE NO.	ITEM	UNIT	URBAN TOTAL	ROADWAY 0003	STRUCTURAL 0013	LANDSCAPING 0031
25100105	MULCH, METHOD 1	ACRE	4			4
25100115	MULCH, METHOD 2	ACRE	3			3
25100630	EROSION CONTROL BLANKET	SQ YD	4,678	4,678		
28000305	TEMPORARY DITCH CHECKS	FOOT	733	735		
28000400	PERIMETER EROSION BARRIER	FOOT	3,597	3,597		
28000500	INLET AND PIPE PROTECTION	EACH	225	225		
28100101	STONE RIPRAP, CLASS A1	SQ YD	230	230		
28100107	STONE RIPRAP, CLASS A4	SQ YD	230	230		
28200200	FILTER FABRIC	SQ YD	230	230		
31200502	STABILIZED SUBBASE - HOT-MIX ASPHALT, 4 1/2"	SQ YD	54,580	54,580		
42001300	PROTECTIVE COAT	SQ YD	16,650	16,650		
42001420	BRIDGE APPROACH PAVEMENT CONNECTOR (PCC)	SQ YD	823	823		
44000100	PAVEMENT REMOVAL	SQ YD	445	445		
44213000	PATCHING REINFORCEMENT	SQ YD	180	180		
44213200	SAW CUTS	FOOT	780	780		

N:\PROJ\33841-3_East\Design\MacSheets\33841E-S0101.dgn

Rev.

ENGINEERING CONSULTANT
Ciorba Group, Inc.
CONSULTING ENGINEERS
5607 North Cumberland Avenue, Suite 402
Chicago, Illinois 60656
Tel 773.775.4008 Fax 773.775.4014
Email: Design@ciorba.com

USER NAME = jkjellman	DESIGNED - CRC	REVISED -	
	DRAWN - JMK	REVISED -	
PLOT SCALE = 1.0000 ' / IN.	CHECKED - MRJ	REVISED -	
PLOT DATE = 10/28/2010	DATE - 10/27/2010	REVISED -	

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

F.A.I. 80 FROM NS RAILROAD TO US 45
SUMMARY OF QUANTITIES

SCALE: | SHEET NO. OF SHEETS | STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
80	99(5&5-1) Y-1	WILL	309	4

CONTRACT NO. 60M59
ILLINOIS FED. AID PROJECT