

CODE NO.	ITEM	UNIT	90% FED. 10% STATE URBAN TOTAL	ROADWAY 0003	STRUCTURAL 0013	LANDSCAPING 0031
73000100	WOOD SIGN SUPPORT	FOOT	506	506		
73100100	REMOVE GROUND MOUNTED SIGN SUPPORT	EACH	2	2		
73100100	BASE FOR TELESCOPING STEEL SIGN SUPPORT	EACH	1	1		
73100200	REMOVE CONCRETE FOUNDATION - GROUND MOUNT	EACH	2	2		
78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	75,031	75,031		
78008220	POLYUREA PAVEMENT MARKING TYPE I - LINE 5"	FOOT	19,225	19,225		
78008240	POLYUREA PAVEMENT MARKING TYPE I - LINE 8"	FOOT	6,792	6,792		
78008250	POLYUREA PAVEMENT MARKING TYPE I - LINE 12"	FOOT	3,628	3,628		
78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	925	925		
78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	25	25		
78100300	REPLACEMENT REFLECTOR	EACH	154	154		
78200100	MONODIRECTIONAL PRISMATIC BARRIER REFLECTOR	EACH	95	95		
78200410	GUARDRAIL MARKERS, TYPE A	EACH	50	50		
78200530	BARRIER WALL MARKERS, TYPE C	EACH	2,960	2,960		
78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	3	3		
78300100	PAVEMENT MARKING REMOVAL	SQ FT	26,705	26,705		
80400200	ELECTRIC UTILITY SERVICE CONNECTION	L SUM	1	1		

* DENOTES SPECIALTY ITEM

CODE NO.	ITEM	UNIT	90% FED. 10% STATE URBAN TOTAL	ROADWAY 0003	STRUCTURAL 0013	LANDSCAPING 0031
81000600	CONDUIT IN TRENCH, 2" DIA., GALVANIZED STEEL	FOOT	330	330		
81000800	CONDUIT IN TRENCH, 3" DIA., GALVANIZED STEEL	FOOT	125	125		
81013000	CONDUIT IN TRENCH, 4" DIA., PVC	FOOT	18,200	18,200		
81018600	CONDUIT PUSHED, 2 1/2" DIA., GALVANIZED STEEL	FOOT	175	175		
81018700	CONDUIT PUSHED, 3" DIA., GALVANIZED STEEL	FOOT	1,210	1,210		
81018900	CONDUIT PUSHED, 4" DIA., GALVANIZED STEEL	FOOT	430	430		
81101005	CONDUIT ATTACHED TO STRUCTURE, 4" DIA., PVC COATED GALVANIZED STEEL	FOOT	220	220		
81300960	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 42" X 36" X 12"	EACH	2	2		
81400200	HEAVY-DUTY HANDHOLE	EACH	11	11		
81603037	UNIT DUCT, 600V, 2-1C NO.6, 1/C NO.6 GROUND, (XLP-TYPE USE), 1 1/4" DIA. POLYETHYLENE	FOOT	1,600	1,600		
81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	18,900	18,900		
83600200	LIGHT POLE FOUNDATION, 24" DIAMETER	FOOT	100	100		
83800105	BREAKAWAY DEVICE, TRANSFORMER BASE, 11.5 INCH BOLT CIRCLE	EACH	10	10		
84200400	REMOVAL OF LIGHTING UNIT, NO SALVAGE	EACH	3	3		
87800200	CONCRETE FOUNDATION, TYPE D	FOOT	40	40		
89502200	MODIFY EXISTING CONTROLLER	EACH	2	2		

N:\PROJ\3384\3_East\Design\MiscSheets\3384E-SC0086.dwg



USER NAME = oornwell
 DESIGNED - CRC
 DRAWN - JMK
 CHECKED - MRJ
 DATE - 10/27/2010
 PLOT SCALE = 1/8" = 1' IN.
 PLOT DATE = 10/28/2010

REVISOR -
 REVISION -
 REVISOR -
 REVISION -

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

F.A.I. 80 FROM NS RAILROAD TO US 45
 SUMMARY OF QUANTITIES
 SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.I. SECTION COUNTY TOTAL SHEETS SHEET NO.
 80 99(S&S-1) Y-1 WILL 309 8
 CONTRACT NO. 60M59
 ILLINOIS FED. AID PROJECT

Rev.