

STATION	STAGE 1					STAGE 2						
	20200100		20201200			20200100		20201200				
	EARTH EXCAVATION	EARTH EXCAVATION VOLUME USED (15% SHRINKAGE)	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)	EARTH EXCAVATION	EARTH EXCAVATION VOLUME USED (15% SHRINKAGE)	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)		
1-80 FROM NS RAILROAD TO US 45	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)		
932+00.00	TO	933+00.00	84.6	71.9	58.5	1.1	70.8	0.0	0.0	30.6	16.3	-16.3
933+00.00	TO	934+00.00	83.0	70.5	58.5	1.5	69.0	0.0	0.0	41.7	23.3	-23.3
934+00.00	TO	935+00.00	84.6	71.9	58.5	0.9	71.0	0.0	0.0	23.7	11.1	-11.1
935+00.00	TO	936+00.00	87.8	74.6	58.5	0.2	74.4	0.0	0.0	15.4	3.7	-3.7
936+00.00	TO	937+00.00	105.2	89.4	58.5	0.0	89.4	0.0	0.0	10.4	2.8	-2.8
937+00.00	TO	938+00.00	117.2	99.6	58.5	0.0	99.6	0.0	0.0	0.0	0.0	0.0
938+00.00	TO	939+00.00	113.9	96.8	59.4	0.0	96.8	0.0	0.0	0.0	0.0	0.0
939+00.00	TO	940+00.00	93.3	79.3	63.3	9.6	69.7	0.0	0.0	0.0	0.0	0.0
940+00.00	TO	941+00.00	69.8	59.3	66.7	18.7	40.6	0.0	0.0	0.0	0.0	0.0
941+00.00	TO	942+00.00	73.7	62.6	65.2	9.6	53.0	0.0	0.0	0.0	0.0	0.0
942+00.00	TO	943+00.00	91.1	77.4	60.9	0.6	76.9	0.0	0.0	0.0	0.0	0.0
943+00.00	TO	944+00.00	102.4	87.0	58.3	0.0	87.0	0.0	0.0	0.0	0.0	0.0
944+00.00	TO	945+00.00	94.8	80.6	58.3	1.3	79.3	0.0	0.0	0.0	0.0	0.0
945+00.00	TO	946+00.00	76.1	64.7	58.5	18.0	46.7	0.0	0.0	0.0	0.0	0.0
946+00.00	TO	947+00.00	64.8	55.1	58.5	34.4	20.6	0.0	0.0	0.0	0.0	0.0
947+00.00	TO	948+00.00	68.7	58.4	58.5	24.8	33.6	0.0	0.0	0.0	0.0	0.0
948+00.00	TO	949+00.00	73.5	62.5	58.5	10.9	51.6	0.0	0.0	0.0	0.0	0.0
949+00.00	TO	950+00.00	74.1	63.0	58.5	7.2	55.7	0.0	0.0	0.0	0.0	0.0
950+00.00	TO	951+00.00	74.8	63.6	58.5	6.7	56.9	0.0	0.0	0.0	0.0	0.0
951+00.00	TO	952+00.00	73.1	62.2	58.5	7.8	54.4	0.0	0.0	0.0	0.0	0.0
952+00.00	TO	953+00.00	69.8	59.3	58.5	9.4	49.9	0.0	0.0	0.0	0.0	0.0
953+00.00	TO	954+00.00	67.6	57.5	58.5	14.3	43.2	0.0	0.0	0.0	0.0	0.0
954+00.00	TO	955+00.00	65.6	55.7	58.5	20.7	35.0	0.0	0.0	0.0	0.0	0.0
955+00.00	TO	956+00.00	64.6	54.9	58.5	22.2	32.7	0.0	0.0	0.0	0.0	0.0
956+00.00	TO	957+00.00	68.3	58.1	58.5	20.2	37.9	0.0	0.0	0.0	0.0	0.0
957+00.00	TO	958+00.00	70.4	59.8	58.5	21.3	38.5	0.0	0.0	0.0	0.0	0.0
958+00.00	TO	959+00.00	66.9	58.6	58.5	24.4	34.1	0.0	0.0	0.0	0.0	0.0
959+00.00	TO	960+00.00	69.3	58.9	58.5	24.6	34.2	0.0	0.0	0.0	0.0	0.0
960+00.00	TO	961+00.00	74.8	63.6	58.5	20.4	43.2	0.0	0.0	0.0	0.0	0.0
961+00.00	TO	962+00.00	75.4	64.1	62.4	16.9	47.2	0.0	0.0	0.0	0.0	0.0
962+00.00	TO	963+00.00	85.0	72.3	62.4	9.6	62.6	0.0	0.0	0.0	0.0	0.0
963+00.00	TO	964+00.00	90.0	76.5	61.5	4.4	72.1	0.0	0.0	0.0	0.0	0.0
964+00.00	TO	965+00.00	72.2	61.4	65.0	11.9	49.5	0.0	0.0	0.0	0.0	0.0
965+00.00	TO	966+00.00	68.1	57.9	62.0	12.2	45.7	0.0	0.0	0.0	0.0	0.0
966+00.00	TO	967+00.00	76.1	64.7	58.5	5.6	59.1	0.0	0.0	0.0	0.0	0.0
967+00.00	TO	968+00.00	81.1	68.9	58.3	3.1	65.8	0.0	0.0	0.0	0.0	0.0
968+00.00	TO	969+00.00	80.0	68.0	74.3	1.3	66.7	0.0	0.0	0.0	0.0	0.0
969+00.00	TO	970+00.00	76.9	65.3	98.0	0.0	65.3	0.0	0.0	0.0	0.0	0.0
970+00.00	TO	971+00.00	78.3	66.6	112.8	0.0	66.6	0.0	0.0	0.0	0.0	0.0
971+00.00	TO	972+00.00	80.6	68.5	121.7	0.0	68.5	0.0	0.0	0.0	0.0	0.0
972+00.00	TO	973+00.00	83.5	71.0	125.0	0.0	71.0	0.0	0.0	0.0	0.0	0.0
973+00.00	TO	974+00.00	86.3	73.4	127.2	0.0	73.4	0.0	0.0	0.0	0.0	0.0
974+00.00	TO	975+00.00	108.9	92.6	93.1	0.0	92.6	0.0	0.0	0.0	0.0	0.0
975+00.00	TO	976+00.00	126.1	107.2	58.5	0.0	107.2	0.0	0.0	0.0	0.0	0.0
976+00.00	TO	977+00.00	118.9	101.1	58.5	0.0	101.1	0.0	0.0	0.0	0.0	0.0
977+00.00	TO	978+00.00	117.2	99.6	58.5	0.0	99.6	0.0	0.0	0.0	0.0	0.0
978+00.00	TO	979+00.00	110.2	93.7	58.5	0.0	93.7	0.0	0.0	0.0	0.0	0.0
979+00.00	TO	980+00.00	88.1	74.9	58.5	8.7	66.2	0.0	0.0	0.0	0.0	0.0
980+00.00	TO	981+00.00	70.9	60.3	58.5	20.0	40.3	0.0	0.0	0.0	0.0	0.0
981+00.00	TO	982+00.00	73.1	62.2	58.5	18.3	43.8	0.0	0.0	0.0	0.0	0.0
982+00.00	TO	983+00.00	79.4	67.5	58.3	10.9	56.6	0.0	0.0	0.0	0.0	0.0

c:\prow\338A\3_sant\design\m\across\338A-F4_schm02.dgn

ENGINEERING CONSULTANT
 **Giorgio Group, Inc.**
 CONSULTING ENGINEERS
 5007 North Cumberland Avenue, Suite 402
 Chicago, Illinois 60630
 Tel. 773.776.4000 Fax 773.776.4014
 Email: cgreg@giorgio.com

USER NAME = jkjemmen	DESIGNED - CRC	REVISED -
PLOT SCALE = 1:8000 / IN.	DRAWN - JMK	REVISED -
PLOT DATE = 10/28/2010	CHECKED - MRJ	REVISED -
	DATE - 10/27/2010	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**F.A.I. 80 FROM NS RAILROAD TO US 45
EARTHWORK SCHEDULES**

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
80	99(5&5-1) Y-1	WILL	309	17
CONTRACT NO. 60M59				
ILLINOIS FED. AID PROJECT				