


STATION			STAGE 1					STAGE 2				
			20200100		20201200			20200100		20201200		
I-80 FROM NS RAILROAD TO US 45			EARTH EXCAVATION (CU YD)	EARTH EXCAVATION VOLUME USED (15% SHRINKAGE) (CU YD)	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL (CU YD)	EMBANKMENT (CU YD)	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-) (CU YD)	EARTH EXCAVATION (CU YD)	EARTH EXCAVATION VOLUME USED (15% SHRINKAGE) (CU YD)	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL (CU YD)	EMBANKMENT (CU YD)	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-) (CU YD)
983+00.00	TO	984+00.00	83.1	70.7	58.3	5.9	64.8	0.0	0.0	0.0	0.0	0.0
984+00.00	TO	985+00.00	93.1	79.2	58.5	2.0	77.1	0.0	0.0	0.0	0.0	0.0
985+00.00	TO	986+00.00	98.5	83.7	58.3	0.4	83.4	0.0	0.0	0.0	0.0	0.0
986+00.00	TO	987+00.00	104.3	88.6	58.3	0.4	88.3	0.0	0.0	0.0	0.0	0.0
987+00.00	TO	988+00.00	110.9	94.3	58.5	0.0	94.3	0.0	0.0	0.0	0.0	0.0
988+00.00	TO	989+00.00	112.4	95.5	58.5	0.0	95.5	0.0	0.0	0.0	0.0	0.0
989+00.00	TO	990+00.00	110.6	94.0	58.5	0.0	94.0	0.0	0.0	0.0	0.0	0.0
990+00.00	TO	991+00.00	95.2	80.9	58.5	1.3	79.6	0.0	0.0	0.0	0.0	0.0
991+00.00	TO	992+00.00	76.9	65.3	58.5	10.9	54.4	0.0	0.0	0.0	0.0	0.0
992+00.00	TO	993+00.00	64.8	55.1	58.5	34.6	20.5	0.0	0.0	0.0	0.0	0.0
993+00.00	TO	994+00.00	71.7	60.9	58.5	28.9	32.0	0.0	0.0	0.0	0.0	0.0
994+00.00	TO	995+00.00	86.9	73.8	58.5	5.6	68.3	0.0	0.0	0.0	0.0	0.0
995+00.00	TO	996+00.00	90.7	77.1	58.5	3.0	74.2	0.0	0.0	0.0	0.0	0.0
996+00.00	TO	997+00.00	88.9	75.6	58.3	2.8	72.8	0.0	0.0	0.0	0.0	0.0
997+00.00	TO	998+00.00	85.6	72.7	58.3	5.6	67.2	0.0	0.0	0.0	0.0	0.0
998+00.00	TO	999+00.00	83.7	71.1	58.5	8.5	62.6	0.0	0.0	0.0	0.0	0.0
999+00.00	TO	1000+00.00	78.1	66.4	58.5	15.6	50.9	0.0	0.0	0.0	0.0	0.0
1000+00.00	TO	1001+00.00	71.5	60.8	58.5	24.3	36.5	0.0	0.0	0.0	0.0	0.0
1001+00.00	TO	1002+00.00	68.3	58.1	58.5	25.7	32.3	0.0	0.0	0.0	0.0	0.0
1002+00.00	TO	1003+00.00	68.1	57.9	58.3	26.3	31.6	0.0	0.0	0.0	0.0	0.0
1003+00.00	TO	1004+00.00	66.9	56.8	58.3	33.7	23.1	0.0	0.0	0.0	0.0	0.0
1004+00.00	TO	1005+00.00	66.5	56.5	58.5	33.9	22.6	0.0	0.0	0.0	0.0	0.0
1005+00.00	TO	1006+00.00	70.0	59.5	58.5	26.7	32.8	0.0	0.0	0.0	0.0	0.0
1006+00.00	TO	1007+00.00	71.9	61.1	58.3	25.6	35.5	0.0	0.0	0.0	0.0	0.0
1007+00.00	TO	1008+00.00	73.7	62.6	58.3	23.3	39.3	0.0	0.0	0.0	0.0	0.0
1008+00.00	TO	1009+00.00	76.1	64.7	58.5	20.4	44.3	0.0	0.0	0.0	0.0	0.0
1009+00.00	TO	1010+00.00	78.1	66.4	58.5	18.5	47.9	0.0	0.0	0.0	0.0	0.0
1010+00.00	TO	1011+00.00	78.9	67.1	58.5	17.2	49.8	0.0	0.0	0.0	0.0	0.0
1011+00.00	TO	1011+50.00	37.8	32.1	31.1	9.4	22.8	0.0	0.0	4.1	1.2	-1.2
1011+50.00	TO	1011+65.00	10.9	9.3	9.9	3.1	6.2	0.0	0.0	2.5	0.8	-0.8
1011+65.00	TO	1012+00.00	26.4	22.5	21.8	6.9	15.6	0.0	0.0	4.9	1.6	-1.6
1012+00.00	TO	1013+00.00	77.0	65.5	58.5	18.5	47.0	0.0	0.0	12.0	4.1	-4.1
1013+00.00	TO	1014+00.00	74.6	63.4	58.5	19.1	44.4	0.0	0.0	12.6	4.8	-4.8
1014+00.00	TO	1015+00.00	70.2	59.7	58.5	19.8	39.8	0.0	0.0	14.1	6.3	-6.3
1015+00.00	TO	1016+00.00	68.5	58.2	58.5	23.5	34.7	0.0	0.0	16.7	7.6	-7.6
1016+00.00	TO	1017+00.00	81.3	69.1	58.5	14.1	55.0	0.0	0.0	8.7	3.7	-3.7
1017+00.00	TO	1018+00.00	98.3	83.6	58.5	0.6	83.0	0.0	0.0	0.0	0.0	0.0
1018+00.00	TO	1019+00.00	108.5	92.2	58.5	0.0	92.2	0.0	0.0	0.0	0.0	0.0
1019+00.00	TO	1020+00.00	111.1	94.4	55.6	0.0	94.4	0.0	0.0	0.0	0.0	0.0
1020+00.00	TO	1021+00.00	94.6	80.4	55.6	1.3	79.1	0.0	0.0	0.0	0.0	0.0
1021+00.00	TO	1022+00.00	76.9	65.3	61.1	5.6	59.8	0.0	0.0	0.0	0.0	0.0
1022+00.00	TO	1023+00.00	86.3	73.4	62.6	4.3	69.1	0.0	0.0	0.0	0.0	0.0
1023+00.00	TO	1024+00.00	90.6	77.0	62.0	0.2	76.8	0.0	0.0	0.0	0.0	0.0
1024+00.00	TO	1025+00.00	85.7	72.9	62.6	0.2	72.7	0.0	0.0	0.0	0.0	0.0
1025+00.00	TO	1026+00.00	98.5	83.7	60.6	0.0	83.7	0.0	0.0	0.0	0.0	0.0
1026+00.00	TO	1027+00.00	108.9	92.6	58.5	0.0	92.6	0.0	0.0	0.0	0.0	0.0
1027+00.00	TO	1028+00.00	100.9	85.8	58.5	0.2	85.6	0.0	0.0	0.0	0.0	0.0
1028+00.00	TO	1029+00.00	85.7	72.9	58.5	3.9	69.0	0.0	0.0	0.0	0.0	0.0
1029+00.00	TO	1030+00.00	93.3	79.3	58.5	3.7	75.6	0.0	0.0	0.0	0.0	0.0
1030+00.00	TO	1031+00.00	100.9	85.8	58.5	0.0	85.8	0.0	0.0	0.0	0.0	0.0
1031+00.00	TO	1032+00.00	86.7	73.7	58.5	2.8	70.9	0.0	0.0	0.0	0.0	0.0

m:\p\g\13384\3\_enet\dm\gpn\ms\sheet\3384E-EW\_sched03.dgn

	ENGINEERING CONSULTANT	USER NAME = jk.jellman	DESIGNED - CRC	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>F.A.I. 80 FROM NS RAILROAD TO US 45 EARTHWORK SCHEDULES</b>	F.A.I. RTE:	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	PLOT SCALE = 1:2000' / IN. PLOT DATE = 10/28/2010	DRAWN - JMK CHECKED - MRJ DATE - 10/27/2010	REVISED - REVISED - REVISED - REVISED -	80			99(5&5-1) Y-1	WILL	309	18	
						SCALE:	SHEET NO. OF SHEETS STA. TO STA.		ILLINOIS FED. AID PROJECT CONTRACT NO. 60M59		