

STATION			STAGE 1					STAGE 2				
			20200100		20201200		EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)	20200100		20201200		EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)
I-80 FROM NS RAILROAD TO US 45			EARTH EXCAVATION (CU YD)	EARTH EXCAVATION VOLUME USED (15% SHRINKAGE) (CU YD)	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL (CU YD)	EMBANKMENT (CU YD)		EARTH EXCAVATION (CU YD)	EARTH EXCAVATION VOLUME USED (15% SHRINKAGE) (CU YD)	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL (CU YD)	EMBANKMENT (CU YD)	
1032+00.00	TO	1033+00.00	83.1	70.7	58.5	3.0	67.7	0.0	0.0	0.0	0.0	0.0
1033+00.00	TO	1034+00.00	92.8	78.9	58.5	0.2	78.7	0.0	0.0	0.0	0.0	0.0
1034+00.00	TO	1035+00.00	98.5	83.7	58.5	0.0	83.7	0.0	0.0	0.0	0.0	0.0
1035+00.00	TO	1036+00.00	94.6	80.4	58.5	1.7	78.8	0.0	0.0	0.0	0.0	0.0
1036+00.00	TO	1037+00.00	91.5	77.8	58.5	3.0	74.8	0.0	0.0	0.0	0.0	0.0
1037+00.00	TO	1038+00.00	87.6	74.5	58.5	9.4	65.0	0.0	0.0	0.0	0.0	0.0
1038+00.00	TO	1039+00.00	80.2	68.2	58.5	18.0	50.2	0.0	0.0	0.0	0.0	0.0
1039+00.00	TO	1040+00.00	77.6	66.0	58.5	20.6	45.4	0.0	0.0	0.0	0.0	0.0
1040+00.00	TO	1041+00.00	78.3	66.6	58.5	20.7	45.8	0.0	0.0	0.0	0.0	0.0
1041+00.00	TO	1042+00.00	74.4	63.3	58.5	23.3	39.9	0.0	0.0	0.0	0.0	0.0
1042+00.00	TO	1043+00.00	68.7	58.4	58.5	30.9	27.5	0.0	0.0	0.0	0.0	0.0
1043+00.00	TO	1044+00.00	67.8	57.6	58.3	33.1	24.5	0.0	0.0	0.0	0.0	0.0
1044+00.00	TO	1045+00.00	66.5	56.5	58.3	31.5	25.0	0.0	0.0	0.0	0.0	0.0
1045+00.00	TO	1046+00.00	67.0	57.0	58.5	26.7	30.3	0.0	0.0	0.0	0.0	0.0
1046+00.00	TO	1047+00.00	71.9	61.1	58.5	18.3	42.7	0.0	0.0	0.0	0.0	0.0
1047+00.00	TO	1048+00.00	75.2	63.9	58.5	16.3	47.6	0.0	0.0	0.0	0.0	0.0
1048+00.00	TO	1049+00.00	74.8	63.6	58.5	16.1	47.5	0.0	0.0	0.0	0.0	0.0
1049+00.00	TO	1050+00.00	74.1	63.0	58.5	15.2	47.8	0.0	0.0	0.0	0.0	0.0
1050+00.00	TO	1051+00.00	75.0	63.8	58.5	14.3	49.5	0.0	0.0	0.0	0.0	0.0
1051+00.00	TO	1052+00.00	81.7	69.4	58.5	9.3	60.2	0.0	0.0	0.0	0.0	0.0
1052+00.00	TO	1053+00.00	85.6	72.7	58.5	3.0	69.8	0.0	0.0	0.0	0.0	0.0
1053+00.00	TO	1054+00.00	90.4	76.8	58.5	0.2	76.6	0.0	0.0	0.0	0.0	0.0
1054+00.00	TO	1055+00.00	91.9	78.1	60.4	0.0	78.1	0.0	0.0	0.0	0.0	0.0
1055+00.00	TO	1056+00.00	86.3	73.4	62.2	0.2	73.2	0.0	0.0	0.0	0.0	0.0
1056+00.00	TO	1057+00.00	81.1	68.9	62.8	2.6	66.4	0.0	0.0	11.9	8.1	-8.1
1057+00.00	TO	1057+30.00	23.2	19.7	19.0	1.5	18.2	0.0	0.0	8.1	6.3	-6.3
1057+30.00	TO	1057+60.00	0.0	0.0	0.0	0.0	0.0	0.0	0.0	8.7	7.1	-7.1
1057+60.00	TO	1058+00.00	34.1	29.0	25.0	0.5	28.5	0.0	0.0	5.6	4.3	-4.3
1058+00.00	TO	1059+00.00	90.7	77.1	62.0	0.0	77.1	0.0	0.0	0.0	0.0	0.0
1059+00.00	TO	1060+00.00	82.6	70.2	60.2	8.1	62.1	0.0	0.0	0.0	0.0	0.0
1060+00.00	TO	1061+00.00	70.9	60.3	58.5	17.2	43.1	0.0	0.0	0.0	0.0	0.0
1061+00.00	TO	1062+00.00	69.8	59.3	58.5	18.0	41.4	0.0	0.0	0.0	0.0	0.0
1062+00.00	TO	1063+00.00	68.1	57.9	61.5	16.3	41.6	0.0	0.0	0.0	0.0	0.0
1063+00.00	TO	1064+00.00	70.4	59.8	63.7	9.6	50.2	44.4	37.8	45.6	0.4	37.4
1064+00.00	TO	1065+00.00	84.4	71.8	60.7	2.4	69.4	139.6	118.7	101.3	13.3	105.4
1065+00.00	TO	1066+00.00	115.2	97.9	58.5	0.2	97.7	203.9	173.3	112.4	15.6	157.8
1066+00.00	TO	1066+60.00	95.0	80.8	35.1	0.0	80.8	138.0	117.3	56.3	5.3	112.0
1066+60.00	TO	1067+00.00	36.1	30.7	11.7	0.0	30.7	78.9	67.1	35.1	3.0	64.0
1067+00.00	TO	1068+00.00	0.0	0.0	0.0	0.0	0.0	161.1	136.9	94.8	8.9	128.1
TOTALS			14,642	12,446	11,117	2,259	10,187	3,417	2,904	1,917	514	2,390

SUMMARY						
STAGE	20200100	20201200	20400800			
	EARTH EXCAVATION	EARTH EXCAVATION VOLUME USED (15% SHRINKAGE)	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)	FURNISHED EXCAVATION
1	14,642	12,446	11,117	2,259	10,187	0
2	3,417	2,904	1,917	514	2,390	0
TOTAL	18,059	15,350	13,034	2,773	12,577	0

n:\p\o\1335\13_eest\design\m\cshreets\3084E-EK_sched04.dgn