EAST CONTRACT SIGN SCHEDULE

SIGN NO.	STATION	LEGEND/DESCRIPTION	EXISTING PANEL DIMENSIONS WIDTH (FT)	EXISTING PANEL DIMENSIONS HEIGHT (FT)	PROPOSED PANEL DIMENSIONS WIDTH (FT)	PROPOSED PANEL DIMENSIONS HEIGHT (FT)	72000100 SIGN PANEL TYPE 1 (SQ FT)	72000200 SIGN PANEL TYPE 2 (SQ FT)	72000300 SIGN PANEL TYPE 3 (SQ FT)	72400100 REMOVE SIGN PANEL ASSEMBLY - TYPE A (EACH)	72400200 REMOVE SIGN PANEL ASSEMBLY - TYPE B (EACH)	72400330 REMOVE SIGN PANEL - TYPE 3 (SQ FT)	72600100 MILE POST MARKER ASSEMBLY (EACH)	72800100 TELESCOPING STEEL SIGN SUPPORT (FOOT)	73000100 WOOD SIGN SUPPORT POST 1 (FOOT)	73000100 WOOD SIGN SUPPORT POST 2 (FOOT)	73100100 BASE FOR TELESCOPING STEEL SIGN SUPPORT (EACH)	X0300247 REMOVE WOOD POST (EACH)	84200600 REMOVAL OF SIGN LIGHTING, NO SALVAGE (EACH)
EB-WP-01a	883+45	SPEED / LIMIT/ 65	4.0	5.0	4.0	5.0		20.0			1.0				22.0				
EB-WP-01b	883+45	MINIMUM / 45	4.0	3.0	4.0	3.0		12.0											
EB-BS-02	888+45	US 45 5 / INDIANA STATE LINE 22 / TOLDEO 246	10.0	8.0	17.0	6.0			102.0			80.0							
EB-WP-03	893+15	SLOWER / TRAFFIC / KEEP / RIGHT	3.0	5.0							1.0								
EB-TS-04	898+90	MILE 141 .5			1.0	4.0							1.0						
EB-WP-04a	909+00	TRUCKS / USE/ 2 / RIGHT / LANES			5.0	4.0		20.0							16.0				
EB-BS-05	912+50	WEIGH / STATION / 1 MILE	9.5	6.5	8.0	6.0			48.0			61.8							
EB-BS-06	918+65	A.V.I. TRUCKS / VEHICLES USE RIGHT LANE / PRE-PASS SITE	10.0	7.0	14.5	8.5			123.3			70.0							
EB-BS-07	925+00	A.V.I. TRUCKS / FOLLOW / ONBOARD / SIGNALS	10.0	7.0	14.5	8.0			116.0			70.0							
EB-TS-08	928+00	MILE 142 .0	1.0	4.0	1.0	4.0				1.0			1.0						
EB-WP-09	934+00	EXCESSIVE / ENGINE / BRAKING / NOISE / PROHIBITED / NEXT	4.0	5.0	4.0	5.0		20.0			1.0				19.0				
EB-WP-10	938+10	MAPLE RD	6.0	2.0	6.0	2.0		12.0			1.0				16.0	18.0			
EB-TS-11a•	945+95	R3-4	4.0	4.0	4.0	4.0		16.0			1.0			17.0					
EB-TS-11b•	945+95	EXCEPT / AUTHORIZED / VEHICLES	4.0	3.0	4.0	3.0		12.0											
EB-BS-12	946+55	TRUCKS / OVER 8 TONS / MUST WEIGH	12.5	6.5	11.5	6.0			69.0			81.3							
EB-WP-13	950+10	WATCH / FOR / STOPPED / TRUCKS	4.0	4.0	4.0	4.0		16.0			1.0				17.0				
EB-TS-14	954+40	MILE 142 .5			1.0	4.0							1.0						
EB-BS-15	958+00	WEIGH / STATION / NEXT RIGHT	10.5	6.5	9.0	7.5			67.5			68.3							
EB-WP-16	969+00	RAMP / 30 / M.P.H.	4.0	5.0	4.0	5.0		20.0			1.0				18.0	19.0			
EB-OHC-17	969+15	WEIGH / STATION	15.0	6.5	13.0	6.5			84.5			97.5							1.0
EB-WP-18	970+70	RAMP / 30 / M.P.H.	4.0	5.0	4.0	5.0		20.0			1.0				18.0	18.0			
EB-WP-19	972+70	RAMP / 30 / M.P.H.	4.0	5.0	4.0	5.0		20.0			1.0				18.0	18.0			
EB-WP-20•	974+20	WEIGH / STATION	7.5	7.0	7.5	7.0			52.5			52.5			20.0	21.0		1.0	
EB-TS-21	977+95	MILE 143 .0	1.0	4.0	1.0	4.0				1.0			1.0						
EB-WP-22	998+25	W4-1	4.0	4.0	4.0	4.0		16.0			1.0				18.0				
EB-TS-23	1004+35	MILE 143 .5			1.0	4.0							1.0						
EB-WP-24•	1017+10	NOTICE / MOVE OVER - SLOW DOWN / FOR STOPPED EMERGENCY / OR MAINTENANCE VEHICLES / IT•S THE LAW	24.5	11.0	24.5	11.0			269.5			269.5			25.0	28.0		2.0	
EB-BM-25•	1019+85	WOLF RD	5.5	2.0	5.5	2.0		11.0											
EB-WP-25a	1024+00	TRUCKS / USE / 2 / RIGHT / LANES			5.0	4.0		20.0							16.0				
EB-TS-26	1031+50	MILE 144 .0	1.0	4.0	1.0	4.0				1.0			1.0						

• EXISTING SIGN DIMENSIONS NOT AVAILABLE; PROPOSED SIGN DIMENSIONS USED

n:\proj\33841\3.east\design\tr\plan\signing\sch\sign01.dgn

ENGINEERING CONSULTANT
Ciorba Group, Inc.
CONSULTING ENGINEERS
5507 North Cumberland Avenue, Suite 402
Chicago, Illinois 60656
Tel. 773.775.4000 - Fax 773.775.4014
Email chicago@ciorba.com

USER NAME = jkjellman	DESIGNED - CRC	REVISED -
	DRAWN - JMK	REVISED -
PLOT SCALE = 1.0000 ' / IN.	CHECKED - MRJ	REVISED -
PLOT DATE = 12/6/2010	DATE - 10/27/2010	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

F.A.I. 80 FROM NS RAILROAD TO US 45
SIGNING SCHEDULE

SCALE: | SHEET NO. OF SHEETS | STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
80	99(5&5-1) Y-1	WILL	309	111

CONTRACT NO. 60M59

ILLINOIS FED. AID PROJECT