SIGN DETAIL
1:75

SIGN NUMBER	EB-WP-28; STA. 1052+80
WIDTH x HGHT.	7'-0" x 4'-0"
BORDER WIDTH	1.75"
CORNER RADIUS	6"
MOUNTING	Overhead
BACKGROUND	TYPE: Reflective
	COLOR: Green
LEGEND/BORDER	TYPE: Reflective
	COLOR: White / White



FONT:
(1) ClearviewHwy-5-W

Panel Style: guide_exp_advance_a.ssi
M.U.T.C.D.: 2009 Edition

SYMBOL	ROT	X	Y	WID	HT

Panel Style: guide_exp_advance_a.ssi
Dimensions are in inches.tenths

Letter locations are panel edge to lower left corner

LETTER POSITIONS (X)

										LENGTH	SERIES/SIZE
S	t		X	a	v	i	e	r			ClearviewHwy-5-W
12	19.5	23.4	31.3	39.9	47.4	55.4	59.8	68.4		60	8/6.5
U	n	i	v	e	r	s	i	t	y		ClearviewHwy-5-W
8.9	18.2	26.6	30.4	38.2	46.8	52.1	59.6	63.5	68.9	66.2	8/6.5
E	X	I	T	1	4	5					ClearviewHwy-5-W
16.3	21.4	28.3	31.2	47.5	53.7	62.2				51.4	6,8

FILE NAME = N:\PROJ\3384\3_East\Design\Striping_Signing\Signing-details.dgn	DESIGNED - ST	REVISED -	LIN ENGINEERING, LTD. Consulting Engineers Chatham, Illinois Westmont, Illinois	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SIGNING DETAILS
USER NAME = jkjellman	DRAWN - ST	REVISED -			
PLOT DATE = 12/6/2010	CHECKED - FML	REVISED -			
	DATE - 10/2010	REVISED -			

SCALE: N.T.S. SHEET NO. __ OF __ SHEETS STA. _____ TO STA. _____

F.A.-RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
80	99(5&5-1) Y-1	WILL	309	136
		CONTRACT NO. 60M59		
FED. ROAD DIST. NO. _	ILLINOIS	FED. AID PROJECT		