

20100110 - TREE REMOVAL (6 TO 15 UNITS DIAMETER)		
IL RTE 53		
STATION	OFFSET	UNIT
146+63.53	48.91	11
146+84.23	44.35	11
146+89.04	46.50	11
147+18.19	49.19	11
147+41.34	45.17	11
147+64.87	48.70	11
151+56.15	28.12	11
152+53.12	41.35	11
152+86.13	42.65	11
153+22.77	43.07	11
155+89.00	-42.92	11
155+90.55	-43.23	10
156+01.13	-27.69	13
176+55.05	-33.91	13
176+57.38	-39.99	11
176+83.58	-39.91	13
176+90.42	-38.84	11
176+90.67	-42.68	11
177+05.28	-32.78	11
177+16.89	-32.02	11
177+19.31	-32.37	11
177+21.51	-32.00	11
177+26.46	-29.99	11
177+26.77	-37.12	9
177+28.67	-29.66	11
177+29.06	-37.30	9
177+31.33	-42.31	11
177+31.61	-36.57	9
177+35.79	-43.30	13
177+48.94	-42.35	9
177+49.58	-38.29	11
177+51.60	-39.39	9
177+51.61	-42.40	9
177+53.86	-40.17	9
177+54.75	-36.40	11
177+57.14	-43.47	8
177+70.65	-34.91	9
177+78.44	-37.50	10
177+87.26	-39.56	15
177+89.30	-44.30	13
178+89.42	-43.57	11
179+00.89	-39.76	11
180+99.19	-31.32	13
181+89.81	-28.37	11
182+01.69	-28.38	11
183+00.11	-36.99	11
183+03.72	-44.82	11
183+49.29	-26.05	10
188+27.21	-48.51	15
189+55.47	-33.66	7
189+58.42	-30.25	6
189+74.43	-29.70	6
189+86.70	-32.94	9
190+14.08	-32.38	9
190+20.98	-28.95	7
190+47.74	-31.55	9
195+69.40	-46.64	11
195+73.91	-46.61	11

20100110 - TREE REMOVAL (6 TO 15 UNITS DIAMETER)		
IL RTE 53		
STATION	OFFSET	UNIT
196+49.10	-47.59	13
196+53.88	-47.56	13
198+55.64	-39.86	13
198+75.85	-39.15	13
198+97.34	-37.54	13
200+34.46	-36.06	13
204+32.17	-36.99	13
204+90.46	-36.89	13
205+35.92	-37.34	13
205+87.97	-36.37	13
206+45.79	-38.40	13
231+04.82	48.73	13
231+09.23	48.73	13
231+13.94	48.73	13
231+17.61	48.73	13
237+77.27	75.56	13
245+92.39	68.86	15
245+94.79	69.83	15
SUBTOTAL =		3376

20100110 - TREE REMOVAL (6 TO 15 UNITS DIAMETER)		
ARMY TRAIL RD		
STATION	OFFSET	UNIT
15+82.53	-68.08	9
16+16.02	-65.54	9
16+89.54	-65.86	9
SUBTOTAL =		27

20100110 - TREE REMOVAL (6 TO 15 UNITS DIAMETER)		
NORDIC RD		
STATION	OFFSET	UNIT
10+76.76	-22.55	11
10+87.71	-18.71	11
10+94.45	-21.15	11
12+96.61	31.55	11
12+99.09	31.55	11
SUBTOTAL =		55

20100110 - TREE REMOVAL (6 TO 15 UNITS DIAMETER)		
IRVING PARK RD		
STATION	OFFSET	UNIT
10+37.24	-38.82	13
13+01.98	43.48	10
13+13.03	46.13	10
13+14.49	42.95	10
13+61.71	-37.28	13
13+73.55	43.07	13
SUBTOTAL =		69

SUMMARY TABLE	
20100110 - TREE REMOVAL (6 TO 15 UNITS DIAMETER)	
IL RTE 53	3376
ARMY TRAIL RD	27
NORDIC RD	55
IRVING PARK RD	69
TOTAL =	3527 UNITS

NOTE:

THE ORIGINAL TREE SURVEY WAS PERFORMED IN 2001. EACH TREE DIAMETER WAS INCREASED BY 5 UNITS TO ACCOUNT FOR THE INCREASED TREE SIZES. PAYMENT FOR TREE REMOVAL SHALL BE BASED ON THE ACTUAL MEASUREMENT OF THE TREE AT THE TIME OF REMOVAL, AS DEFINED BY ARTICLE 201.10 OF THE STANDARD SPECIFICATIONS.