

SUMMARY OF QUANTITIES				100% STATE						90% STATE	93.3% STATE	93.3% STATE	100% WHEATON	90% STATE	80% STATE	100% STATE	
				ROADWAY FAP 365	ROADWAY NAPERVILLE RD HERRICK RD	ROADWAY CROSS RDS.	IL 56	TRAFFIC SIGNAL INTERCONNECT		5% WHEATON 5% DUPAGE	6-7% WHEATON	6-7% WHEATON	(50% WHEATON 50% WARRENVILLE FOR HERRICK ONLY)	10% DUPAGE	20% DUPAGE	SIGNING	LANDSCAPING
CODE	DESCRIPTION	UNIT	TOTAL QUANTITY	IL 56	DUPAGE CO.	WHEATON	CULVERTS	IL 56 BUTTERFIELD RD	NAPERVILLE RD	TRAF. SIG. HERRICK-WIES. RD	TRAF. SIG. ORCHARD RD	TRAF. SIG. CROWNWELL DR	EMERGENCY VEHICLE PRE-EMPTION	TRAFFIC SIGNALS NAPERVILLE RD	TRAFFIC SIGNALS DANADA SQ.	0021	0001
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1	1													
50104400	CONCRETE HEADWALL REMOVAL	EACH	6	6													
50200100	STRUCTURE EXCAVATION	CU YD	1,098			1,098											
51500100	NAME PLATES	EACH	2			2											
54001001	BOX CULVERT END SECTIONS, CULVERT NO.1	EACH	2			2											
54001002	BOX CULVERT END SECTIONS, CULVERT NO.2	EACH	2			2											
54010404	PRECAST CONCRETE BOX CULVERTS 4' X 4'	FOOT	152			152											
54011003	PRECAST CONCRETE BOX CULVERTS 10' X 3'	FOOT	257			257											
542A0217	PIPE CULVERTS, CLASS A, TYPE 1 12"	FOOT	12	12													
542A0220	PIPE CULVERTS, CLASS A, TYPE 1 15"	FOOT	13	13													
542A0223	PIPE CULVERTS, CLASS A, TYPE 1 18"	FOOT	499	417	82												
542A0226	PIPE CULVERTS, CLASS A, TYPE 1 21"	FOOT	149	149													
542A0229	PIPE CULVERTS, CLASS A, TYPE 1 24"	FOOT	151	151													
542A0235	PIPE CULVERTS, CLASS A, TYPE 1 30"	FOOT	7	7													
542A1060	PIPE CULVERTS, CLASS A, TYPE 2 15"	FOOT	237	237													
542A1063	PIPE CULVERTS, CLASS A, TYPE 2 18"	FOOT	564	564													
542A1069	PIPE CULVERTS, CLASS A, TYPE 2 24"	FOOT	537	537													
542A1072	PIPE CULVERTS, CLASS A, TYPE 2 27"	FOOT	196	196													
542A5479	PIPE CULVERTS, CLASS A, TYPE 1 EQUIVALENT ROUND-SIZE 24"	FOOT	139	139													
542A5491	PIPE CULVERTS, CLASS A, TYPE 1 EQUIVALENT ROUND-SIZE 36"	FOOT	279	279													
542A8203	PIPE CULVERTS, CLASS A, TYPE 2 EQUIVALENT ROUND-SIZE 18"	FOOT	33	33													
542C0215	PIPE CULVERTS, CLASS C, TYPE 1 10"	FOOT	46	46													
54213655	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 10"	EACH	4	4													
54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	33	33													
54213660	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 15"	EACH	9	6	1	2											
54213663	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 18"	EACH	25	21	4												
54213666	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 21"	EACH	2	2													
54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	9	9													
54213672	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 27"	EACH	4	4													
54213681	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 36"	EACH	2	2													
54214503	PRECAST REINFORCED CONCRETE FLARED END SECTIONS, EQUIVALENT ROUND-SIZE 18"	EACH	1	1													
54214521	PRECAST REINFORCED CONCRETE FLARED END SECTIONS, EQUIVALENT ROUND-SIZE 36"	EACH	4	4													
54216180	REINFORCED CONCRETE PIPE TEE, 12" PIPE WITH 12" RISER	EACH	1	1													
54216190	REINFORCED CONCRETE PIPE TEE, 18" PIPE WITH 12" RISER	EACH	3	3													
54216200	REINFORCED CONCRETE PIPE TEE, 24" PIPE WITH 12" RISER	EACH	1	1													

\* SPECIALTY ITEMS  
 \*\*\* NON-PARTICIPATING ITEM \*\*\*

FILE NAME =	DESIGNED - JMM	REVISED -
...General\0162419-soq-003.dgn	DRAWN - TMB	REVISED -
USER NAME = BENESCH	CHECKED - RMT	REVISED -
PLOT DATE = 12/3/2010	DATE - 12/6/10	REVISED -

**benesch**

**STATE OF ILLINOIS  
 DEPARTMENT OF TRANSPORTATION**

**SUMMARY OF QUANTITIES**

SCALE: N.T.S. SHEET NO. 3 OF 12 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
365	157 & 58WRS-2	DUPAGE	681	7
CONTRACT NO. 62419				
ILLINOIS FED. AID PROJECT				