

SUMMARY OF QUANTITIES				100% STATE						90% STATE	93.3% STATE	93.3% STATE	100% WHEATON	90% STATE	80% STATE	100% STATE	
				ROADWAY FAP 365	ROADWAY NAPERVILLE RD HERRICK RD	ROADWAY CROSS RDS.	IL 56	TRAFFIC SIGNAL INTERCONNECT		5% WHEATON 5% DUPAGE	6.7% WHEATON	6.7% WHEATON	(50% WHEATON 50% WARRENVILLE FOR HERRICK ONLY)	10% DUPAGE	20% DUPAGE	100% STATE	
				IL 56	DUPAGE CO.	WHEATON	CULVERTS	IL 56 BUTTERFIELD RD	NAPERVILLE RD	TRAF. SIG. HERRICK-WIES. RD	TRAF. SIG. ORCHARD RD	TRAF. SIG. CROMWELL DR	EMERGENCY VEHICLE PRE-EMPTION	TRAFFIC SIGNALS NAPERVILLE RD	TRAFFIC SIGNALS DANADA SQ.	SIGNING	LANDSCAPING
CODE	DESCRIPTION	UNIT	TOTAL QUANTITY	0003	0003	0004	0040	0021	0021	0021	0021	0021	0021	0021	0021	0021	
60604400	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.18	FOOT	1,549	640	573	336											
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	5,016	919	4,097												
60608300	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-2.12	FOOT	2,039		2,039												
60619600	CONCRETE MEDIAN, TYPE SB-6.12	SQ FT	22,713	22,713													
60624600	CORRUGATED MEDIAN	SQ FT	200		200												
60625600	ISLAND PAVEMENT (6')	SQ YD	600	83	517												
60625900	P.C.C. RAMPED MEDIAN TERMINAL	EACH	10	4	6												
66600105	FURNISHING AND ERECTING RIGHT OF WAY MARKERS	EACH	148	34	102	12											
66700205	PERMANENT SURVEY MARKERS, TYPE I	EACH	32	15	10	7											
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	24	24													
67100100	MOBILIZATION	L SUM	1	1													
70101700	TRAFFIC CONTROL AND PROTECTION	L SUM	1	1													
X7011005	TRAFFIC CONTROL AND PROTECTION FOR TEMPORARY DETOUR	L SUM	1	1													
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	96	96													
70400100	TEMPORARY CONCRETE BARRIER	FOOT	893	893													
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	845	845													
* 72000100	SIGN PANEL - TYPE 1	SQ FT	1,020	698	157	14										151	
* 72000200	SIGN PANEL - TYPE 2	SQ FT	190	20	60	20											90
* 72400310	REMOVE SIGN PANEL - TYPE 1	SQ FT	639	435	196	8											
* 72400320	REMOVE SIGN PANEL - TYPE 2	SQ FT	92	36	56												
* 72400710	RELOCATE SIGN PANEL - TYPE 1	SQ FT	12	4	8												
* 72800100	TELESCOPING STEEL SIGN SUPPORT	FOOT	437	389	48												
* 72900100	METAL POST - TYPE A	FOOT	1,451	1,136	288	27											
* 73000100	WOOD SIGN SUPPORT	FOOT	159	34	96	29											
* 73100100	BASE FOR TELESCOPING STEEL SIGN SUPPORT	EACH	30	26	4												
* 73700100	REMOVE GROUND-MOUNTED SIGN SUPPORT	EACH	166	115	50	1											
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	4,406	2,884	1,307	215											
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	54,921	40,187	6,776	7,958											
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	26,707	16,374	9,334	999											
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	406	406													
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	5,659	4,307	1,256	96											
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	1,428	1,141	287												
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	943	943													
* 78200530	BARRIER WALL MARKERS, TYPE C	EACH	100	100													
78300100	PAVEMENT MARKING REMOVAL	SQ FT	10,000	10,000													

* SPECIALTY ITEMS
 * NON PARTICIPATING ITEM

FILE NAME =	DESIGNED - JMM	REVISED -
...General\0162419-soq-006.dgn	DRAWN - TMB	REVISED -
USER NAME = BENESCH	CHECKED - RMT	REVISED -
PLOT DATE = 12/3/2010	DATE - 12/6/10	REVISED -

benesch

**STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES

SCALE: N.T.S. SHEET NO. 6 OF 12 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
365	157 & 58WRS-2	DUPAGE	681	10
ILLINOIS FED. AID PROJECT			CONTRACT NO. 62419	