

SUMMARY OF QUANTITIES				100% STATE						90% STATE	93.3% STATE	93.3% STATE	100% WHEATON	90% STATE	90% STATE	100% STATE	
				ROADWAY FAP 365	ROADWAY NAPERVILLE RD HERRICK RD	ROADWAY CROSS RDS.	IL 56	TRAFFIC SIGNAL INTERCONNECT		5% WHEATON 5% DUPAGE	6.7% WHEATON	6.7% WHEATON	(50% WHEATON 50% WARRENVILLE FOR HERRICK ONLY)	10% DUPAGE	20% DUPAGE	SIGNING	LANDSCAPING
CODE	DESCRIPTION	UNIT	TOTAL QUANTITY	IL 56	DUPAGE CO.	WHEATON	CULVERTS	IL 56 BUTTERFIELD RD	NAPERVILLE RD	TRAF. SIG. HERRICK-WIES. RD	TRAF. SIG. ORCHARD RD	TRAF. SIG. CROMWELL DR	EMERGENCY VEHICLE PRE-EMPTION	TRAFFIC SIGNALS NAPERVILLE RD	TRAFFIC SIGNALS DANADA SQ.	0021	0031
X0327001	PERMANENT DITCH CHECK WITH 12" PIPE	EACH	5	5													
50105220	PIPE CULVERT REMOVAL	FOOT	85	85													
Z0062456	TEMPORARY PAVEMENT	SQ YD	8,289	8,289													
X4021000	TEMPORARY ACCESS (PRIVATE ENTRANCE)	EACH	5	5													
X4022000	TEMPORARY ACCESS (COMMERCIAL ENTRANCE)	EACH	15	15													
X4023000	TEMPORARY ACCESS (ROAD)	EACH	11	11													
X5610712	WATER MAIN REMOVAL, 12"	FOOT	6,820	5,900	920												
X5610716	WATER MAIN REMOVAL, 16"	FOOT	480		480												
X7011005	TRAFFIC CONTROL & PROTECTION FOR TEMPORARY DETOUR	L SUM	1	1													
X7030030	REFLECTIVE WET TEMPORARY TAPE TYPE III, 4 INCH	FOOT	228,342	228,342													
X7030040	REFLECTIVE WET TEMPORARY TAPE TYPE III, 6 INCH	FOOT	27,481	27,481													
X7030050	REFLECTIVE WET TEMPORARY TAPE TYPE III, 12 INCH	FOOT	8,602	8,602													
X7030055	REFLECTIVE WET TEMPORARY TAPE TYPE III, 24 INCH	FOOT	1,640	1,640													
X7030025	REFLECTIVE WET TEMPORARY TAPE TYPE III, LETTERS AND SYMBOLS	SQ FT	5,922	5,922													
X7810300	RECESSED REFLECTIVE PAVEMENT MARKER	EACH	179	11	168												
X8050015	SERVICE INSTALLATION - POLE MOUNTED	EACH	5							1	1	1		1	1		
X8620020	UNINTERRUPTIBLE POWER SUPPLY	EACH	5							1	1	1		1	1		
X8710020	FIBER OPTIC CABLE IN CONDUIT, NO. 62.5/125, MM12F SM12F	FOOT	15,672					15,672									
X8730027	ELECTRIC CABLE IN CONDUIT, GROUNDING, NO. 6 1C	FOOT	3,763							660	519	796		1,070	718		
X8730250	ELECTRIC CABLE IN CONDUIT NO. 20 3/C, TWISTED, SHIELDED	FOOT	3,044										3,044				
Z0001056	AGGREGATE SUBGRADE 16"	SQ YD	30,025		30,025												
XX000882	WOODEN FENCE	FOOT	500	500													
Z0033050	COAXIAL CABLE IN CONDUIT	FOOT	843												843		
XX004096	REMOVE AND RE-INSTALL CONCRETE FLARED END SECTIONS	EACH	3	3													
XX006722	TEMPORARY AGGREGATE BERM-COURSE AGGREGATE	TON	450	450													
XX006723	TEMPORARY AGGREGATE BERM - RIPRAP	TON	986	986													
XX006821	CONCRETE TRUCK WASHOUT	L SUM	1	1													
XX008001	AGGREGATE PATH, 8"	SQ YD	1,607	1,607													
Z0001050	AGGREGATE SUBGRADE 12"	SQ YD	161,533	156,984	4,549												
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1													
Z0030240	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 2	EACH	3	3													
Z0030255	IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, NARROW), TEST LEVEL 2	EACH	3	3													
Z0030320	IMPACT ATTENUATORS, RELOCATE (FULLY REDIRECTIVE), TEST LEVEL 2	EACH	3	3													
Z0030340	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 2	EACH	3	3													
Z0064800	SELECTIVE CLEARING	UNIT	25	25													

* SPECIALTY ITEMS
 -NON PARTICIPATING ITEM- <> FOREST PRESERVE DISTRICT OF DUPAGE COUNTY 0021

FILE NAME =	DESIGNED - JMM	REVISED -	benesch	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES			F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
...General\0162419-soq--011.dgn	DRAWN - TMB	REVISED -						365	(57 & 58)WRS-2	DUPAGE	681	15
USER NAME = BENESCH	CHECKED - RMT	REVISED -			SCALE: N.T.S. SHEET NO. 11 OF 12 SHEETS STA. TO STA.			CONTRACT NO. 62419				
PLOT DATE = 12/3/2010	DATE - 12/6/10	REVISED -			ILLINOIS FED. AID PROJECT							