



COORDIANTE DATA

STATION	NORTHING	EASTING	REMARKS
343+60.03	1,880,359.26	1,040,692.62	PC CURVE 6 IL. RTE. 56
344+29.77	1,880,347.91	1,040,761.42	POT IL. RTE. 56 (STA. 900+00.00 ORCHARD RD)
357+68.91	1,880,249.55	1,042,095.32	PT CURVE 6 IL. RTE. 56
370+61.40	1,880,264.80	1,043,387.72	POT IL. RTE. 56 (STA. 10000+00.00 CROMWELL DR)
900+00.00	1,880,347.68	1,040,762.90	POT STA. 900+00.00 ORCHARD RD (STA. 344+31.27 IL. RTE. 56)
907+68.18	1,881,115.83	1,040,756.74	POT ORCHARD RD
909+42.98	1,881,290.61	1,040,754.13	POT ORCHARD RD
10000+00.00	1,880,264.80	1,043,387.72	POT CROMWELL DR (STA. 370+61.40 IL. RTE. 56)
10003+54.95	1,880,619.75	1,043,387.00	POT CROMWELL DR

CURVE DATA

CURVE	P.I. STATION	Δ	D	T	L	R	E	PC STATION	PT STATION	M	CHORD
IL. RTE. 56 CURVE 6	350+66.38	10° 17' 47" (LT)	0° 43' 51"	706.34'	1,408.88'	7,840.00'	31.75'	343+60.03	357+68.91	31.63'	1,406.98'

FILE NAME =	DESIGNED - JMM	REVISED -
...\\DIG2419-shr-9BT2.dgn	DRAWN - TMB	REVISED -
USER NAME = tbleak	CHECKED - RMT	REVISED -
PLOT DATE = 12/7/2010	DATE - 12/6/10	REVISED -

benesch

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

ALIGNMENT PLAN

SCALE: 1"=250' SHEET NO. 2 OF 4 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
365	(57 & 58)WRS-2	DUPAGE	681	40
CONTRACT NO. 62419			ILLINOIS FED. AID PROJECT	