

TEMPORARY DRAINAGE SCHEDULE - TEMPORARY STRUCTURES AND STORM SEWER

STRUCTURE	TEMPORARY CONDITION		RIM ELEVATION	X0323236 *	550A0050	X0323221
	STATION	OFFSET		TEMPORARY INLET (EA)	STORM SEWERS, CLASS A, TYPE 1, 12" (FOOT)	PLUG AND ABANDON EXISTING PIPE (CY)
TEMP 25850	258+50	6' RT	758.35	1		
TEMP 32100	321+00	0	746.6	1		
TEMP 33900	339+00	5.4' RT	744.75	1	72	2.1
TEMP 34250	342+50	3.7' LT	743.0	1		
TEMP 36700	367+00	3.8' LT	752.15	1		
TEMP 37700	377+00	5.75' RT	757.0	1		
TEMP 38204	382+04	5' RT	759.0	1	5	
TEMP 38500	385+50	10' RT	760.75	1		
TEMP 39550	395+50	12.5' RT	760.5	1		
TEMP 2780	11027+80	1.5 RT	MATCH PVMT	1	163*	
TEMP 3030	11030+30	1.1 RT	MATCH PVMT	1	30*	
TEMP 3155	11031+55	1.5 RT	MATCH PVMT	1	26*	
TEMP 3260	11032+60	1.8 RT	MATCH PVMT	1	40*	
TEMP 3424	11034+24	1.3 RT	MATCH PVMT	1	24*	
TEMP 3576	11035+76	0	MATCH PVMT	1	24*	
TEMP 3690	11036+90	8 LT	MATCH PVMT	1	10*	
TOTAL				16	394	2.1

* REMOVE IN STAGE 2. QUANTITIES FOR TEMPORARY STORM SEWER IS PAID FOR IN PAY ITEMS FOR INSTALLATION AND REMOVAL

STATION	X0322463*
	TEMPORARY CONNECTION TO EXISTING STORM SEWER (EA)
261+93	1
280+00	1
326+00	1
337+50	1
348+37	1
372+50	1
382+10	2
11021+30	1
11027+80	3*
11030+30	2*
11034+55	2*
11032+60	2*
11034+24	2*
11035+76	2*
11036+90	2*
TOTAL	24

*MULTIPLE CONNECTIONS OF NEW AND EXISTING SEWER TO TEMPORARY STORM SEWER AND INLET

STATION	X0322208
	TEMPORARY STORM SEWER PLUG (EA)
286+00	1
290+00	1
303+00	1
322+50	1
327+00	1
346+00	1
347+00	1
359+00	1
363+00	1
372+30	2
390+00	1
399+00	1
401+50	1
403+00	1
404+50	1
406+50	1
408+00	1
410+00	1
413+00	1
11011+00	1
11012+50	1
11016+00	1
11018+00	1
TOTAL	24

TEMPORARY DRAINAGE SCHEDULE - PERMANENT STRUCTURES

STRUCTURE NUMBER	PERMANENT CONDITION			TEMPORARY CONDITION	60250200	60252800
	STATION	OFFSET	PROPOSED RIM ELEVATION	TEMPORARY RIM ELEVATION	CATCH BASIN TO BE ADJUSTED (EA)	CATCH BASIN TO BE RECONSTRUCTED (EA)
S-26166	261+66	0	758.53	757.32	1	
S-27707	277+07	0	761.39	759.00		1
S-29700	297+00	0	760.88	758.15		1
S-30000	300+00	3.6' RT	755.99	754.40	1	
S-31650	316+50	0	749.19	745.75		1
S-35000A	350+00	2.7' RT	745.11	742.25		1
S-35450A	354+50	0	747.61	745.00		1
S-37260	372+60	1.6' LT	757.27	754.50		1
TOTAL					2	6

STATION	TEMPORARY BOX CULVERT PLUG (EA)
349+00	2
TOTAL	2