

SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	CONSTRUCTION TYPE CODE													
			URBAN	NHF			CMF			NHF			0043			
			TOTAL QUANTITIES	0003 ROADWAY IL. RTE. 56 80% FEDERAL 20% STATE	0004 FERRY CREEK CULVERT 80% FEDERAL 20% STATE	0010 DUPAGE RIVER BRIDGE 80% FEDERAL 20% STATE	0014 PRAIRIE PATH BRIDGE 80% FEDERAL 20% STATE	0021 T.S. AT IL. RTE. 59 80% FEDERAL 20% STATE	0021 T.S. AT BATAVIA RD. 80% FEDERAL 10% STATE 10% C.O.W.	0021 T.S. AT WINFIELD RD. 80% FEDERAL 10% STATE 10% DuPAGE	0021 INTERCONNECT IL. RTE. 56 80% FEDERAL 20% STATE	0021 ROADWAY LIGHTING 80% FEDERAL 20% STATE	0021 SIGNING 80% FEDERAL 20% STATE	0031 LANDSCAPE 80% FEDERAL 20% STATE	100% CITY OF WARRENVILLE	
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	1,404	1,404												
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	859	859												
20100500	TREE REMOVAL, ACRES	ACRE	6.7	6.7												
20101000	TEMPORARY FENCE	FOOT	4,000	4,000												
20101300	TREE PRUNING (1 TO 10 INCH DIAMETER)	EACH	75												75	
20101350	TREE PRUNING (OVER 10 INCH DIAMETER)	EACH	75												75	
20200100	EARTH EXCAVATION	CU YD	82,252	82,252												
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	80,656	79,056												1,600
20400800	FURNISHED EXCAVATION	CU YD	6,289	6,289												
20800150	TRENCH BACKFILL	CU YD	6,841	6,741												
* 21101625	TOPSOIL FURNISH AND PLACE, 6"	SQ YD	26,421												26,421	
* 21101630	TOPSOIL FURNISH AND PLACE, 8"	SQ YD	132,642												132,642	
* 21101645	TOPSOIL FURNISH AND PLACE, 12"	SQ YD	6,770												6,770	
* 21101685	TOPSOIL FURNISH AND PLACE, 24"	SQ YD	23,700												23,700	
* 21101805	COMPOST FURNISH AND PLACE, 2"	SQ YD	26,421												26,421	
* 21101815	COMPOST FURNISH AND PLACE, 4"	SQ YD	6,770												6,770	
* 21301072	EXPLORATION TRENCH 72" DEPTH	FOOT	200	200												
* 25000210	SEEDING, CLASS 2A	ACRE	22.6												22.6	
* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	3,900												3,900	
* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	3,900												3,900	
* Δ 25000750	MOWING	ACRE	20.0												20.0	
* 25100105	MULCH, METHOD 1	ACRE	4.0												4.0	
* 25100115	MULCH, METHOD 2	ACRE	36.0												36.0	
* 25100630	EROSION CONTROL BLANKET	SQ YD	156,290												156,290	
* 25100900	TURF REINFORCEMENT MAT	SQ YD	600												600	
* 25200110	SODDING, SALT TOLERANT	SQ YD	4,468												4,468	
* 25200200	SUPPLEMENTAL WATERING	UNIT	120												120	
28000200	EARTH EXCAVATION FOR EROSION CONTROL	CU YD	300	300												
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	40,000	40,000												
28000305	TEMPORARY DITCH CHECKS	FOOT	4,860	4,860												
28000400	PERIMETER EROSION BARRIER	FOOT	8,000	8,000												
28000500	INLET AND PIPE PROTECTION	EACH	480	480												
28001000	AGGREGATE (EROSION CONTROL)	TON	276	276												
28100101	STONE RIPRAP, CLASS A1	SQ YD	2,085	2,085												
28100103	STONE RIPRAP, CLASS A2	SQ YD	27	27												
28100105	STONE RIPRAP, CLASS A3	SQ YD	76	76												
28100107	STONE RIPRAP, CLASS A4	SQ YD	2,085	2,085												
28200200	FILTER FABRIC	SQ YD	2,188	2,188												
28300400	AGGREGATE DITCH	TON	500	500												
31101900	SUB BASE GRANULAR MATERIAL, TYPE C	TON	5,560	5,560												

* SPECIALTY ITEM Δ NON-PARTICIPATING

FILE NAME = 0162428-shr-500.dgn
 PLOT DATE = 12/3/2010
 PLOT SCALE = 50.0000' / IN.

CR
ENGINEERS-PLANNERS-SURVEYORS
 211 WEST WACKER DRIVE
 CHICAGO, ILLINOIS 60606
 PHONE: (312)372-2023 FAX: (312)372-5274

DESIGNED - S.J.P.	REVISED -
DRAWN - A.C.S.	REVISED -
CHECKED - M.P.	REVISED -
DATE - DECEMBER 3, 2010	REVISED -

**STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION**

**SUMMARY OF QUANTITIES
 IL. RTE. 56**

SCALE: NONE SHEET NO. 1 OF 12 SHEETS STA. 90+00 TO STA. 255+00

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
365	(58&59) WRS-3	DuPAGE	466	5
CONTRACT NO. 62420				
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				

Rev.