

SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	CONSTRUCTION TYPE CODE															
			URBAN	NHF			CMF			CONSTRUCTION TYPE CODE				NHF			CMF	
			TOTAL QUANTITIES	0003 ROADWAY IL. RTE. 56	0004 FERRY CREEK CULVERT	0010 DUPAGE RIVER BRIDGE	0014 PRAIRIE PATH BRIDGE	0021 T.S. AT IL. RTE. 59	0021 T.S. AT BATAVIA RD. 80% FEDERAL 10% STATE 10% C.O.W.	0021 T.S. AT WINFIELD RD. 80% FEDERAL 10% STATE 10% DUPAGE	0021 INTERCONNECT IL. RTE. 56	0021 ROADWAY LIGHTING	0021 SIGNING	0031 LANDSCAPE	0043			
35101800	AGGREGATE BASE COURSE, TYPE B 6"	SQ YD	7,582															80% FED. 10% STATE 10% WARRENVILLE
35300700	PORTLAND CEMENT CONCRETE BASE COURSE 12"	SQ YD	177	177														
35501308	HOT-MIX ASPHALT BASE COURSE, 6"	SQ YD	1,370	1,370														
35501316	HOT-MIX ASPHALT BASE COURSE, 8"	SQ YD	3,177	3,177														
40200710	AGGREGATE SURFACE COURSE, TYPE A 10"	SQ YD	333	333														
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	234	234														
40600300	AGGREGATE (PRIME COAT)	TON	1,233	1,233														
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	174	174														
40600895	CONSTRUCTING TEST STRIP	EACH	4	4														
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	88	88														
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	85	85														
40603080	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	TON	850															850
40603090	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N90	TON	86,295	86,295														
40603148	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, STONE MATRIX ASPHALT, N80	TON	17,255	17,255														
40603153	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, STONE MATRIX ASPHALT, N80	TON	17,471	17,471														
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	1,389	509														850
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	1,730	1,730														
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	250	250														
42001300	PROTECTIVE COAT	SQ YD	22,951	22,951														
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	123	123														
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	27,110	27,110														
42400800	DETECTABLE WARNINGS	SQ FT	856	856														
44000100	PAVEMENT REMOVAL	SQ YD	99,944	99,944														
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SQ YD	1,259	1,259														
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	5,449	5,449														
44000300	CURB REMOVAL	FOOT	1,340	1,340														
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	15,346	15,346														
44000600	SIDEWALK REMOVAL	SQ FT	15,312	15,312														
44002216	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 4"	SQ YD	375	375														
44003100	MEDIAN REMOVAL	SQ FT	33,016	33,016														
44004250	PAVED SHOULDER REMOVAL	SQ YD	25,447	25,447														
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SQ YD	200	200														
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SQ YD	100	100														
44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SQ YD	230	230														
48101200	AGGREGATE SHOULDERS, TYPE B	TON	1,572	1,572														
48203053	HOT-MIX ASPHALT SHOULDERS, 14"	SQ YD	24,187	24,187														
50100300	REMOVAL OF EXISTING STRUCTURES NO. 1	EACH	1		1													
50100400	REMOVAL OF EXISTING STRUCTURES NO. 2	EACH	1			1												
50102400	CONCRETE REMOVAL	CU YD	8.6					8.6										
50104400	CONCRETE HEADWALL REMOVAL	EACH	2	2														
50105220	PIPE CULVERT REMOVAL	FOOT	603	603														

* SPECIALTY ITEM

FILE NAME = D:\62420\ah-500.dgn
 PLOT DATE = 12/3/2010
 PLOT SCALE = 50.0000 / 1 IN.

CHRISTIAN-ROGE & ASSOCIATES, INC.
 ENGINEERS-PLANNERS-SURVEYORS
 211 WEST WACKER DRIVE
 CHICAGO, ILLINOIS 60606
 PHONE: (312)372-2023 FAX: (312)372-5274

DESIGNED - S.J.P.	REVISED -
DRAWN - A.C.S.	REVISED -
CHECKED - M.P.	REVISED -
DATE - DECEMBER 3, 2010	REVISED -

**STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION**

**SUMMARY OF QUANTITIES
 IL. RTE. 56**

SCALE: NONE SHEET NO. 2 OF 12 SHEETS STA. 90+00 TO STA. 255+00

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
365	(58&59) WRS-3	DuPAGE	466	6
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT			CONTRACT NO. 62420	

Rev