

# SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	CONSTRUCTION TYPE CODE													
			URBAN		NHF		CMF		NHF		NHF		0043			
			TOTAL QUANTITIES	80% FEDERAL 20% STATE	0003 ROADWAY IL. RTE. 56	0004 FERRY CREEK CULVERT	0010 DUPAGE RIVER BRIDGE	0014 PRAIRIE PATH BRIDGE	0021 T.S. AT IL. RTE. 59	0021 T.S. AT BATAVIA RD. 80% FEDERAL 10% STATE 10% C.O.W.	0021 T.S. AT WINFIELD RD. 80% FEDERAL 10% STATE 10% DUPAGE	0021 INTERCONNECT IL. RTE. 56	0021 ROADWAY LIGHTING	0021 SIGNING	0031 LANDSCAPE	100% CITY OF WARRENVILLE
60618740	CONCRETE MEDIAN, TYPE M-2.12	SQ FT	657	657												
60619600	CONCRETE MEDIAN, TYPE SB-6.12	SQ FT	14,171	14,171												
X6060300	CONCRETE MEDIAN, TYPE SB-6.24 (SPECIAL)	SQ FT	11,443	11,443												
60623200	CONCRETE MEDIAN, TYPE SM-6.24	SQ FT	459	459												
60624600	CORRUGATED MEDIAN	SQ FT	2,670	2,670												
* 63000001	STEEL PLATE BEAM GUARD RAIL, TYPE A, 6 FOOT POSTS	FOOT	1,275	1,275												
* 63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	4	4												
* 63100070	TRAFFIC BARRIER TERMINAL, TYPE 5	EACH	4	4												
* 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	4	4												
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	8	8												
63200310	GUARDRAIL REMOVAL	FOOT	3,533	3,533												
66600105	FURNISHING AND ERECTING RIGHT OF WAY MARKERS	EACH	16	16												
66700205	PERMANENT SURVEY MARKERS, TYPE I	EACH	8	8												
66700305	PERMANENT SURVEY MARKERS, TYPE II	EACH	9	9												
* 66900105	UNDERGROUND STORAGE TANK REMOVAL	EACH	1	1												
* 66900200	NON-SPECIAL WASTE DISPOSAL	CU YD	1,205	1,205												
* 66900400	SPECIAL WASTE GROUND WATER DISPOSAL	GALLON	400	400												
* 66900450	SPECIAL WASTE PLANS AND REPORTS	L SUM	1	1												
* 66900530	SOIL DISPOSAL ANALYSIS	EACH	3	3												
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	30	30												
67100100	MOBILIZATION	L SUM	1	1												
X7010216	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	1												
70102550	TRAFFIC CONTROL AND PROTECTION FOR TEMPORARY DETOUR	EACH	2	2												
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	670	670												
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	12	12												
70300100	SHORT TERM PAVEMENT MARKING	FOOT	3,000	3,000												
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	504	504												
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	31,914	31,914												
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	1,720	1,720												
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	144	144												
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1,500	1,500												
70400100	TEMPORARY CONCRETE BARRIER	FOOT	575	575												
* 72000100	SIGN PANEL - TYPE 1	SQ FT	1,524						55	55	57				1,357	
* 72000200	SIGN PANEL - TYPE 2	SQ FT	100						30	30	30				10	
* 72400500	RELOCATE SIGN PANEL ASSEMBLY - TYPE A	EACH	16												16	
* 72400600	RELOCATE SIGN PANEL ASSEMBLY - TYPE B	EACH	8												8	
* 72800100	TELESCOPING STEEL SIGN SUPPORT	FOOT	425												425	
* 72900100	METAL POST - TYPE A	FOOT	1,331												1,331	
* 72900200	METAL POST - TYPE B	FOOT	2,095												2,095	
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	3,240	3,240												

\* SPECIALTY ITEM

FILE NAME = D162428-sh1-500.dgn  
 PLOT DATE = 12/3/2010  
 PLOT SCALE = 50.0000' / 1" IN.

**CR & A**  
**CHRISTIAN-ROGE & ASSOCIATES, INC.**  
 ENGINEERS-PLANNERS-SURVEYORS  
 211 WEST WACKER DRIVE  
 CHICAGO, ILLINOIS 60606  
 PHONE: (312)372-2023 FAX: (312)372-5274

DESIGNED - S.J.P.	REVISED -
DRAWN - A.C.S.	REVISED -
CHECKED - M.P.	REVISED -
DATE - DECEMBER 3, 2010	REVISED -

**STATE OF ILLINOIS  
 DEPARTMENT OF TRANSPORTATION**

**SUMMARY OF QUANTITIES  
 IL. RTE. 56**

SCALE: NONE    SHEET NO. 6 OF 12 SHEETS    STA. 90+00    TO STA. 255+00

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
365	(58&59) WRS-3	DUPAGE	466	10
CONTRACT NO. 62420				

FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT

Rev.