SUMMARY OF QUANTITIES

	CODE NO	ITEM	UNIT	TOTAL QUANTITIES	URBAN 0003 ROADWAY IL. RTE. 56 80% FEDERAL 20% STATE	NHF 0004 FERRY CREEK CULVERT 80% FEDERAL 20% STATE	NHF 0010 DuPAGE RIVER BRIDGE 80% FEDERAL 20% STATE	CMF 0014 PRAIRIE PATH BRIDGE 80% FEDERAL 20% STATE	CMF CONSTRUCTION TYPE CODE 0021 T.S. AT IL. RTE. 59 80% FEDERAL 20% STATE	0021 T.S. AT BATAVIA RD. 80% FEDERAL 10% STATE 10% C.O.W.	0021 T.S. AT WINFIELD RD. 80% FEDERAL 10% STATE 10% DuPAGE	0021 INTERCONNECT IL. RTE. 56 80% FEDERAL 20% STATE	NHF 0021 ROADWAY LIGHTING 80% FEDERAL 20% STATE	0021 SIGNING 80% FEDERAL 20% STATE	0031 LANDSCAPE 80% FEDERAL 20% STATE	0043 100% CITY OF WARRENVILLE
*	84100110	REMOVAL OF TEMPORARY LIGHTING UNIT	EACH	19									19			
*	84200500	REMOVAL OF LIGHTING UNIT, SALVAGE	EACH	12									12			
*	84200804	REMOVAL OF POLE FOUNDATION	EACH	12									12			
*	84500110	REMOVAL OF LIGHTING CONTROLLER	EACH	1									1			
*	84500130	REMOVAL OF LIGHTING CONTROLLER FOUNDATION	EACH	1									1			
*	85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	1								1				
*	85700200	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET	EACH	1							1					
*	85700205	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET, SPECIAL	EACH	1					1							
*	85700300	FULL-ACTUATED CONTROLLER AND TYPE V CABINET	EACH	1						1						
*	86000100	MASTER CONTROLLER	EACH	1								1				
*	86400100	TRANSCEIVER - FIBER OPTIC	EACH	3					1	1	1					
*	87301215	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C	FOOT	6,120					859	2,713	2,548					
*	87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	11,167					2,037	6,222	2,908					
*	87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	12,584					3,241	6,128	3,215					
*	87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	4,065					2,035		2,030					
*	87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	12,285					4,772	2,962	4,551					
*	87301805	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 2C	FOOT	102					42	28	32					
*	87502440	TRAFFIC SIGNAL POST, GALVANIZED STEEL 10 FT.	EACH	2						2						
*	87502480	TRAFFIC SIGNAL POST, GALVANIZED STEEL 14 FT.	EACH	4						4						
*	87502500	TRAFFIC SIGNAL POST, GALVANIZED STEEL 16 FT.	EACH	1							1					
*	87700120	STEEL MAST ARM ASSEMBLY AND POLE, 16 FT.	EACH	5					3		2					
*	87700130	STEEL MAST ARM ASSEMBLY AND POLE, 18 FT.	EACH	2						1	1					
*	87700150	STEEL MAST ARM ASSEMBLY AND POLE, 22 FT.	EACH	1						1						
*	87700170	STEEL MAST ARM ASSEMBLY AND POLE, 26 FT.	EACH	1					1							
*	87700220	STEEL MAST ARM ASSEMBLY AND POLE, 36 FT.	EACH	1						1						
*	87700260	STEEL MAST ARM ASSEMBLY AND POLE, 44 FT.	EACH	2						2						
*	87700330	STEEL MAST ARM ASSEMBLY AND POLE, 56 FT.	EACH	1						1						
*	87700340	STEEL MAST ARM ASSEMBLY AND POLE, 58 FT.	EACH	2							2					
*	87700404	STEEL MAST ARM ASSEMBLY AND POLE, 62 FT.	EACH	1							1					
*	87700408	STEEL MAST ARM ASSEMBLY AND POLE, 64 FT.	EACH	1							1					
*	87700414	STEEL MAST ARM ASSEMBLY AND POLE, 66 FT.	EACH	1							1					
*	87700420	STEEL MAST ARM ASSEMBLY AND POLE, 70 FT.	EACH	1							1					
*	87700428	STEEL MAST ARM ASSEMBLY AND POLE, 74 FT.	EACH	1							1					
*	87704170	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE, 48 FT. (SPECIAL)	EACH	1					1							
*	87704188	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE, 54 FT. (SPECIAL)	EACH	2					2							
*	87704190	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE, 55 FT. (SPECIAL)	EACH	1					1							
*	87800100	CONCRETE FOUNDATION, TYPE A	FOOT	28						24	4					
*	87800150	CONCRETE FOUNDATION, TYPE C	FOOT	12					4	4	4					
*	87800400	CONCRETE FOUNDATION, TYPE E, 30-INCH DIAMETER	FOOT	104					40	34	30					
*	87800415	CONCRETE FOUNDATION, TYPE E, 36-INCH DIAMETER	FOOT	84					58	26						

* SPECIALTY ITEM

FILE NAME =D162420-sht-SOQ.dgn
PLOT DATE =12/3/2010
PLOT SCALE=50.0000 ' / IN.

CHRISTIAN-ROGE & ASSOCIATES, INC.
ENGINEERS-PLANNERS-SURVEYORS
211 WEST WACKER DRIVE
CHICAGO, ILLINOIS 60606
PHONE: (312)372-2023 FAX: (312)372-5274

DESIGNED	-	S.J.P.	REVISED -
DRAWN	-	A.C.S.	REVISED -
CHECKED	-	M.P.	REVISED -
DATE	-	DECEMBER 3, 2010	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES
IL. RTE. 56

SCALE: NONE | SHEET NO. 8 OF 12 SHEETS | STA. 90+00 TO STA. 255+00

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
365	(58&59) WRS-3	DuPAGE	466	12

CONTRACT NO. 62420

FED. ROAD DIST. NO. 1 | ILLINOIS | FED. AID PROJECT