

SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	TOTAL QUANTITIES	CONSTRUCTION TYPE CODE											100% CITY OF WARRENVILLE		
				URBAN	NHF			CMF	CONSTRUCTION TYPE CODE				NHF				
					0003 ROADWAY IL. RTE. 56	0004 FERRY CREEK CULVERT	0010 DUPAGE RIVER BRIDGE	0014 PRAIRIE PATH BRIDGE	0021 T.S. AT IL. RTE. 59	0021 T.S. AT BATAVIA RD. 80% FEDERAL 10% STATE 10% C.O.W.	0021 T.S. AT WINFIELD RD. 80% FEDERAL 10% STATE 10% DUPAGE	0021 INTERCONNECT IL. RTE. 56	0021 ROADWAY LIGHTING	0021 SIGNING		0031 LANDSCAPE	0043
* A2008468	TREE, ULMUS AMERICANA PRINCETON (PRINCETON AMERICAN ELM), 2" CALIPER, BALLED AND BURLAPPED	EACH	49														49
* B2000566	TREE, AMELANCHIER CANADENSIS (SHADBLOW SERVICEBERRY), 6' HEIGHT, SHRUB FORM, BALLED AND BURLAPPED	EACH	14														14
* B2001166	TREE, CERCIS CANADENSIS (EASTERN REDBUD), 6' HEIGHT, CLUMP FORM, BALLED AND BURLAPPED	EACH	17														17
* B2001566	TREE, CRATAEGUS CRUSGALLI (COCKSPUR HAWTHORN), 6' HEIGHT, SHRUB FORM, BALLED AND BURLAPPED	EACH	18														18
* B2001666	TREE, CRATAEGUS CRUSGALLI INERMIS (THORNLESS COCKSPUR HAWTHORN), 6' HEIGHT, SHRUB FORM, BALLED AND BURLAPPED	EACH	19														19
* B2010070	TREE, CLADRASTIS KENTUCKEA (AMERICAN YELLOWWOOD), 2" CALIPER, BALLED AND BURLAPPED	EACH	7														7
* C2003360	SHRUB, HAMAMELIS VIRGINIANA (COMMON WITCHHAZEL), 5' HEIGHT, BALLED AND BURLAPPED	EACH	8														8
* D2002484	EVERGREEN, PINUS FLEXILIS VANDERWOLF'S PYRAMID (VANDERWOLF'S PYRAMID LIMBER PINE), 7' HEIGHT, BALLED AND BURLAPPED	EACH	15														15
* E2002066	VINE-CAMPSIS RADICANS (TRUMPET VINE), 1-GALLON POT	EACH	32														32
* E2015061	VINE-HYDRANGEA ANOMALA SUBSP. PETIOLARIS (CLIMBING HYDRANGEA), 1-GALLON POT	EACH	32														32
* E2021061	VINE-PARTHENOCISSUS QUINQUEFOLIA ENGEL MANNII (ENGELMANNII VIRGINIA CREEPER), 1-GALLON POT	EACH	736														736
* K0012970	PERENNIAL PLANTS, BULB TYPE	UNIT	35														35
* K0013060	PERENNIAL PLANTS, SEDGE MEADOW TYPE, 2" DIAMETER BY 4" DEEP PLUG	UNIT	130														130
* K0026850	PERENNIAL PLANT CARE	SQ YD	3,500													3,500	
* K0028500	SNAG PLACEMENT	EACH	15														15
* K0029626	WEED CONTROL, TEASEL	POUND	1														1
* K0029632	WEED CONTROL, NON-SELECTIVE AND NON-RESIDUAL	GALLON	5														5
* K0029634	WEED CONTROL, PRE-EMERGENT GRANULAR HERBICIDE	POUND	125														125
* K1005863	TREE ROOT PRUNING	EACH	45														45
X6020094	MANHOLES, TYPE A, 6'-DIAMETER, TYPE 1 FRAME, CLOSED LID, RESTRICTOR PLATE	EACH	1		1												
X0301423	NOISE ABATEMENT WALL, GROUND MOUNTED	SQ FT	6,814	6,814													
X6020294	MANHOLES, TYPE A, 7'-DIAMETER, TYPE 1 FRAME, CLOSED LID, RESTRICTOR PLATE	EACH	1		1												
X6020298	MANHOLES, TYPE A, 8'-DIAMETER, TYPE 1 FRAME, CLOSED LID, RESTRICTOR PLATE	EACH	1		1												
X0322943	BRIDGE DECK THIN POLYMER OVERLAY 1/4"	SQ YD	231						231								
X0324097	COARSE SAND PLACEMENT, 2"	SQ YD	6,770													6,770	
X0325751	DRIVING SOLDIER PILES	FOOT	760		760												
60224458	MANHOLES, TYPE A, 8'-DIAMETER, TYPE 8 GRATE	EACH	4		4												
* K1005428	SEEDING, SEDGE MEADOW MIX	ACRE	0.5													0.5	
X0327002	STEEL CASINGS JACKED IN PLACE, 20"	FOOT	125														125
X2010300	TREE REMOVAL (UNDER 6 UNITS DIAMETER)	UNIT	80													80	
X2070304	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	464				464										
* X2501820	SEEDING, CLASS 5 (MODIFIED)	ACRE	1.1													1.1	
* X2502014	SEEDING, CLASS 4A (MODIFIED)	ACRE	9.3													9.3	
* X2502024	SEEDING, CLASS 4B (MODIFIED)	ACRE	1.7													1.7	
* X2503315	INTERSEEDING, CLASS 4A (MODIFIED)	ACRE	5.0													5.0	
* X2510635	HEAVY DUTY EROSION CONTROL BLANKET, SPECIAL	SQ YD	26,421													26,421	
X2800400	PERIMETER EROSION BARRIER, SPECIAL	FOOT	19,175		19,175												
X4021000	TEMPORARY ACCESS (PRIVATE ENTRANCE)	EACH	24		24												
X4022000	TEMPORARY ACCESS (COMMERCIAL ENTRANCE)	EACH	17		17												
X4023000	TEMPORARY ACCESS (ROAD)	EACH	15		15												

* SPECIALTY ITEM

FILE NAME = D162428-8ht-500.dgn
 PLOT DATE = 12/3/2010
 PLOT SCALE = 50.0000' / 1" IN.



DESIGNED - S.J.P.	REVISED -
DRAWN - A.C.S.	REVISED -
CHECKED - M.P.	REVISED -
DATE - DECEMBER 3, 2010	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**SUMMARY OF QUANTITIES
IL. RTE. 56**

SCALE: NONE SHEET NO. 10 OF 12 SHEETS STA. 90+00 TO STA. 255+00

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
365	(58&59) WRS-3	DUPAGE	466	14
CONTRACT NO. 62420				
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				