

SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	CME															
			URBAN	NHF			CME		CONSTRUCTION TYPE CODE						NHF		TE	
			TOTAL QUANTITIES	0003 ROADWAY IL. RTE. 56 80% FEDERAL 20% STATE	0004 FERRY CREEK CULVERT 80% FEDERAL 20% STATE	0010 DUPAGE RIVER BRIDGE 80% FEDERAL 20% STATE	0014 PRAIRIE PATH BRIDGE 80% FEDERAL 20% STATE	0021 T.S. AT IL. RTE. 59 80% FEDERAL 20% STATE	0021 T.S. AT BATAVIA RD. 80% FEDERAL 10% STATE 10% C.O.W.	0021 T.S. AT WINFIELD RD. 80% FEDERAL 10% STATE 10% DUPAGE	0021 INTERCONNECT IL. RTE. 56 80% FEDERAL 20% STATE	0021 ROADWAY LIGHTING 80% FEDERAL 20% STATE	0021 SIGNING 80% FEDERAL 20% STATE	0031 LANDSCAPE 80% FEDERAL 20% STATE	0043 80% FEDERAL 20% STATE WARRENVILLE			
*4066685	TEST STRIP (STONE MATRIX ASPHALT)	EACH	4	4														
X4240430	PORTLAND CEMENT CONCRETE SIDEWALK, 5 INCH, SPECIAL	SQ FT	2,120															2,120
X5015200	REMOVE EXISTING CULVERTS	EACH	1	1														
X5020501	UNDERWATER STRUCTURE EXCAVATION PROTECTION - LOCATION 1	EACH	1															
X5537800	STORM SEWERS TO BE CLEANED 12"	FOOT	100	100														
X5537900	STORM SEWERS TO BE CLEANED 15"	FOOT	719	719														
X5538000	STORM SEWERS TO BE CLEANED 18"	FOOT	224	224														
X5538200	STORM SEWERS TO BE CLEANED 24"	FOOT	891	891														
X6020088	MANHOLES, TYPE A, 8'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	4	4														
X7030030	REFLECTIVE WET TEMPORARY TAPE, TYPE III, 4 INCH	FOOT	92,650	92,650														
X7030040	REFLECTIVE WET TEMPORARY TAPE, TYPE III, 6 INCH	FOOT	4,473	4,473														
X7030025	REFLECTIVE WET TEMPORARY TAPE, TYPE III-LETTERS AND SYMBOLS	SQ FT	1,920	1,920														
X7030055	REFLECTIVE WET TEMPORARY TAPE, TYPE III, 24 INCH	FOOT	842	842														
* X7810300	RECESSED REFLECTIVE PAVEMENT MARKER	EACH	263	263														
* X8050015	SERVICE INSTALLATION - POLE MOUNTED	EACH	3						1	1	1							
* X8250085	LIGHTING CONTROLLER, DUPLEX CONSOLE TYPE	EACH	1										1					
* X8620020	UNINTERRUPTIBLE POWER SUPPLY	EACH	3						1	1	1							
* X8710020	FIBER OPTIC CABLE IN CONDUIT, NO. 62.5/125, MM12F SM12F	FOOT	6,774										6,774					
* X8730027	ELECTRIC CABLE IN CONDUIT, GROUNDING, NO. 6-1C	FOOT	3,349						963	1,460	986							
* X8730320	ELECTRIC CABLE IN CONDUIT, NO. 20 3/C, TWISTED, SHIELDED SIGNAL	FOOT	3,922						1,144	1,662	1,116							
* XX005920	SEEDING WET PRAIRIE	ACRE	3.3														3.3	
* XX006144	SEEDING, MESIC PRAIRIE	ACRE	1.3														1.3	
Z0001050	AGGREGATE SUBGRADE 12"	SQ YD	192,481	192,481														
Z0001900	ASBESTOS BEARING PAD REMOVAL	EACH	68			68												
Z0004552	APPROACH SLAB REMOVAL	SQ YD	653	653														
Z0007118	UNTREATED TIMBER LAGGING	SQ FT	1,200	1,200														
Z0007430	TEMPORARY SIDEWALK	SQ FT	10,292	10,292														
Z0012100	CONCRETE BRIDGE DECK SCARIFICATION (1/4 INCH)	SQ YD	231					231										
Z0012754	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SQ FT	11					11										
Z0012755	STRUCTURAL REPAIR OF CONCRETE (DEPTH GREATER THAN 5 INCHES)	SQ FT	1					1										
Z0013797	STABILIZED CONSTRUCTION ENTRANCE	SQ YD	200	200														
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1														
Z0016001	DECK SLAB REPAIR (FULL DEPTH, TYPE I)	SQ YD	1					1										
Z0016002	DECK SLAB REPAIR (FULL DEPTH, TYPE II)	SQ YD	1					1										
Z0018002	DRAINAGE SCUPPERS, DS-11	EACH	4			4												
Z0024478	FLEXIBLE DELINEATORS	EACH	10	10														
Z0026402	FURNISHING SOLDIER PILES (HP SECTION)	FOOT	760	760														
Z0026407	TEMPORARY SHEET PILING	SQ FT	4,400	3,150	750	500												
Z0030240	IMPACT ATTENUATORS, TEMPORARY (NON- REDIRECTIVE), TEST LEVEL 2	EACH	4	4														
* Z0030850	TEMPORARY INFORMATION SIGNING	SQ FT	398	398														

* SPECIALTY ITEM

FILE NAME = D162420-sh1-500.dgn
 PLOT DATE = 12/3/2010
 PLOT SCALE = 50.0000 1/1 IN.

CHRISTIAN-ROGE & ASSOCIATES, INC.
 ENGINEERS-PLANNERS-SURVEYORS
 211 WEST WACKER DRIVE
 CHICAGO, ILLINOIS 60606
 PHONE: (312)372-2023 FAX: (312)372-5274

DESIGNED - S.J.P.	REVISED -
DRAWN - A.C.S.	REVISED -
CHECKED - M.P.	REVISED -
DATE - DECEMBER 3, 2010	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**SUMMARY OF QUANTITIES
IL. RTE. 56**

SCALE: NONE SHEET NO. 11 OF 12 SHEETS STA. 90+00 TO STA. 255+00

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
365	(58&59) WRS-3	DUPAGE	466	15
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT			CONTRACT NO. 62420	