



**PROPOSED LEGEND**

- ① HMA PAVEMENT (FULL DEPTH), 14"
- ② NOT USED
- ③ AGGREGATE SUBGRADE, 12"
- ④ HOT MIX ASPHALT SHOULDERS, 14"
- ⑤ COMBINATION CONCRETE CURB & GUTTER, TYPE B-6.24
- ⑤A COMBINATION CONCRETE CURB & GUTTER, TYPE B-6.12
- ⑥ FURNISHING & PLACING TOPSOIL, 8"
- ⑥A FURNISHING & PLACING TOPSOIL, 24"
- ⑦ SEE LANDSCAPING PLANS FOR SEEDING AND SODDING LIMITS
- ⑧ HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50, 1 1/2" HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50, 2 1/2" AGGREGATE BASE COURSE, TYPE A, 6"
- ⑨ AG SEE NOTES 1 & 2. TYPE B, 8" (2' WIDTH)
- ⑩ PIPE UNDERDRAINS, 4"
- ⑪ NOT USED
- ⑫ NOT USED
- ⑬ NOT USED

**NOTES:**

- 1. SEE PLANS FOR TYPE OF SOLID BARRIER MEDIAN.
- 2. CONCRETE MEDIAN TYPE SB-6.24 (SPECIAL) SHALL CONSIST OF A 12" AND 24" GUTTER FLAG WITH A 6" BARRIER CURB. THE 24" GUTTER FLAG SHALL BE PLACED ON THE GUTTER CONVEYANCE SIDE OF THE MEDIAN. THIS WORK SHALL BE IN ACCORDANCE WITH SECTION 606 AND STANDARD 606306.

FILE NAME = D162420-shr-typical5.dgn  
 PLOT DATE = 12/2/2010  
 PLOT SCALE = 1/8" = 1' IN.

**CHRISTIAN-ROGE & ASSOCIATES, INC.**  
 ENGINEERS-PLANNERS-SURVEYORS  
 211 WEST WACKER DRIVE  
 CHICAGO, ILLINOIS 60606  
 PHONE: (312)372-2023 FAX: (312)372-5274

DESIGNED - D.L.	REVISED -
DRAWN - B.K.	REVISED -
CHECKED - M.P.	REVISED -
DATE - DECEMBER 3, 2010	REVISED -

**STATE OF ILLINOIS**  
**DEPARTMENT OF TRANSPORTATION**

**PROPOSED TYPICAL SECTION DETAILS**  
**IL RTE. 56**

SCALE: NONE SHEET NO. 1 OF 1 SHEETS STA. TO STA.

F.A.P. RTE. 365	SECTION (58&59) WRS-3	COUNTY DuPAGE	TOTAL SHEETS 466	SHEET NO. 21
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				CONTRACT NO. 62420