



NOTES:
 1. ALL TEMPORARY PAVEMENT MARKINGS ON NEW PAVEMENT OR ON EXISTING PAVEMENT NOT BEING RESURFACED SHALL BE WET REFLECTIVE TAPE, TYPE III OF THE COLOR AND SIZE NOTED ON THE PLANS

LEGEND

- (A) SOLID WHITE LINE, 4"
- (B) (NOT USED)
- (C) (NOT USED)
- (D) SOLID YELLOW LINE, 4"
- (E) 4" YELLOW DIAGONALS @ 20' CTRS.
- (F) 6" WHITE SKIP-DASH LINE, 2' DASH & 6' SPACE
- (G) 2 - 4" YELLOW LINES @ 11" c-c. WITH 2 TEMPORARY PAVEMENT MARKERS @ 40' c-c.
- (H) LEFT TURN ARROW "↶" AND WORD "ONLY"
- (I) SOLID WHITE LINE, 6"

LEGEND

- WORK AREA
- TRAFFIC LANE
- TEMPORARY PAVEMENT
- VERTICAL PANELS @ 50' INTERVALS UNLESS OTHERWISE SHOWN
- TEMPORARY SIGNS
- DRUMS @ 50' INTERVALS UNLESS OTHERWISE SHOWN
- PAVEMENT MARKING REMOVAL

FILE NAME = D162428-sh1-mot3-wr.dgn
 PLOT DATE = 12/2/2010
 PLOT SCALE = 50.000' / IN.

CHRISTIAN-ROGE & ASSOCIATES, INC.
 ENGINEERS-PLANNERS-SURVEYORS
 211 WEST WACKER DRIVE
 CHICAGO, ILLINOIS 60606
 PHONE: (312)372-2023 FAX: (312)372-5274

DESIGNED - S.J.P.	REVISED -
DRAWN - B.K.	REVISED -
CHECKED - E.J.M.	REVISED -
DATE - DECEMBER 3, 2010	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUGGESTED TRAFFIC CONTROL AND PROTECTION - STAGE III
WINFIELD ROAD

SCALE: 1" = 50' SHEET NO. 1 OF 1 SHEETS STA. 709+55 TO STA. 733+65

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
365	(58&59) WRS-3	DuPAGE	466	56
CONTRACT NO. 62420				
FED. ROAD DIST. NO. 1 [ILLINOIS] FED. AID PROJECT				