



FILE NAME = D162420-sh1-e01-4.dgn
 PLOT DATE = 12/2/2010
 PLOT SCALE = 50,000' / 1"

CHRISTIAN-ROGE & ASSOCIATES, INC.
 ENGINEERS-PLANNERS-SURVEYORS
 211 WEST WACKER DRIVE
 CHICAGO, ILLINOIS 60606
 PHONE: (312)372-2023 FAX: (312)372-5274

DESIGNED - S.J.P.	REVISED -
DRAWN - B.K.	REVISED -
CHECKED - M.P.	REVISED -
DATE - DECEMBER 3, 2010	REVISED -

**STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION**

**EROSION AND SEDIMENT CONTROL PLAN - STAGE I
 IL. RTE. 56**

SCALE: 1" = 50' SHEET NO. 4 OF 6 SHEETS STA. 174+00 TO STA. 204+00

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS NO.	SHEET NO.
365	(58&59) WRS-3	DuPAGE	466	65
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT			CONTRACT NO. 62420	

CONSTRUCTION LEGEND

- WORK ZONE
- CONSTRUCTION LIMITS

NOTE: TEMPORARY DITCH CHECKS SHALL BE INSTALLED AT 100' INTERVALS AND PROVIDE A ONE FOOT DEPTH UNLESS OTHERWISE NOTED.

NOTE: INSTALL 13 INLET FILTERS THIS SHEET.

EROSION CONTROL LEGEND

- PERIMETER EROSION BARRIER
- PERIMETER EROSION BARRIER, SPECIAL
- INLET AND PIPE PROTECTION OR HEADWALL PROTECTION
- TEMPORARY DITCH CHECK (SEE NOTE)
- RIPRAP
- ROCK CHECK DAM
- SEDIMENT BASIN (50' x 10' x 1' DEPTH)
- TURF REINFORCEMENT MAT

THE CONTRACTOR SHALL PREPARE AN IN-STREAM WORK PLAN THAT IS IN ACCORDANCE WITH THE REQUIREMENTS OF THE SWPPP, 401 AND 404 PERMITS. ALL EROSION AND SEDIMENT CONTROL, COFFERDAMS, WORK PADS AND ANY WORK REQUIRED BY THE CONTRACTOR'S OPERATION WILL BE INCLUDED IN THE COST OF "UNDERWATER STRUCTURE EXCAVATION PROTECTION - LOCATION 1".