

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

WESTBOUND ROADWAY

CL BEAM 4

CL BEAM 5

CL BEAM 6

LOCATION	STATION	OFFSET	THEORETICAL GRADE ELEVATIONS	THEORETICAL GRADE ELEVATIONS ADJUSTED FOR DEAD LOAD DEFLECTIONS	LOCATION	STATION	OFFSET	THEORETICAL GRADE ELEVATIONS	THEORETICAL GRADE ELEVATIONS ADJUSTED FOR DEAD LOAD DEFLECTIONS	LOCATION	STATION	OFFSET	THEORETICAL GRADE ELEVATIONS	THEORETICAL GRADE ELEVATIONS ADJUSTED FOR DEAD LOAD DEFLECTIONS
BACK OF WEST ABUT.	191+31.40	-41.29	705.08	705.08	BACK OF WEST ABUT.	191+35.08	-34.95	705.18	705.18	BACK OF WEST ABUT.	191+38.76	-28.60	705.28	705.28
CL WEST ABUT.	191+32.84	-41.32	705.06	705.06	CL WEST ABUT.	191+36.52	-34.98	705.17	705.17	CL WEST ABUT.	191+40.19	-28.63	705.27	705.27
A	191+42.92	-41.52	704.96	705.00	A	191+46.59	-35.17	705.06	705.10	A	191+50.25	-28.82	705.16	705.21
B	191+53.00	-41.70	704.85	704.93	B	191+56.66	-35.34	704.96	705.04	B	191+60.31	-28.98	705.06	705.14
C	191+63.08	-41.86	704.75	704.85	C	191+66.73	-35.50	704.85	704.96	C	191+70.36	-29.13	704.96	705.06
D	191+73.17	-42.00	704.64	704.77	D	191+76.80	-35.63	704.75	704.87	D	191+80.42	-29.25	704.85	704.98
E	191+83.25	-42.12	704.54	704.65	E	191+86.87	-35.74	704.65	704.75	E	191+90.48	-29.36	704.75	704.85
F	191+93.34	-42.22	704.44	704.52	F	191+96.94	-35.83	704.54	704.62	F	192+00.54	-29.44	704.65	704.73
G	192+03.42	-42.30	704.34	704.38	G	192+07.01	-35.90	704.44	704.48	G	192+10.60	-29.51	704.55	704.59
CL W BRG PIER	192+13.51	-42.36	704.23	704.23	CL W BRG PIER	192+17.09	-35.96	704.34	704.34	CL W BRG PIER	192+20.66	-29.55	704.44	704.44
CL PIER	192+14.51	-42.36	704.22	704.22	CL PIER	192+18.09	-35.96	704.33	704.33	CL PIER	192+21.66	-29.56	704.43	704.43
CL E BRG PIER	192+15.52	-42.37	704.21	704.21	CL E BRG PIER	192+19.10	-35.96	704.32	704.32	CL E BRG PIER	192+22.67	-29.56	704.42	704.42
H	192+25.61	-42.40	704.11	704.15	H	192+29.17	-35.99	704.22	704.26	H	192+32.73	-29.58	704.32	704.36
I	192+35.69	-42.42	704.01	704.09	I	192+39.25	-36.00	704.12	704.20	I	192+42.79	-29.58	704.22	704.30
J	192+45.78	-42.41	703.91	704.01	J	192+49.32	-35.99	704.02	704.12	J	192+52.85	-29.56	704.12	704.23
K	192+55.86	-42.39	703.81	703.93	K	192+59.39	-35.95	703.92	704.04	K	192+62.91	-29.52	704.02	704.15
L	192+65.95	-42.34	703.71	703.81	L	192+69.46	-35.90	703.82	703.92	L	192+72.97	-29.46	703.92	704.03
M	192+76.04	-42.27	703.61	703.69	M	192+79.53	-35.83	703.72	703.80	M	192+83.02	-29.38	703.82	703.90
N	192+86.12	-42.19	703.51	703.55	N	192+89.61	-35.74	703.62	703.66	N	192+93.08	-29.28	703.73	703.77
CL EAST ABUT.	192+96.20	-42.08	703.41	703.41	CL EAST ABUT.	192+99.68	-35.62	703.52	703.52	CL EAST ABUT.	193+03.14	-29.16	703.63	703.63
BACK OF EAST ABUT.	192+97.64	-42.06	703.40	703.40	BACK OF EAST ABUT.	193+01.11	-35.60	703.51	703.51	BACK OF EAST ABUT.	193+04.58	-29.14	703.61	703.61

TOP OF SLAB ELEVATIONS-III  
IL. ROUTE 56 OVER  
WEST BRANCH DUPAGE RIVER  
F.A.P. RTE. 365  
SECTION (58&59) WRS-3  
DuPAGE COUNTY  
STA. 192+38.00  
STRUCTURE NO. 022-2027

DESIGNED -
CHECKED -
DRAWN -
CHECKED -

**CR** CHRISTIAN-ROGE & ASSOCIATES, INC.  
ENGINEERS-PLANNERS-SURVEYORS  
211 WEST WACKER DRIVE  
CHICAGO, ILLINOIS 60606  
PHONE: (312)372-2023 FAX: (312)372-5274

SHEET NO. 56	F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
S43 SHEETS	365	(58&59) WRS-3	DUPAGE	466	212
			CONTRACT NO. 62420		
ILLINOIS FED. AID PROJECT					