

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

EASTBOUND ROADWAY

CL BEAM 16

CL BEAM 17

CL BEAM 18

LOCATION	STATION	OFFSET	THEORETICAL GRADE ELEVATIONS	THEORETICAL GRADE ELEVATIONS ADJUSTED FOR DEAD LOAD DEFLECTIONS	LOCATION	STATION	OFFSET	THEORETICAL GRADE ELEVATIONS	THEORETICAL GRADE ELEVATIONS ADJUSTED FOR DEAD LOAD DEFLECTIONS	LOCATION	STATION	OFFSET	THEORETICAL GRADE ELEVATIONS	THEORETICAL GRADE ELEVATIONS ADJUSTED FOR DEAD LOAD DEFLECTIONS
BACK OF WEST ABUT.	191+75.00	34.98	705.66	705.66	BACK OF WEST ABUT.	191+78.57	41.36	705.67	705.67	BACK OF WEST ABUT.	191+82.14	47.73	705.50	705.50
CL WEST ABUT.	191+76.42	34.97	705.65	705.65	CL WEST ABUT.	191+79.99	41.34	705.65	705.65	CL WEST ABUT.	191+83.55	47.72	705.49	705.49
A	191+86.35	34.85	705.54	705.59	A	191+89.90	41.23	705.55	705.60	A	191+93.46	47.62	705.39	705.43
B	191+96.28	34.76	705.44	705.52	B	191+99.82	41.15	705.46	705.54	B	192+03.36	47.54	705.29	705.37
C	192+06.21	34.69	705.34	705.45	C	192+09.74	41.08	705.36	705.46	C	192+13.27	47.48	705.20	705.30
D	192+16.14	34.63	705.24	705.37	D	192+19.66	41.03	705.26	705.39	D	192+23.17	47.44	705.10	705.22
E	192+26.07	34.60	705.14	705.25	E	192+29.58	41.01	705.16	705.27	E	192+33.08	47.42	705.00	705.10
F	192+36.00	34.58	705.04	705.12	F	192+39.50	41.00	705.06	705.14	F	192+42.98	47.42	704.90	704.98
G	192+45.93	34.59	704.94	704.98	G	192+49.42	41.01	704.96	705.01	G	192+52.89	47.44	704.80	704.84
CL W BRG PIER	192+55.86	34.62	704.84	704.84	CL W BRG PIER	192+59.33	41.05	704.86	704.86	CL W BRG PIER	192+62.80	47.48	704.70	704.70
CL PIER	192+56.86	34.62	704.83	704.83	CL PIER	192+60.33	41.05	704.85	704.85	CL PIER	192+63.79	47.48	704.69	704.69
CL E BRG PIER	192+57.85	34.62	704.82	704.82	CL E BRG PIER	192+61.32	41.05	704.84	704.84	CL E BRG PIER	192+64.78	47.49	704.68	704.68
H	192+67.78	34.67	704.73	704.77	H	192+71.24	41.11	704.74	704.79	H	192+74.68	47.55	704.58	704.62
I	192+77.71	34.74	704.63	704.71	I	192+81.15	41.19	704.64	704.72	I	192+84.59	47.64	704.48	704.56
J	192+87.64	34.83	704.53	704.63	J	192+91.07	41.28	704.54	704.65	J	192+94.49	47.74	704.38	704.48
K	192+97.57	34.94	704.43	704.56	K	193+00.99	41.40	704.44	704.57	K	193+04.40	47.86	704.28	704.40
L	193+07.50	35.07	704.34	704.44	L	193+10.91	41.54	704.34	704.44	L	193+14.30	48.00	704.18	704.28
M	193+17.43	35.22	704.24	704.32	M	193+20.82	41.69	704.24	704.32	M	193+24.21	48.17	704.07	704.15
N	193+27.36	35.39	704.15	704.19	N	193+30.74	41.87	704.13	704.18	N	193+34.11	48.35	703.97	704.01
CL EAST ABUT.	193+37.29	35.58	704.05	704.05	CL EAST ABUT.	193+40.65	42.06	704.03	704.03	CL EAST ABUT.	193+44.01	48.55	703.87	703.87
BACK OF EAST ABUT.	193+38.70	35.60	704.04	704.04	BACK OF EAST ABUT.	193+42.07	42.09	704.02	704.02	BACK OF EAST ABUT.	193+45.42	48.58	703.85	703.85

TOP OF SLAB ELEVATIONS-VIII
IL. ROUTE 56 OVER
WEST BRANCH DuPAGE RIVER
F.A.P. RTE. 365
SECTION (58&59) WRS-3
DuPAGE COUNTY
STA. 192+38.00
STRUCTURE NO. 022-2027

DESIGNED -
CHECKED -
DRAWN -
CHECKED -

CR & A
CHRISTIAN-ROGE & ASSOCIATES, INC.
ENGINEERS-PLANNERS-SURVEYORS
211 WEST WACKER DRIVE
CHICAGO, ILLINOIS 60606
PHONE: (312)372-2023 FAX: (312)372-5274

SHEET NO. S11	F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	365	(58&59) WRS-3	DuPAGE	466	217
S43 SHEETS	CONTRACT NO. 62420			ILLINOIS FED. AID PROJECT	