



**RESTORATION OF WORK AREA.**  
 RESTORATION OF THE TRAFFIC SIGNAL WORK AREA SHALL BE INCIDENTAL TO THE RELATED PAY ITEM SUCH AS FOUNDATION, CONDUIT, HANDHOLE, TRENCH AND BACKFILL, ETC., AND NO EXTRA COMPENSATION SHALL BE ALLOWED. ALL ROADWAY SURFACES SUCH AS SHOULDER, MEDIAN, SIDEWALKS, PAVEMENT, ETC., SHALL BE REPLACED IN KIND. ALL DAMAGE TO MOWED LAWNS SHALL BE REPLACED WITH AN APPROVED SALT TOLERANT SOD, AND ALL DAMAGE TO UNMOWED FIELDS SHALL BE SEEDED IN ACCORDANCE WITH STANDARD SPECIFICATIONS 252 AND 250 RESPECTIVELY.

FILE NAME = TS-13.dgn  
 PLOT DATE = 8/12/2018

**SPAAN Tech, Inc.**  
 311 S. Wacker Drive, Suite 2400 Chicago, IL 60606  
 Phone: 312.277.8800 Fax: 312.277.8808 web: www.SpaanTech.com

DESIGNED - R.A.S.	REVISED -
DRAWN - R.A.S.	REVISED -
CHECKED - A.D.O.	REVISED -
DATE - AUGUST 2010	REVISED -

**STATE OF ILLINOIS**  
**DEPARTMENT OF TRANSPORTATION**

**TRAFFIC SIGNAL INSTALLATION PLAN**  
 IL ROUTE 56 (BUTTERFIELD ROAD) AND IL ROUTE 59 - SHEET 2 OF 2

SCALE: 1" = 20' SHEET NO. OF SHEETS STA. 117+70 TO STA. 125+35

F.A.P. RTE. 365	SECTION (58&59) WRS-3	COUNTY DuPAGE	TOTAL SHEETS 466	SHEET NO. 295
CONTRACT NO. 62420				TS-12
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				