



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

January 13, 2011

SUBJECT: FAP Route 353
Project ACNHF-0353 (019)
Section (12 & 13) WRS-4
Will County
Contract No. 62478
Item No. 135, January 21, 2011 Letting
Addendum B

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Replaced the Schedule of Prices.
2. Revised pages ii - vi of the Table of Contents to the Special Provisions.
3. Revised page 32 of the Special Provisions.
4. Added page 330 to the Special Provisions.
5. Revised sheet 11 of the Plans.

Prime contractors must utilize the enclosed material when preparing their bid and must include any Schedule of Prices changes in their bidding proposal.

Bidders using computer-generated bids are cautioned to reflect any and all Schedule of Prices changes, if involved, into their computer programs.

Very truly yours,

Scott E. Stitt, P.E.
Acting Engineer of Design and Environment

A handwritten signature in cursive script, reading "Ted B. Walschleger P.E." with a small "P.E." to the right.

By: Ted B. Walschleger, P. E.
Engineer of Project Management

cc: Diane O'Keefe, Region 1, District 1; Mike Renner; D. Carl Puzey;
Estimates

TBW:MS:jc

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 62478

State Job # - C-91-218-02
 PPS NBR - 1-71012-0600
 County Name - WILL - -
 Code - 197 - -
 District - 1 - -
 Section Number - (12&13)WRS-4

Project Number
 ACNHF-0353/019/

Route
 FAP 353

** REVISED : JANUARY 12, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
A2000120	T-ACERX FREM AB 2-1/2	EACH	28.000				
A2000174	T-ACERX FRM AB CL 10'	EACH	2.000				
A2001818	T-ACER SACR GM 2-1/4	EACH	11.000				
A2002376	T-BETULA NIGRA CL 12'	EACH	11.000				
A2002516	T-CARP CAROL 2	EACH	12.000				
A2002920	T-CELTIS OCCID 2-1/2	EACH	34.000				
A2004720	T-GLED TRI-I SM 2-1/2	EACH	42.000				
A2005020	T-GYMNOCLA DIO 2-1/2	EACH	47.000				
A2005122	T-KOEL PANICULAT CF 6	EACH	7.000				
A2005616	T-OSTRYA VIRG 2	EACH	18.000				
A2006270	T-POPUL TREM CL 8'	EACH	13.000				
A2006416	T-QUERCUS ALBA 2	EACH	3.000				
A2006516	T-QUERCUS BICOL 2	EACH	13.000				
A2006716	T-QUERCUS MACR 2	EACH	15.000				
A2007620	T-TAXODIUM DIS 2-1/2	EACH	8.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 62478

State Job # - C-91-218-02
 PPS NBR - 1-71012-0600
 County Name - WILL - -
 Code - 197 - -
 District - 1 - -
 Section Number - (12&13)WRS-4

Project Number
 ACNHF-0353/019/

Route
 FAP 353

** REVISED : JANUARY 12, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
A2007870	T-TILIA AMER CL 8'	EACH	12.000				
B2000668	T-AMELAN X GF SF 7'	EACH	43.000				
B2001168	T-CERCIS CAN CL 7'	EACH	37.000				
B2001668	T-CRATAE CRU-I SF 7'	EACH	39.000				
B2003274	T-MALUS DOLGO 2 BB	EACH	9.000				
B2003368	T-MALUS DW CL 7'	EACH	19.000				
B2003416	T-MALUS FLOR TF 2	EACH	24.000				
B2004150	T-MALUS PR TF 2	EACH	21.000				
B2005466	T-PRUN VR SH CL 6'	EACH	17.000				
B2005720	T-PYRUS C CH TF 2-1/2	EACH	12.000				
B2006168	T-SYRING PEK M CL 7'	EACH	48.000				
B2006268	T-SYRING RET CL 7'	EACH	91.000				
C2C00324	S-ARONIA MELAN IB 2'C	EACH	68.000				
C2C00524	S-ARONIA MELAN 2'C	EACH	30.000				
C2C01120	S-CEPHALAN OCCID 2' C	EACH	30.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER -

62478

State Job # - C-91-218-02
 PPS NBR - 1-71012-0600
 County Name - WILL - -
 Code - 197 - -
 District - 1 - -
 Section Number - (12&13)WRS-4

Project Number
 ACNHF-0353/019/

Route
 FAP 353

** REVISED : JANUARY 12, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
C2C01424	S-CORNUS AMOMUM 2'C	EACH	164.000				
C2C01536	S-CORNUS RACEMOSA 3'C	EACH	55.000				
C2C06212	S-RIBES AMER WBC 12WC	EACH	45.000				
C2C06220	S-RIBES MO GOOSB 12WC	EACH	28.000				
C2C09624	S-SAMBUCUS CANAD 2'C	EACH	101.000				
C2C11024	S-SYRINGA PAT MK 2'C	EACH	45.000				
C2002048	S-CORYLUS AMER 4'	EACH	13.000				
C2005812	S-RHUS AROMA GRO 2 BB	EACH	78.000				
C2011936	S-VIBURN DEN R S 3'	EACH	47.000				
C2012448	S-VIBURN LENT 4'	EACH	51.000				
C2012760	S-VIBURN PRUN 5'	EACH	29.000				
D2C00424	E-JUNIP CH PFITZ 2'C	EACH	15.000				
D2C01018	E-JUNIP HOR WIL 18C	EACH	30.000				
D2001972	E-PICEA GLAU DEN 6'	EACH	7.000				
D2002484	E-PINUS FLX VWP 7'	EACH	31.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 62478

State Job # - C-91-218-02
 PPS NBR - 1-71012-0600
 County Name - WILL - -
 Code - 197 - -
 District - 1 - -
 Section Number - (12&13)WRS-4

Project Number
 ACNHF-0353/019/

Route
 FAP 353

** REVISED : JANUARY 12, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
K0012990	P PL ORNAMENT T GAL P	UNIT	54.000				
K0013030	P PL WETLND 2X4 DPPLG	UNIT	97.000				
K0026610	TRANSP SALV TREES	EACH	12.000				
K0026850	PERENNIAL PLANT CARE	SQ YD	2,600.000				
K0029618	WEED CONT BROADLF TRF	GALLON	9.000				
K0029626	WEED CONTROL TEASEL	POUND	1.000				
K0029632	WEED CONT N SEL/N RES	GALLON	1.000				
K0029634	WEED CONTR PRE-EM GRN	POUND	191.000				
K0036120	MULCH PLACEMENT 4	SQ YD	1,797.000				
XX003037	D I FITTINGS & ACCESS	POUND	3,300.000				
XX004760	FIRE HYD W/A V VB & T	EACH	13.000				
XX004998	PVC WATER MAIN 6	FOOT	35.000				
XX007776	REM & ABAND VALVE BOX	EACH	5.000				
XX008196	TRENCH BACK WTRMN SPL	FOOT	330.000				
X0320816	SLEEPER SLAB	SQ YD	487.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 62478

State Job # - C-91-218-02
 PPS NBR - 1-71012-0600
 County Name - WILL - -
 Code - 197 - -
 District - 1 - -
 Section Number - (12&13)WRS-4

Project Number
 ACNHF-0353/019/

Route
 FAP 353

** REVISED : JANUARY 12, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
X0322959	WEED CONT NS/NR WETLN	GALLON	0.250				
X0322992	COARSE SAND PLACE 4	SQ YD	900.000				
X0323842	WM LINE STOP 12	EACH	1.000				
X0324752	STORM SEWER FILLED	CU YD	10.000				
X0324876	CONC BARRIER SPL	FOOT	60.000				
X0325034	MH TA 6D W/2 T1FOL RP	EACH	4.000				
X0325742	CONC FDN TY E SPL	FOOT	50.000				
X0326020	UTILITY PROTECTION PAD	SQ YD	1,603.000				
X0327022	WATER SERV LN 1 BORED	EACH	1.000				
X0327023	WATER SERV LN 1 OP CT	EACH	1.000				
X0327024	FIRE HYDNT REM & SALV	EACH	13.000				
X0327025	ABAN EX WM FILL CLSM	FOOT	6,000.000				
X0327029	REM SUBDIV MONUM SIGN	EACH	2.000				
X0327030	REMOVE DEC ARBOR	EACH	2.000				
X0327031	EXPLOR EXCAVATION	L SUM	1.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 62478

State Job # - C-91-218-02
 PPS NBR - 1-71012-0600
 County Name - WILL - -
 Code - 197 - -
 District - 1 - -
 Section Number - (12&13)WRS-4

Project Number
 ACNHF-0353/019/

Route
 FAP 353

** REVISED : JANUARY 12, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
X0327032	TEMP VIDEO DETECTION	EACH	1.000				
X0327033	REL EX VV CON PR P WM	L SUM	1.000				
X0327034	24DIA S SLVE 0.375 AG	FOOT	355.000				
X0351580	PVC WATER MAIN 12	FOOT	6,200.000				
X2070304	POROUS GRAN EMB SPEC	CU YD	142.000				
X2130010	EXPLOR TRENCH SPL	FOOT	500.000				
X2502024	SEEDING CL 4B MOD	ACRE	1.250				
X2800520	ABOVE GRADE INLT FLTR	EACH	88.000				
X4021000	TEMP ACCESS- PRIV ENT	EACH	50.000				
X4022000	TEMP ACCESS- COM ENT	EACH	47.000				
X4023000	TEMP ACCESS- ROAD	EACH	24.000				
X4201400	BR APPROACH PAVT SPL	SQ YD	363.000				
X4401198	HMA SURF REM VAR DP	SQ YD	3,654.000				
X4403800	MEDIAN SURF REMOVAL	SQ FT	40,379.000				
X5012502	CONC REM SPEC	CU YD	14.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 62478

State Job # - C-91-218-02
 PPS NBR - 1-71012-0600
 County Name - WILL - -
 Code - 197 - -
 District - 1 - -
 Section Number - (12&13)WRS-4

Project Number
 ACNHF-0353/019/

Route
 FAP 353

** REVISED : JANUARY 12, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
X5020501	UNWAT STR EX PROT L1	EACH	1.000				
X5020502	UNWAT STR EX PROT L2	EACH	1.000				
X5630006	CUT & CAP EX 6 WM	EACH	1.000				
X5630012	CUT & CAP EX 12 WM	EACH	10.000				
X6020088	MAN TA 8 DIA T1F CL	EACH	1.000				
X6020098	MAN TA 9 DIA T1F CL	EACH	1.000				
X6022900	CB RECONST SPL	EACH	49.000				
X6026050	SANITARY MANHOLE ADJ	EACH	17.000				
X6026800	INLETS RECONST SPL	EACH	1.000				
X6028000	MAN RECONST SPL	EACH	12.000				
X6700410	ENGR FLD OFF A SPL	CAL MO	24.000				
X7030104	WET TEM PM TAPE T3 4	FOOT	153,148.000				
X7030106	WET TEM PM TAPE T3 6	FOOT	7,171.000				
X7030112	WET TEM PM TAPE T3 12	FOOT	2,152.000				
X7030120	WET TEM PM TAP T3 L&S	SQ FT	1,416.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 62478

State Job # - C-91-218-02
 PPS NBR - 1-71012-0600
 County Name - WILL - -
 Code - 197 - -
 District - 1 - -
 Section Number - (12&13)WRS-4

Project Number
 ACNHF-0353/019/

Route
 FAP 353

** REVISED : JANUARY 12, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
X7030124	WET TEM PM TAPE T3 24	FOOT	1,901.000				
X8050015	SERV INSTALL POLE MT	EACH	4.000				
X8620020	UNINTER POWER SUPPLY	EACH	4.000				
X8710020	FOCC62.5/125 MM12SM12	FOOT	17,627.000				
X8730027	ELCBL C GROUND 6 1C	FOOT	2,877.000				
X8730250	ELCBL C 20 3C TW SH	FOOT	2,333.000				
X8772630	S MAA & P DMA 40 & 58	EACH	1.000				
Z0001050	AGG SUBGRADE 12	SQ YD	20,367.000				
Z0001055	AGG SUBGRADE 12 SPL	SQ YD	141,757.000				
Z0004552	APPROACH SLAB REM	SQ YD	39.000				
Z0007510	ENGINEERED BARRIER	SQ YD	125.000				
Z0007601	BLDG REMOV NO 1	L SUM	1.000				
Z0013798	CONSTRUCTION LAYOUT	L SUM	1.000				
Z0022800	FENCE REMOVAL	FOOT	817.000				
Z0026407	TEMP SHT PILING	SQ FT	7,297.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 62478

State Job # - C-91-218-02
 PPS NBR - 1-71012-0600
 County Name - WILL - -
 Code - 197 - -
 District - 1 - -
 Section Number - (12&13)WRS-4

Project Number
 ACNHF-0353/019/

Route
 FAP 353

** REVISED : JANUARY 12, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
Z0030250	IMP ATTN TEMP NRD TL3	EACH	12.000				
Z0030350	IMP ATTN REL NRD TL3	EACH	6.000				
Z0030850	TEMP INFO SIGNING	SQ FT	747.000				
Z0033028	MAINTAIN LIGHTING SYS	CAL MO	20.000				
Z0033046	RE-OPTIMIZE SIG SYS 2	EACH	1.000				
Z0033056	OPTIM TRAF SIGNAL SYS	EACH	1.000				
Z0033060	PREFORM DETECT LOOP	FOOT	3,680.000				
Z0033090	ELCBL C TRACER 14 1C	FOOT	17,538.000				
Z0042002	POROUS GRAN EMB SUBGR	CU YD	9,847.000				
Z0046304	P UNDR FOR STRUCT 4	FOOT	159.000				
Z0056608	STORM SEW WM REQ 12	FOOT	288.000				
Z0056610	STORM SEW WM REQ 15	FOOT	56.000				
Z0056612	STORM SEW WM REQ 18	FOOT	495.000				
Z0056614	STORM SEW WM REQ 21	FOOT	30.000				
Z0056616	STORM SEW WM REQ 24	FOOT	51.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 62478

State Job # - C-91-218-02
 PPS NBR - 1-71012-0600
 County Name - WILL - -
 Code - 197 - -
 District - 1 - -
 Section Number - (12&13)WRS-4

Project Number
 ACNHF-0353/019/

Route
 FAP 353

** REVISED : JANUARY 12, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
Z0056618	STORM SEW WM REQ 27	FOOT	69.000				
Z0062456	TEMP PAVEMENT	SQ YD	38,138.000				
Z0064800	SELECTIVE CLEARING	UNIT	19.000				
Z0073510	TEMP TR SIGNAL TIMING	EACH	2.000				
Z0076600	TRAINEES	HOUR	4,000.000		0.800		3,200.000
20100110	TREE REMOV 6-15	UNIT	1,241.000				
20100210	TREE REMOV OVER 15	UNIT	152.000				
20101000	TEMPORARY FENCE	FOOT	4,526.000				
20101100	TREE TRUNK PROTECTION	EACH	185.000				
20101200	TREE ROOT PRUNING	EACH	185.000				
20200100	EARTH EXCAVATION	CU YD	88,669.000				
20201200	REM & DISP UNS MATL	CU YD	51,577.000				
20300100	CHANNEL EXCAVATION	CU YD	1,179.000				
20400800	FURNISHED EXCAVATION	CU YD	45,511.000				
20800150	TRENCH BACKFILL	CU YD	7,461.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 62478

State Job # - C-91-218-02
 PPS NBR - 1-71012-0600
 County Name - WILL - -
 Code - 197 - -
 District - 1 - -
 Section Number - (12&13)WRS-4

Project Number
 ACNHF-0353/019/

Route
 FAP 353

** REVISED : JANUARY 12, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
21001000	GEOTECH FAB F/GR STAB	SQ YD	19,396.000				
21101615	TOPSOIL F & P 4	SQ YD	61,373.000				
21101630	TOPSOIL F & P 8	SQ YD	68,284.000				
21101685	TOPSOIL F & P 24	SQ YD	15,705.000				
21101815	COMPOST F & P 4	SQ YD	53,358.000				
25000210	SEEDING CL 2A	ACRE	19.500				
25000310	SEEDING CL 4	ACRE	10.250				
25000322	SEEDING CL 5A	ACRE	0.750				
25000400	NITROGEN FERT NUTR	POUND	3,245.000				
25000500	PHOSPHORUS FERT NUTR	POUND	3,245.000				
25000600	POTASSIUM FERT NUTR	POUND	3,245.000				
25000775	SELECT MOWING STAKES	EACH	373.000				
25100115	MULCH METHOD 2	ACRE	6.000				
25100630	EROSION CONTR BLANKET	SQ YD	613,157.000				
25200110	SODDING SALT TOLERANT	SQ YD	30,211.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER -

62478

State Job # - C-91-218-02
 PPS NBR - 1-71012-0600
 County Name - WILL - -
 Code - 197 - -
 District - 1 - -
 Section Number - (12&13)WRS-4

Project Number
 ACNHF-0353/019/

Route
 FAP 353

** REVISED : JANUARY 12, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
25200200	SUPPLE WATERING	UNIT	4,610.000				
28000250	TEMP EROS CONTR SEED	POUND	13,278.000				
28000305	TEMP DITCH CHECKS	FOOT	3,864.000				
28000400	PERIMETER EROS BAR	FOOT	18,020.000				
28000510	INLET FILTERS	EACH	382.000				
28100105	STONE RIPRAP CL A3	SQ YD	261.000				
28100107	STONE RIPRAP CL A4	SQ YD	1,061.000				
28200200	FILTER FABRIC	SQ YD	1,061.000				
31101400	SUB GRAN MAT B 6	SQ YD	22,262.000				
31200502	STAB SUBBASE HMA 4.5	SQ YD	141,757.000				
35101598	AGG BASE CSE B 3	SQ YD	4,218.000				
35101600	AGG BASE CSE B 4	SQ YD	564.000				
35101800	AGG BASE CSE B 6	SQ YD	415.000				
35501308	HMA BASE CSE 6	SQ YD	3,413.000				
35501316	HMA BASE CSE 8	SQ YD	7,660.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 62478

State Job # - C-91-218-02
 PPS NBR - 1-71012-0600
 County Name - WILL - -
 Code - 197 - -
 District - 1 - -
 Section Number - (12&13)WRS-4

Project Number
 ACNHF-0353/019/

Route
 FAP 353

** REVISED : JANUARY 12, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
35501324	HMA BASE CSE 10	SQ YD	565.000				
40600100	BIT MATLS PR CT	GALLON	7,211.000				
40600300	AGG PR CT	TON	20.000				
40600895	CONSTRUC TEST STRIP	EACH	4.000				
40600982	HMA SURF REM BUTT JT	SQ YD	58.000				
40603085	HMA BC IL-19.0 N70	TON	868.000				
40603310	HMA SC "C" N50	TON	2,716.000				
40603335	HMA SC "D" N50	TON	229.000				
40603340	HMA SC "D" N70	TON	309.000				
40701861	HMA PAVT FD 9	SQ YD	7,882.000				
40701881	HMA PAVT FD 10	SQ YD	1,882.000				
42000416	PCC PVT 9 3/4 JOINTD	SQ YD	135,293.000				
42001300	PROTECTIVE COAT	SQ YD	171,392.000				
42001420	BR APPR PVT CON (PCC)	SQ YD	1,206.000				
42300200	PCC DRIVEWAY PAVT 6	SQ YD	564.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 62478

State Job # - C-91-218-02
 PPS NBR - 1-71012-0600
 County Name - WILL - -
 Code - 197 - -
 District - 1 - -
 Section Number - (12&13)WRS-4

Project Number
 ACNHF-0353/019/

Route
 FAP 353

** REVISED : JANUARY 12, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
42300400	PCC DRIVEWAY PAVT 8	SQ YD	1,072.000				
42400200	PC CONC SIDEWALK 5	SQ FT	37,954.000				
42400800	DETECTABLE WARNINGS	SQ FT	392.000				
44000100	PAVEMENT REM	SQ YD	131,599.000				
44000155	HMA SURF REM 1 1/2	SQ YD	1,066.000				
44000200	DRIVE PAVEMENT REM	SQ YD	16,059.000				
44000300	CURB REM	FOOT	1,097.000				
44000500	COMB CURB GUTTER REM	FOOT	24,379.000				
44000600	SIDEWALK REM	SQ FT	13,428.000				
44003100	MEDIAN REMOVAL	SQ FT	12,059.000				
44004250	PAVED SHLD REMOVAL	SQ YD	7,742.000				
44201761	CL D PATCH T1 10	SQ YD	13.000				
44201765	CL D PATCH T2 10	SQ YD	824.000				
44201769	CL D PATCH T3 10	SQ YD	571.000				
44201771	CL D PATCH T4 10	SQ YD	843.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 62478

State Job # - C-91-218-02
 PPS NBR - 1-71012-0600
 County Name - WILL - -
 Code - 197 - -
 District - 1 - -
 Section Number - (12&13)WRS-4

Project Number
 ACNHF-0353/019/

Route
 FAP 353

** REVISED : JANUARY 12, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
44300100	AREA REF CR CON TREAT	SQ YD	1,068.000				
48101500	AGGREGATE SHLDS B 6	SQ YD	1,580.000				
48203021	HMA SHOULDERS 6	SQ YD	205.000				
48203029	HMA SHOULDERS 8	SQ YD	36.000				
50100100	REM EXIST STRUCT	EACH	1.000				
50102400	CONC REM	CU YD	127.300				
50104400	CONC HDWL REM	EACH	4.000				
50105220	PIPE CULVERT REMOV	FOOT	508.000				
50200100	STRUCTURE EXCAVATION	CU YD	217.000				
50300100	FLOOR DRAINS	EACH	21.000				
50300225	CONC STRUCT	CU YD	221.800				
50300255	CONC SUP-STR	CU YD	324.600				
50300260	BR DECK GROOVING	SQ YD	447.000				
50300280	CONCRETE ENCASEMENT	CU YD	16.800				
50300300	PROTECTIVE COAT	SQ YD	1,125.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 62478

State Job # - C-91-218-02
 PPS NBR - 1-71012-0600
 County Name - WILL - -
 Code - 197 - -
 District - 1 - -
 Section Number - (12&13)WRS-4

Project Number
 ACNHF-0353/019/

Route
 FAP 353

** REVISED : JANUARY 12, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
50500105	F & E STRUCT STEEL	L SUM	1.000				
50500505	STUD SHEAR CONNECTORS	EACH	4,428.000				
50800105	REINFORCEMENT BARS	POUND	16,140.000				
50800205	REINF BARS, EPOXY CTD	POUND	84,740.000				
50800515	BAR SPLICERS	EACH	122.000				
50901720	BICYCLE RAILING	FOOT	175.000				
50901750	PARAPET RAILING	FOOT	216.000				
51201610	FUR STL PILE HP12X63	FOOT	910.000				
51201700	FUR STL PILE HP12X74	FOOT	665.000				
51202305	DRIVING PILES	FOOT	1,575.000				
51203610	TEST PILE ST HP12X63	EACH	2.000				
51203700	TEST PILE ST HP12X74	EACH	1.000				
51204650	PILE SHOES	EACH	48.000				
51500100	NAME PLATES	EACH	2.000				
52000110	PREF JT STRIP SEAL	FOOT	224.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 62478

State Job # - C-91-218-02
 PPS NBR - 1-71012-0600
 County Name - WILL - -
 Code - 197 - -
 District - 1 - -
 Section Number - (12&13)WRS-4

Project Number
 ACNHF-0353/019/

Route
 FAP 353

** REVISED : JANUARY 12, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
52100020	ELAST BEARING ASSY T2	EACH	9.000				
52100520	ANCHOR BOLTS 1	EACH	72.000				
54001001	BOX CUL END SEC C1	EACH	1.000				
54001002	BOX CUL END SEC C2	EACH	2.000				
54001003	BOX CUL END SEC C3	EACH	3.000				
54001004	BOX CUL END SEC C4	EACH	2.000				
54002020	EXPAN BOLTS 3/4	EACH	33.000				
54003000	CONC BOX CUL	CU YD	58.400				
54010302	PCBC 3X2	FOOT	275.000				
54010402	PCBC 4X2	FOOT	1,145.000				
54010704	PCBC 7X4	FOOT	2,102.000				
54010903	PCBC 9X3	FOOT	118.000				
54010905	PCBC 9X5	FOOT	519.000				
54011005	PCBC 10X5	FOOT	620.000				
542A1081	P CUL CL A 2 36	FOOT	19.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 62478

State Job # - C-91-218-02
 PPS NBR - 1-71012-0600
 County Name - WILL - -
 Code - 197 - -
 District - 1 - -
 Section Number - (12&13)WRS-4

Project Number
 ACNHF-0353/019/

Route
 FAP 353

** REVISED : JANUARY 12, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
542A1093	P CUL CL A 2 48	FOOT	8.000				
542D5503	P CUL CL D 1 EQRS 48	FOOT	52.000				
5421A024	P CUL CL A 1 24 TEMP	FOOT	46.000				
5421A030	P CUL CL A 1 30 TEMP	FOOT	42.000				
5421D012	P CUL CL D 1 12 TEMP	FOOT	190.000				
5421D015	P CUL CL D 1 15 TEMP	FOOT	90.000				
5421D018	P CUL CL D 1 18 TEMP	FOOT	90.000				
5421D048	P CUL CL D 1 48 TEMP	FOOT	99.000				
54210184	PIPE ELBOW 15	EACH	1.000				
54213471	END SECTIONS 36	EACH	1.000				
54213483	END SECTIONS 48	EACH	2.000				
54213657	PRC FLAR END SEC 12	EACH	6.000				
54213660	PRC FLAR END SEC 15	EACH	63.000				
54213663	PRC FLAR END SEC 18	EACH	3.000				
54213666	PRC FLAR END SEC 21	EACH	1.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 62478

State Job # - C-91-218-02
 PPS NBR - 1-71012-0600
 County Name - WILL - -
 Code - 197 - -
 District - 1 - -
 Section Number - (12&13)WRS-4

Project Number
 ACNHF-0353/019/

Route
 FAP 353

** REVISED : JANUARY 12, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
54213669	PRC FLAR END SEC 24	EACH	8.000				
54213672	PRC FLAR END SEC 27	EACH	3.000				
54213678	PRC FLAR END SEC 33	EACH	2.000				
54213693	PRC FLAR END SEC 48	EACH	1.000				
5422A036	P CUL CL A 2 36 TEMP	FOOT	162.000				
54244405	FL INLT BX MED 542546	EACH	1.000				
54247130	GRATING-C FL END S 24	EACH	8.000				
54247140	GRATING-C FL END S 27	EACH	3.000				
54247153	GRATING-C FL END S 33	EACH	2.000				
54247190	GRATING-C FL END S 48	EACH	1.000				
550A0050	STORM SEW CL A 1 12	FOOT	1,581.000				
550A0070	STORM SEW CL A 1 15	FOOT	1,113.000				
550A0090	STORM SEW CL A 1 18	FOOT	55.000				
550A0120	STORM SEW CL A 1 24	FOOT	24.000				
550A0190	STORM SEW CL A 1 48	FOOT	20.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 62478

State Job # - C-91-218-02
 PPS NBR - 1-71012-0600
 County Name - WILL - -
 Code - 197 - -
 District - 1 - -
 Section Number - (12&13)WRS-4

Project Number
 ACNHF-0353/019/

Route
 FAP 353

** REVISED : JANUARY 12, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
550A0340	STORM SEW CL A 2 12	FOOT	10,687.000				
550A0360	STORM SEW CL A 2 15	FOOT	2,966.000				
550A0380	STORM SEW CL A 2 18	FOOT	2,494.000				
550A0400	STORM SEW CL A 2 21	FOOT	1,318.000				
550A0410	STORM SEW CL A 2 24	FOOT	2,527.000				
550A0420	STORM SEW CL A 2 27	FOOT	545.000				
550A0430	STORM SEW CL A 2 30	FOOT	1,378.000				
550A0440	STORM SEW CL A 2 33	FOOT	810.000				
550A0450	STORM SEW CL A 2 36	FOOT	60.000				
550A0470	STORM SEW CL A 2 42	FOOT	845.000				
550A0500	STORM SEW CL A 2 60	FOOT	189.000				
550A0730	STORM SEW CL A 3 30	FOOT	189.000				
55100200	STORM SEWER REM 6	FOOT	162.000				
55100300	STORM SEWER REM 8	FOOT	228.000				
55100400	STORM SEWER REM 10	FOOT	381.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 62478

State Job # - C-91-218-02
 PPS NBR - 1-71012-0600
 County Name - WILL - -
 Code - 197 - -
 District - 1 - -
 Section Number - (12&13)WRS-4

Project Number
 ACNHF-0353/019/

Route
 FAP 353

** REVISED : JANUARY 12, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
55100500	STORM SEWER REM 12	FOOT	2,845.000				
55100700	STORM SEWER REM 15	FOOT	2,586.000				
55100800	STORM SEWER REM 16	FOOT	48.000				
55100900	STORM SEWER REM 18	FOOT	1,830.000				
55101100	STORM SEWER REM 21	FOOT	383.000				
55101200	STORM SEWER REM 24	FOOT	787.000				
55101300	STORM SEWER REM 27	FOOT	77.000				
55101400	STORM SEWER REM 30	FOOT	58.000				
55101600	STORM SEWER REM 36	FOOT	202.000				
55101900	STORM SEWER REM 48	FOOT	104.000				
56105750	BUTTERFLY VALVES 12	EACH	8.000				
56108800	TAP VALVE & SLEEVE 6	EACH	1.000				
56109100	TAP VALVE & SLEEVE 12	EACH	7.000				
56400300	FIRE HYDNTS TO BE ADJ	EACH	9.000				
56500600	DOM WAT SER BOX ADJ	EACH	3.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 62478

State Job # - C-91-218-02
 PPS NBR - 1-71012-0600
 County Name - WILL - -
 Code - 197 - -
 District - 1 - -
 Section Number - (12&13)WRS-4

Project Number
 ACNHF-0353/019/

Route
 FAP 353

** REVISED : JANUARY 12, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
58700300	CONCRETE SEALER	SQ FT	514.000				
59100100	GEOCOMPOSITE WALL DR	SQ YD	72.000				
60100060	CONC HDWL FOR P DRAIN	EACH	1.000				
60107600	PIPE UNDERDRAINS 4	FOOT	5,400.000				
60200105	CB TA 4 DIA T1F OL	EACH	1.000				
60200805	CB TA 4 DIA T8G	EACH	16.000				
60201105	CB TA 4 DIA T11F&G	EACH	3.000				
60201110	CB TA 4 DIA T11V F&G	EACH	11.000				
60201340	CB TA 4 DIA T24F&G	EACH	182.000				
60204505	CB TA 5 DIA T8G	EACH	1.000				
60205040	CB TA 5 DIA T24F&G	EACH	2.000				
60207605	CB TC T8G	EACH	38.000				
60207915	CB TC T11V F&G	EACH	7.000				
60208240	CB TC T24F&G	EACH	93.000				
60218400	MAN TA 4 DIA T1F CL	EACH	57.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 62478

State Job # - C-91-218-02
 PPS NBR - 1-71012-0600
 County Name - WILL - -
 Code - 197 - -
 District - 1 - -
 Section Number - (12&13)WRS-4

Project Number
 ACNHF-0353/019/

Route
 FAP 353

** REVISED : JANUARY 12, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
60221100	MAN TA 5 DIA T1F CL	EACH	52.000				
60221700	MAN TA 5 DIA T8G	EACH	1.000				
60223800	MAN TA 6 DIA T1F CL	EACH	11.000				
60224446	MAN TA 7 DIA T1F CL	EACH	4.000				
60234200	INLETS TA T1F OL	EACH	15.000				
60236200	INLETS TA T8G	EACH	1.000				
60239714	INLETS TA SPL T24F&G	EACH	2.000				
60248000	JUNCTION CHAMBER N1	EACH	1.000				
60248100	JUNCTION CHAMBER N2	EACH	1.000				
60248200	JUNCTION CHAMBER N3	EACH	1.000				
60248300	JUNCTION CHAMBER N4	EACH	1.000				
60248400	JUNCTION CHAMBER N5	EACH	1.000				
60248500	JUNCTION CHAMBER N6	EACH	1.000				
60248600	JUNCTION CHAMBER N7	EACH	1.000				
60248610	JUNCTION CHAMBER N8	EACH	1.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 62478

State Job # - C-91-218-02
 PPS NBR - 1-71012-0600
 County Name - WILL - -
 Code - 197 - -
 District - 1 - -
 Section Number - (12&13)WRS-4

Project Number
 ACNHF-0353/019/

Route
 FAP 353

** REVISED : JANUARY 12, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
60248620	JUNCTION CHAMBER N9	EACH	1.000				
60248630	JUNCTION CHAMBER N10	EACH	1.000				
60248640	JUNCTION CHAMBER N11	EACH	1.000				
60248700	VV TA 4 DIA T1F CL	EACH	9.000				
60248900	VV TA 5 DIA T1F CL	EACH	7.000				
60250200	CB ADJUST	EACH	6.000				
60250400	CB ADJ NEW T1F OL	EACH	3.000				
60250500	CB ADJ NEW T1F CL	EACH	1.000				
60255500	MAN ADJUST	EACH	4.000				
60256400	MAN ADJ NEW T8G	EACH	2.000				
60260050	SAN MAN RECONST	EACH	2.000				
60260100	INLETS ADJUST	EACH	1.000				
60265700	VV ADJUST	EACH	19.000				
60266100	VV RECONST	EACH	1.000				
60266500	VV REMOVED	EACH	3.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 62478

State Job # - C-91-218-02
 PPS NBR - 1-71012-0600
 County Name - WILL - -
 Code - 197 - -
 District - 1 - -
 Section Number - (12&13)WRS-4

Project Number
 ACNHF-0353/019/

Route
 FAP 353

** REVISED : JANUARY 12, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
60266600	VALVE BOX ADJ	EACH	6.000				
60300305	FR & LIDS ADJUST	EACH	2.000				
60402210	GRATES T8	EACH	2.000				
60406100	FR & LIDS T1 CL	EACH	15.000				
60500040	REMOV MANHOLES	EACH	14.000				
60500050	REMOV CATCH BAS	EACH	49.000				
60500060	REMOV INLETS	EACH	37.000				
60600095	CLASS SI CONC OUTLET	CU YD	47.800				
60600605	CONC CURB TB	FOOT	777.000				
60603800	COMB CC&G TB6.12	FOOT	1,557.000				
60605000	COMB CC&G TB6.24	FOOT	59,964.000				
60605900	COMB CC&G TB9.12	FOOT	1,014.000				
60608521	COMB CC&G TM2.24	FOOT	1,612.000				
60618300	CONC MEDIAN SURF 4	SQ FT	15,308.000				
60619600	CONC MED TSB6.12	SQ FT	6,363.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 62478

State Job # - C-91-218-02
 PPS NBR - 1-71012-0600
 County Name - WILL - -
 Code - 197 - -
 District - 1 - -
 Section Number - (12&13)WRS-4

Project Number
 ACNHF-0353/019/

Route
 FAP 353

** REVISED : JANUARY 12, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
60620000	CONC MED TSB6.24	SQ FT	6,488.000				
60620200	CONC MED TSB6.24 MOD	SQ FT	28,590.000				
60624600	CORRUGATED MED	SQ FT	2,764.000				
63000001	SPBGR TY A 6FT POSTS	FOOT	500.000				
63100045	TRAF BAR TERM T2	EACH	2.000				
63100070	TRAF BAR TERM T5	EACH	2.000				
63100085	TRAF BAR TERM T6	EACH	2.000				
63100167	TR BAR TRM T1 SPL TAN	EACH	2.000				
63200310	GUARDRAIL REMOV	FOOT	2,659.000				
66900200	NON SPL WASTE DISPOSL	CU YD	2,100.000				
66900450	SPL WASTE PLNS/REPORT	L SUM	1.000				
66900530	SOIL DISPOSAL ANALY	EACH	11.000				
66901000	BACKFILL PLUGS	CU YD	15.000				
67100100	MOBILIZATION	L SUM	1.000				
70101800	TRAF CONT & PROT SPL	L SUM	1.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 62478

State Job # - C-91-218-02
 PPS NBR - 1-71012-0600
 County Name - WILL - -
 Code - 197 - -
 District - 1 - -
 Section Number - (12&13)WRS-4

Project Number
 ACNHF-0353/019/

Route
 FAP 353

** REVISED : JANUARY 12, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
70102550	TR CONT-PROT TEMP DET	EACH	12.000				
** 70103815	TR CONT SURVEILLANCE	CAL DA	500.000				
* DELETED							
70106800	CHANGEABLE MESSAGE SN	CAL MO	120.000				
70300100	SHORT TERM PAVT MKING	FOOT	6,901.000				
70300210	TEMP PVT MK LTR & SYM	SQ FT	400.000				
70300220	TEMP PVT MK LINE 4	FOOT	83,079.000				
70300240	TEMP PVT MK LINE 6	FOOT	1,150.000				
70300260	TEMP PVT MK LINE 12	FOOT	382.000				
70300280	TEMP PVT MK LINE 24	FOOT	475.000				
70301000	WORK ZONE PAVT MK REM	SQ FT	88,013.000				
70400100	TEMP CONC BARRIER	FOOT	2,025.000				
70400200	REL TEMP CONC BARRIER	FOOT	545.000				
72000100	SIGN PANEL T1	SQ FT	1,353.000				
72000200	SIGN PANEL T2	SQ FT	460.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 62478

State Job # - C-91-218-02
 PPS NBR - 1-71012-0600
 County Name - WILL - -
 Code - 197 - -
 District - 1 - -
 Section Number - (12&13)WRS-4

Project Number
 ACNHF-0353/019/

Route
 FAP 353

** REVISED : JANUARY 12, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
72400100	REMOV SIN PAN ASSY TA	EACH	136.000				
72400200	REMOV SIN PAN ASSY TB	EACH	7.000				
72400310	REMOV SIGN PANEL T1	SQ FT	9.000				
72400500	RELOC SIN PAN ASSY TA	EACH	6.000				
72800100	TELES STL SIN SUPPORT	FOOT	2,514.000				
72900100	METAL POST TY A	FOOT	322.000				
73100100	BASE TEL STL SIN SUPP	EACH	10.000				
78000100	THPL PVT MK LTR & SYM	SQ FT	255.000				
78000200	THPL PVT MK LINE 4	FOOT	16,981.000				
78000400	THPL PVT MK LINE 6	FOOT	650.000				
78000600	THPL PVT MK LINE 12	FOOT	530.000				
78000650	THPL PVT MK LINE 24	FOOT	42.000				
78001150	PAINT PVT MK LINE 12	FOOT	141.000				
78008200	POLYUREA PM T1 LTR-SY	SQ FT	3,706.000				
78008210	POLYUREA PM T1 LN 4	FOOT	17,781.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 62478

State Job # - C-91-218-02
 PPS NBR - 1-71012-0600
 County Name - WILL - -
 Code - 197 - -
 District - 1 - -
 Section Number - (12&13)WRS-4

Project Number
 ACNHF-0353/019/

Route
 FAP 353

** REVISED : JANUARY 12, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
78008230	POLYUREA PM T1 LN 6	FOOT	17,834.000				
78008250	POLYUREA PM T1 LN 12	FOOT	3,937.000				
78008270	POLYUREA PM T1 LN 24	FOOT	1,278.000				
78100100	RAISED REFL PAVT MKR	EACH	1,393.000				
78100200	TEMP RAIS REF PVT MKR	EACH	1,461.000				
78200410	GUARDRAIL MKR TYPE A	EACH	8.000				
78201000	TERMINAL MARKER - DA	EACH	2.000				
78300100	PAVT MARKING REMOVAL	SQ FT	12,610.000				
78300200	RAISED REF PVT MK REM	EACH	331.000				
81000600	CON T 2 GALVS	FOOT	14,806.000				
81000700	CON T 2 1/2 GALVS	FOOT	10.000				
81000800	CON T 3 GALVS	FOOT	306.000				
81001000	CON T 4 GALVS	FOOT	304.000				
81018500	CON P 2 GALVS	FOOT	2,871.000				
81018600	CON P 2 1/2 GALVS	FOOT	26.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 62478

State Job # - C-91-218-02
 PPS NBR - 1-71012-0600
 County Name - WILL - -
 Code - 197 - -
 District - 1 - -
 Section Number - (12&13)WRS-4

Project Number
 ACNHF-0353/019/

Route
 FAP 353

** REVISED : JANUARY 12, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
81018700	CON P 3 GALVS	FOOT	41.000				
81018900	CON P 4 GALVS	FOOT	1,905.000				
81100600	CON AT ST 2 GALVS	FOOT	188.000				
81300720	JUN BX SS AS 16X12X8	EACH	2.000				
81400100	HANDHOLE	EACH	44.000				
81400200	HD HANDHOLE	EACH	14.000				
81400300	DBL HANDHOLE	EACH	7.000				
81603177	UD 3#8 #8G EPRRH1.25	FOOT	600.000				
81900200	TR & BKFIL F ELECT WK	FOOT	15,464.000				
85000200	MAIN EX TR SIG INSTAL	EACH	1.000				
85700205	FAC T4 CAB SPL	EACH	4.000				
86400100	TRANSCEIVER - FIB OPT	EACH	4.000				
87301215	ELCBL C SIGNAL 14 2C	FOOT	1,083.000				
87301225	ELCBL C SIGNAL 14 3C	FOOT	3,472.000				
87301245	ELCBL C SIGNAL 14 5C	FOOT	7,958.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 62478

State Job # - C-91-218-02
 PPS NBR - 1-71012-0600
 County Name - WILL - -
 Code - 197 - -
 District - 1 - -
 Section Number - (12&13)WRS-4

Project Number
 ACNHF-0353/019/

Route
 FAP 353

** REVISED : JANUARY 12, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
87301255	ELCBL C SIGNAL 14 7C	FOOT	5,668.000				
87301305	ELCBL C LEAD 14 1PR	FOOT	13,026.000				
87301805	ELCBL C SERV 6 2C	FOOT	130.000				
87502440	TS POST GALVS 10	EACH	2.000				
87502500	TS POST GALVS 16	EACH	2.000				
87700160	S MAA & P 24	EACH	1.000				
87700200	S MAA & P 32	EACH	1.000				
87700210	S MAA & P 34	EACH	1.000				
87700220	S MAA & P 36	EACH	1.000				
87700270	S MAA & P 46	EACH	1.000				
87700280	S MAA & P 48	EACH	3.000				
87700290	S MAA & P 50	EACH	1.000				
87700300	S MAA & P 52	EACH	2.000				
87700310	S MAA & P 54	EACH	1.000				
87700340	S MAA & P 58	EACH	2.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 62478

State Job # - C-91-218-02
 PPS NBR - 1-71012-0600
 County Name - WILL - -
 Code - 197 - -
 District - 1 - -
 Section Number - (12&13)WRS-4

Project Number
 ACNHF-0353/019/

Route
 FAP 353

** REVISED : JANUARY 12, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
87700400	S MAA & P 60	EACH	1.000				
87702581	S MAA & P DMA 36 & 64	EACH	1.000				
87800100	CONC FDN TY A	FOOT	16.000				
87800150	CONC FDN TY C	FOOT	16.000				
87800400	CONC FDN TY E 30D	FOOT	60.000				
87800415	CONC FDN TY E 36D	FOOT	116.000				
87800420	CONC FDN TY E 42D	FOOT	63.000				
87900200	DRILL EX HANDHOLE	EACH	2.000				
88030020	SH LED 1F 3S MAM	EACH	30.000				
88030050	SH LED 1F 3S BM	EACH	2.000				
88030100	SH LED 1F 5S BM	EACH	8.000				
88030110	SH LED 1F 5S MAM	EACH	17.000				
88030240	SH LED 2F 1-3 1-5 BM	EACH	1.000				
88102717	PED SH LED 1F BM CDT	EACH	8.000				
88200210	TS BACKPLATE LOU ALUM	EACH	47.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 62478

State Job # - C-91-218-02
 PPS NBR - 1-71012-0600
 County Name - WILL - -
 Code - 197 - -
 District - 1 - -
 Section Number - (12&13)WRS-4

Project Number
 ACNHF-0353/019/

Route
 FAP 353

** REVISED : JANUARY 12, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
88500100	INDUCTIVE LOOP DETECT	EACH	45.000				
88700200	LIGHT DETECTOR	EACH	10.000				
88700300	LIGHT DETECTOR AMP	EACH	4.000				
88800100	PED PUSH-BUTTON	EACH	8.000				
89000100	TEMP TR SIG INSTALL	EACH	1.000				
89502205	MOD EX CONTR SPL	EACH	2.000				
89502300	REM ELCBL FR CON	FOOT	600.000				
89502375	REMOV EX TS EQUIP	EACH	2.000				
89502380	REMOV EX HANDHOLE	EACH	19.000				
89502385	REMOV EX CONC FDN	EACH	14.000				

TRAFFIC CONTROL AND PROTECTION FOR TEMPORARY DETOUR 32

TRAFFIC CONTROL SURVEILLANCE (BDE) 32

TEMPORARY RAISED REFLECTIVE PAVEMENT MARKER 33

AGGREGATE SUBGRADE, 12" 33

APPROACH SLAB REMOVAL 34

FENCE REMOVAL 35

TEMPORARY INFORMATION SIGNING 35

POROUS GRANULAR EMBANKMENT, SUBGRADE 36

STORM SEWER ADJACENT TO OR CROSSING WATER MAIN 38

TEMPORARY PAVEMENT 38

SELECTIVE CLEARING 39

PLANTING WOODY PLANTS 39

TRANSPLANTED SALVAGED TREES 40

PERENNIAL PLANT CARE 41

WEED CONTROL, BROADLEAF IN TURF 42

WEED CONTROL, TEASAL (POUND) 43

WEED CONTROL, NON-SELECTIVE AND NON-RESIDUAL 44

WEED CONTROL, PRE-EMERGENT GRANULAR HERBICIDE 46

GENERAL REQUIREMENTS FOR WEED CONTROL SPRAYING 46

SLEEPER SLAB 48

WEED CONTROL, NON-SELECTIVE AND NON-RESIDUAL (WETLAND) 48

COARSE SAND PLACEMENT 49

STORM SEWER TO BE FILLED 50

CONCRETE BARRIER (SPECIAL) 51

MANHOLES, TYPE A, 6'-DIAMETER, WITH 2 TYPE 1 FRAMES, CLOSED LID, RESTRICTOR PLATE 51

UTILITY PROTECTION PAD 51

REMOVE SUBDIVISION MONUMENT SIGN 52

REMOVE DECORATIVE ARBOR 52

EXPLORATORY EXCAVATION 52

EXPLORATION TRENCH, SPECIAL 53

SEEDING, CLASS 4B (MODIFIED) 53

AGGREGATE SURFACE COURSE FOR TEMPORARY ACCESS 54

BRIDGE APPROACH PAVEMENT (SPECIAL) 55

HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH 56

MEDIAN SURFACE REMOVAL 56

CONCRETE REMOVAL (SPECIAL) 56

MANHOLES, TYPE A, 8'-DIAMETER, TYPE 1 FRAME, CLOSED LID..... 57

MANHOLES, TYPE A, 9'-DIAMETER, TYPE 1 FRAME, CLOSED LID..... 57

CATCH BASINS TO BE RECONSTRUCTED (SPECIAL) 57

MANHOLES TO BE RECONSTRUCTED (SPECIAL)..... 57

INLETS TO BE RECONSTRUCTED (SPECIAL) 57

ENGINEER'S FIELD OFFICE TYPE A (SPECIAL) 58

TYPE III TEMPORARY TAPE FOR WET CONDITIONS 59

MULCH PLACEMENT FOR EXISTING WOODY PLANTS..... 59

JUNCTION CHAMBER 60

REMOVAL AND DISPOSAL OF REGULATED SUBSTANCES 61

TRAFFIC SIGNAL SPECIFICATIONS..... 64

FULL-ACTUATED CONTROLLER AND CABINET (SPECIAL) 111

MODIFY EXISTING CONTROLLER (SPECIAL) 112

CONCRETE FOUNDATION, TYPE E (SPECIAL)..... 112

TEMPORARY VIDEO DETECTION 112

GENERAL ELECTRICAL REQUIREMENTS..... 113

MAINTENANCE OF LIGHTING SYSTEMS..... 115

UNDERGROUND RACEWAYS..... 118

TRENCH AND BACKFILL FOR ELECTRICAL WORK 119

WIRE AND CABLE 119

UNIT DUCT 121

REMOVE ELECTRIC CABLE FROM CONDUIT 122

CLEANING AND PAINTING NEW METAL STRUCTURES 123

CLEANING AND PAINTING EXISTING STEEL STRUCTURES 130

TEMPORARY SHEET PILING..... 149

UNDERWATER STRUCTURE EXCAVATION PROTECTION 151

PIPE UNDERDRAINS FOR STRUCTURES 151

POROUS GRANULAR EMBANKMENT, SPECIAL..... 152

SLIPFORM PARAPET 152

DEMOLITION PLANS FOR REMOVAL OF EXISTING STRUCTURES 156

PILING..... 156

WATER MAIN SPECIAL PROVISIONS 158

WATER USE 158

WATER MAIN SHUT DOWN 159

VALVE VAULTS TO BE REMOVED 160

REMOVE AND ABANDON VALVE BOX..... 161

Revised 01/13/2011

DESCRIPTION OF PROCEDURE: 161

INTERRUPTION OF FLOW 162

LINESTOP FITTINGS: 12" 162

DIAMETER AND CONDITION OF MAINS 162

MATERIAL DRAWINGS 163

INSTALLATION OF LINESTOP FITTING 163

PRESSURE TEST 163

THRUST AND SUPPORT BLOCKING 163

CUTTING OPERATION 163

LINESTOP OPERATION 163

TRENCH BACKFILL, WATER MAIN, SPECIAL 164

PVC WATER MAIN 165

CUT AND CAP EXISTING WATER MAIN 166

STEEL SLEEVES – AUGERED 166

WATER SERVICE, (BORED) 167

WATER SERVICE, (OPEN CUT) 168

FIRE HYDRANT TO BE REMOVED & SALVAGED 168

ABANDON EXISTING WATER MAIN, FILL WITH CLSM 168

RELOCATE EXISTING VALVE VAULT AND CONNECT TO PROPOSED WATER MAIN 168

SPECIAL DESIGN PRECAST CONCRETE BOX CULVERTS 169

PERENNIAL PLANTS (MODIFIED) 169

CLEANING AND PAINTING CONTACT SURFACE AREAS OF EXISTING STEEL STRUCTURES 173

CLEANING AND PAINTING NEW METAL STRUCTURES 178

CLEANING AND PAINTING EXISTING STEEL STRUCTURES 185

TEMPORARY SHEET PILING 204

UNDERWATER STRUCTURE EXCAVATION PROTECTION 205

PIPE UNDERDRAINS FOR STRUCTURES 206

POROUS GRANULAR EMBANKMENT, SPECIAL 207

SLIPFORM PARAPET 207

DEMOLITION PLANS FOR REMOVAL OF EXISTING STRUCTURES 211

PILING 211

ABOVE GRADE INLET PROTECTION (BDE) 213

ALKALI-SILICA REACTION FOR CAST-IN-PLACE CONCRETE (BDE) 215

ALKALI-SILICA REACTION FOR PRECAST AND PRECAST PRESTRESSED CONCRETE (BDE) 217

APPROVAL OF PROPOSED BORROW AREAS, USE AREAS, AND/OR WASTE AREAS (BDE) 220

AUTOMATED FLAGGER ASSISTANCE DEVICES (BDE) 220

Revised 01/13/2011

CEMENT (BDE) 222

CERTIFICATION OF METAL FABRICATOR (BDE) 224

CONCRETE ADMIXTURES (BDE) 224

CONSTRUCTION AIR QUALITY – DIESEL RETROFIT (BDE)..... 227

CONSTRUCTION AIR QUALITY - DIESEL VEHICLE EMISSIONS CONTROL (BDE) 229

CONSTRUCTION AIR QUALITY - IDLING RESTRICTIONS (BDE)..... 230

DETERMINATION OF THICKNESS (BDE)..... 231

DISADVANTAGED BUSINESS ENTERPRISE PARTICIPATION (BDE) 241

EQUIPMENT RENTAL RATES (BDE)..... 249

FLAGGER AT SIDE ROADS AND ENTRANCES (BDE) 250

FRICTION AGGREGATE (BDE) 250

HMA - HAULING ON PARTIALLY COMPLETED FULL-DEPTH PAVEMENT (BDE) 252

HOT-MIX ASPHALT – ANTI-STRIPPING ADDITIVE (BDE) 253

HOT-MIX ASPHALT - DENSITY TESTING OF LONGITUDINAL JOINTS (BDE) 254

HOT-MIX ASPHALT – DROP-OFFS (BDE) 255

IMPACT ATTENUATORS, TEMPORARY (BDE) 255

LIQUIDATED DAMAGES (BDE)..... 257

METAL HARDWARE CAST INTO CONCRETE (BDE)..... 257

MULCH (BDE)..... 257

NATIONAL POLLUTANT DISCHARGE ELIMINATION SYSTEM / EROSION AND SEDIMENT CONTROL DEFICIENCY DEDUCTION (BDE) 260

PAVEMENT MARKING REMOVAL (BDE) 262

PAVEMENT PATCHING (BDE) 262

PAYMENTS TO SUBCONTRACTORS (BDE) 262

PIPE CULVERTS (BDE) 263

POST MOUNTING OF SIGNS (BDE)..... 267

PRECAST CONCRETE HANDLING HOLES (BDE) 267

RAISED REFLECTIVE PAVEMENT MARKERS (BDE) 268

SEEDING (BDE) 268

SELF-CONSOLIDATING CONCRETE FOR PRECAST PRODUCTS (BDE)..... 271

STORM SEWERS (BDE)..... 272

SUBCONTRACTOR MOBILIZATION PAYMENTS (BDE) 279

TEMPORARY EROSION CONTROL (BDE) 280

TRAFFIC BARRIER TERMINAL, TYPE 6 (BDE) 283

TRAFFIC CONTROL SURVEILLANCE (BDE)..... 283

TRAINING SPECIAL PROVISIONS 283

BITUMINOUS MATERIALS COST ADJUSTMENTS (BDE) (RETURN FORM WITH BID) 285
FUEL COST ADJUSTMENT (BDE) (RETURN FORM WITH BID) 288
STEEL COST ADJUSTMENT (BDE) (RETURN FORM WITH BID) 292
STORM WATER POLLUTION PREVENTION PLAN..... 296
SEDIMENT TRAP 307
IEPA PERMIT 313
CLEANING AND PAINTING CONTACT SURFACE AREAS OF EXISTING STEEL STRUCTURES..... 314
FREEZE-THAW AGGREGATES FOR CONCRETE SUPERSTRUCTURES POURED ON GRADE..... 318
STORM WATER POLLUTION PREVENTION PLAN..... 319
US ARMY CORPS OF ENGINEERS 404 PERMIT 330

Revised 01/13/2011

TRAFFIC CONTROL AND PROTECTION FOR TEMPORARY DETOUR

Effective: September 1, 1995

Revised: January 1, 2007

When traffic is to be directed over a detour route, the Contractor shall furnish, erect, maintain and remove all applicable traffic control devices along the detour route according to the details shown in the plans.

Basis of Payment. This work will be paid for at the contract unit price each for TRAFFIC CONTROL AND PROTECTION FOR TEMPORARY DETOUR.

TRAFFIC CONTROL SURVEILLANCE (BDE)

Effective: January 1, 2011

Revise the first sentence of the first paragraph of Article 701.10 of the Standard Specifications to read:

“When open holes, broken pavement, trenches over 3 in. (75 mm) deep and 4 in. (100 mm) wide or other hazards are present within 8 ft (2.4 m) of the edge of an open lane, the Contractor shall furnish traffic control surveillance during all hours when the Contractor is not engaged in construction operations.”

Revised 01/13/2011

US ARMY CORPS OF ENGINEERS 404 PERMIT

This project requires a US Army Corps of Engineers 404 permit. The permit issued to the Department does not cover in stream work by the contractor; therefore after award, the contractor will need to coordinate and have his work plan approved by the Corps. Guidelines on acceptable in stream work techniques can be found on the Corps website <http://www.lrc.usace.army.mil/>