

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
353	(12&13)WRS-4	WILL	608	4
STA.		TO STA.		
FED. ROAD DIST. NO. 1		ILLINOIS	FED. AID PROJECT	

URBAN

FUNDING BREAKDOWN		80% FED 20% STATE	80% STATE 20% FPDWC	80% STATE 20% VOF	80% STATE 20% VOF	80% FED 20% STATE	80% FED 20% STATE	80% FED 20% STATE	80% FED 20% STATE	80% FED 20% STATE	80% FED 20% STATE	80% FED 20% STATE	100% VOF	80% FED 20% STATE	80% FED 13.3% STATE 6.7% VOF	80% FED 10% STATE 10% FT	80% FED 10% STATE 5% VOF 5% FT	80% FED 20% STATE	80% FED 20% STATE
LOCATION OF WORK		ROADWAY	BIKEPATH	BIKEPATH	SIDEWALK	SIDEWALK	HICKORY CREEK BRIDGE	BOX CULVERTS	LIGHTING	LANDSCAPING	WATERMAIN	WATERMAIN	TRAFFIC SIGNALS	TRAFFIC SIGNALS	TRAFFIC SIGNALS	TRAFFIC SIGNALS	TRAFFIC SIGNALS	TRAFFIC SIGNALS	INTERCONNECT
SUMMARY OF QUANTITIES																			
CODE NO.	PAY ITEM	UNIT	TOTAL	0003	0021	0021	0021	0021	0013	0040	0021	0031	0043	0043	0021	0021	0021	0021	0021
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	1,241	1,241															
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	152	152															
20101000	TEMPORARY FENCE	FOOT	4,526	4,526															
20101100	TREE TRUNK PROTECTION	EACH	185	185															
20101200	TREE ROOT PRUNING	EACH	185	185															
20200100	EARTH EXCAVATION	CU YD	88,669	88,669															
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	51,577	49,540						2,037									
20300100	CHANNEL EXCAVATION	CU YD	1,179	1,179															
20400800	FURNISHED EXCAVATION	CU YD	45,511	45,511															
20800150	TRENCH BACKFILL	CU YD	7,461	7,461															
21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	19,396	19,396															
● 21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	61,373	61,373															
● 21101630	TOPSOIL FURNISH AND PLACE, 8"	SQ YD	68,284	68,284															
● 21101685	TOPSOIL FURNISH AND PLACE, 24"	SQ YD	15,705	15,705															
● 21101815	COMPOST FURNISH AND PLACE, 4"	SQ YD	53,358	53,358															
● 25000210	SEEDING, CLASS 2A	ACRE	19.50	19.50															
● 25000310	SEEDING, CLASS 4	ACRE	10.25	10.25															
● 25000322	SEEDING, CLASS 5A	ACRE	0.75	0.75															
● 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	3,245	3,245															
● 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	3,245	3,245															
● 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	3,245	3,245															
● 25000775	SELECTIVE MOWING STAKES	EACH	373	373															
25100115	MULCH, METHOD 2	ACRE	6.00	6.00															
25100630	EROSION CONTROL BLANKET	SQ YD	613,157	613,157															
● 25200110	SODDING, SALT TOLERANT	SQ YD	30,211	30,211															
● 25200200	SUPPLEMENTAL WATERING	UNIT	4,610	4,610															
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	13,278	13,278															
28000305	TEMPORARY DITCH CHECKS	FOOT	3,864	3,864															
28000400	PERIMETER EROSION BARRIER	FOOT	18,020	18,020															
28000510	INLET FILTERS	EACH	382	382															

● INDICATES SPECIALTY ITEMS

LEGEND

VOF = VILLAGE OF FRANKFORT
 FPDWC = FOREST PRESERVE DISTRICT OF WILL COUNTY
 FT = FRANKFORT TOWNSHIP

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: VERT. _____
 HORIZ. _____
 DATE 6/11/2010

DRAWN BY JRR
 CHECKED BY JRV