

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
353	(12&13)WRS-4	WILL	608	6
STA.		TO STA.		
FED. ROAD DIST. NO. 1		ILLINOIS FED. AID PROJECT		

URBAN

SUMMARY OF QUANTITIES		FUNDING BREAKDOWN		80% FED 20% STATE	80% STATE 20% FPDWC	80% STATE 20% VOF	80% STATE 20% VOF	80% FED 20% STATE	80% FED 20% STATE	80% FED 20% STATE	80% FED 20% STATE	80% FED 20% STATE	80% FED 20% STATE	100% VOF	80% FED 20% STATE	80% FED 13.3% STATE 6.7% VOF	80% FED 10% STATE 10% FT	80% FED 10% STATE 5% VOF 5% FT	80% FED 20% STATE	80% FED 20% STATE	
		LOCATION OF WORK			STA. 500+85- STA. 539+79										US ROUTE 45	PFEIFFER ROAD	BOTH AVENUE	FRANKFORT SQUARE	HARLEM AVENUE	INTERCONNECT	
CODE NO.	PAY ITEM	UNIT	TOTAL	ROADWAY	BIKEPATH	BIKEPATH	SIDEWALK	SIDEWALK	HICKORY CREEK BRIDGE	BOX CULVERTS	LIGHTING	LANDSCAPING	WATERMAIN	WATERMAIN	TRAFFIC SIGNALS	TRAFFIC SIGNALS	TRAFFIC SIGNALS	TRAFFIC SIGNALS	TRAFFIC SIGNALS	TRAFFIC SIGNALS	
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	16,059	16,059																	
44000300	CURB REMOVAL	FOOT	1,097	1,097																	
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	24,379	24,379																	
44000600	SIDEWALK REMOVAL	SQ FT	13,428	11,179										2,249							
44003100	MEDIAN REMOVAL	SQ FT	12,059	12,059																	
44004250	PAVED SHOULDER REMOVAL	SQ YD	7,742	7,742																	
44201761	CLASS D PATCHES, TYPE I, 10 INCH	SQ YD	13	13																	
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SQ YD	824	824																	
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SQ YD	571	571																	
44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SQ YD	843	843																	
44300100	AREA REFLECTIVE CRACK CONTROL TREATMENT	SQ YD	1,068	1,068																	
48101500	AGGREGATE SHOULDERS, TYPE B 6"	SQ YD	1,580	1,580																	
48203021	HOT-MIX ASPHALT SHOULDERS, 6"	SQ YD	205	205																	
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	36	36																	
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1							1											
50102400	CONCRETE REMOVAL	CU YD	127.3						76.0	51.3											
50104400	CONCRETE HEADWALL REMOVAL	EACH	4	4																	
50105220	PIPE CULVERT REMOVAL	FOOT	508							508											
50200100	STRUCTURE EXCAVATION	CU YD	217						217												
50300100	FLOOR DRAINS	EACH	21						21												
50300225	CONCRETE STRUCTURES	CU YD	221.8						221.8												
50300255	CONCRETE SUPERSTRUCTURES	CU YD	324.6						324.6												
50300260	BRIDGE DECK GROOVING	SQ YD	447						447												
50300280	CONCRETE ENCASEMENT	CU YD	16.8						16.8												
50300300	PROTECTIVE COAT	SQ YD	1,125						1,125												
50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1						1												
50500505	STUD SHEAR CONNECTORS	EACH	4,428						4,428												
50800105	REINFORCEMENT BARS	POUND	16,140							16,140											
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	84,740						83,710	1,030											
50800515	BAR SPLICERS	EACH	122						122												
50901720	BICYCLE RAILING	FOOT	175						175												

● INDICATES SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: VERT. HORIZ. DATE 6/11/2010

DRAWN BY JRR CHECKED BY JRJ