

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
353	(12&13)WRS-4	WILL	608	18
STA.		TO STA.		
FED. ROAD DIST. NO. 1		ILLINOIS	FED. AID PROJECT	

URBAN

FUNDING BREAKDOWN		80% FED 20% STATE	80% STATE 20% FPDWC	80% STATE 20% VOF	80% STATE 20% VOF	80% FED 20% STATE	80% FED 20% STATE	80% FED 20% STATE	80% FED 20% STATE	80% FED 20% STATE	80% FED 20% STATE	80% FED 20% STATE	100% VOF	80% FED 20% STATE	80% FED 13.3% STATE 6.7% VOF	80% FED 10% STATE 10% FT	80% FED 10% STATE 5% VOF 5% FT	80% FED 20% STATE	80% FED 20% STATE	
LOCATION OF WORK			STA. 500+85- STA. 539+79											US ROUTE 45	PFEIFFER ROAD	80TH AVENUE	FRANKFORT SQUARE	HARLEM AVENUE	INTERCONNECT	
SUMMARY OF QUANTITIES		ROADWAY	BIKEPATH	BIKEPATH	SIDEWALK	SIDEWALK	HICKORY CREEK BRIDGE	BOX CULVERTS	LIGHTING	LANDSCAPING	WATERMAIN	WATERMAIN	TRAFFIC SIGNALS	TRAFFIC SIGNALS	TRAFFIC SIGNALS	TRAFFIC SIGNALS	TRAFFIC SIGNALS	TRAFFIC SIGNALS	TRAFFIC SIGNALS	
CODE NO.	PAY ITEM	UNIT	TOTAL	0003	0021	0021	0021	0021	0013	0040	0021	0031	0043	0043	0021	0021	0021	0021	0021	0021
● D2001972	EVERGREEN, PICEA GLAUCA DENSATA (BLACK HILLS SPRUCE), 6' HEIGHT, BALLED AND BURLAPPED	EACH	7									7								
● D2002484	EVERGREEN, PINUS FLEXILIS VANDERWOLF'S PYRAMID (VANDERWOLF'S PYRAMID LIMBER PINE), 7' HEIGHT, BALLED AND BURLAPPED	EACH	31									31								
● K0012990	PERENNIAL PLANTS, ORNAMENTAL TYPE, GALLON POT	UNIT	54									54								
● K0013030	PERENNIAL PLANT, WETLAND TYPE, 2" DIAMETER BY 4" DEEP PLUG	UNIT	97									97								
● K0026610	TRANSPLANTED SALVAGED TREES	EACH	12	12																
● K0026850	PERENNIAL PLANT CARE	SQ YD	2,600								2,600									
● K0029618	WEED CONTROL, BROADLEAF IN TURF	GALLON	9								9									
● K0029626	WEED CONTROL, TEASEL	POUND	1								1									
● K0029632	WEED CONTROL, NON-SELECTIVE AND NON-RESIDUAL	GALLON	1								1									
● K0029634	WEED CONTROL, PRE-EMERGENT GRANULAR HERBICIDE	POUND	191								191									
● XX003037	DUCTILE IRON FITTINGS AND ACCESSORIES	POUND	3,300										2,400	900						
● XX004760	FIRE HYDRANT WITH AUXILIARY VALVE, VALVE BOX AND TEE	EACH	13										13							
● XX004998	PVC WATER MAIN 6"	FOOT	35										35							
● XX007776	REMOVE AND ABANDON VALVE BOX	EACH	5										5							
● XX008196	TRENCH BACKFILL, WATERMAIN, SPECIAL	FOOT	330									310	20							
X0320816	SLEEPER SLAB	SQ YD	487	487																
● X0322959	WEED CONTROL, NON-SELECTIVE AND NON-RESIDUAL (WETLAND)	GALLON	0.25									0.25								
● X0322992	COARSE SAND PLACEMENT, 4"	SQ YD	900									900								
● X0323842	WATER MAIN LINE STOP 12"	EACH	1										1							
X0324752	STORM SEWER TO BE FILLED	CU YD	10	10																
X0324876	CONCRETE BARRIER (SPECIAL)	FOOT	60	60																
X0325034	MANHOLES, TYPE A, 6'-DIAMETER, WITH 2 TYPE 1 FRAME, OPEN LIDS, RESTRICTOR PLATE	EACH	4	4																
● X0325742	CONCRETE FOUNDATION, TYPE E (SPECIAL)	FOOT	50																50	
X0326020	UTILITY PROTECTION PAD	SQ YD	1,603	1,603																
● X0327022	WATER SERVICE LINE 1", (BORED)	EACH	1										1							
● X0327023	WATER SERVICE LINE 1", (OPEN CUT)	EACH	1										1							
● X0327024	FIRE HYDRANTS TO BE REMOVED & SALVAGED	EACH	13										13							
● X0327025	ABANDON EXISTING WATER MAIN, FILL WITH CLSM	FOOT	6,000										5,300	700						
X0327029	REMOVE SUBDIVISION MONUMENT SIGN	EACH	2	2																

● INDICATES SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: VERT. HORIZ. DATE 6/11/2010

DRAWN BY JRR CHECKED BY JRV